CITY WIDE HOME INSPECTORS

PRE-LISTING HOME INSPECTION REPORT



197 Lisa Cres, Vaughan, Ontario

Report Number :21070323Inspection Date:2021-07-23Prepared by:City Wide Home Inspectors
PO Box 325
Tottenham, Ontario, LOG 1W0Phone:(416)203-0333Toll Free :1-877-203-0474Website:www.citywidehomeinspectors.comInspector:Michael FournierEmail:info@citywidehomeinspectors.com

Copyright © 2021 2061490 Ontario Inc. o/a City Wide Home Inspectors

Subject Property: 197 Lisa Cres, Vaughan, Ontario

City Wide Home Inspectors PO Box 325 Tottenham, Ontario, LOG 1W0 Office: (416)203-0333 Toll free: 1-877-203-0474 info@citywidehomeinspectors.com www.citywidehomeinspectors.com



July 27, 2021

Inspection Address: 197 Lisa Cres, Vaughan, Ontario Report Number: 21070323

At your request, an inspection of the above property was performed on 2021-07-23. **City Wide Home Inspectors** is pleased to submit the enclosed report. This report is a professional opinion based on a visual inspection of the accessible components of the home. This report is not an exhaustive technical evaluation. An evaluation of this nature would cost many times more.

Please understand that there are limitations to this inspection. Many components of the home are not visible during the inspection and very little historical information is provided in advance of the inspection. While we can reduce your risk of purchasing a home, we cannot eliminate it, nor can we assume it. Even the most comprehensive inspection cannot be expected to reveal every condition you may consider significant to ownership. In addition to those improvements recommended in our report, we recommend that you budget for unexpected repairs. On average, we have found that setting aside roughly one percent of the value of the home on an annual basis is sufficient to cover unexpected repairs.

The Standards of Practice prohibits us from making any repairs or referring any contractors. We are not associated with any other party to the transaction of this property, except as may be disclosed to you.

The information provided in this report is solely for your use. **City Wide Home Inspectors** will not release a copy of this report without your written consent.

Thank you for selecting our company. We appreciate the opportunity to be of service. Should you have any questions about the general condition of the house in the future, we would be happy to answer these. There is no fee for this telephone or email consulting. Our fees are based on a single visit to the property. If additional visits are required for any reason, additional fees may be assessed.

Sincerely,

Michael Fournier, Owner City Wide Home Inspectors Certified Master Inspector, CMI Certified Mould Inspector, IAC2 Certified Commercial Property Inspector, CCPI Certified Infrared Camera Property Inspector, CICPI

Page 2

BUILDING DATA

Approximate Age:	30 to 50 yrs
Building Type:	Single Family Detached
Building Style:	Two Story
General Appearance:	Satisfactory
Main Entrance Faces:	For the sake of this report East
Weather Condition:	Clear
Temperature:	20 to 30 C
Ground cover:	Dry
Occupancy:	Vacant

This confidential report is prepared exclusively for Dave Elfassy Copyright © 2021 2061490 Ontario Inc. o/s *City Wide Home Inspectors*

REPORT LIMITATIONS

This report is intended only as a general guide to help the client make his own evaluation of the overall condition of the home, and is not intended to reflect the value of the premises, nor make any representation as to the advisability of purchase. The report expresses the personal opinions of the inspector, based upon his visual impressions of the conditions that existed at the time of the inspection only. The inspection and report are not intended to be technically exhaustive, or to imply that every component was inspected, or that every possible defect was discovered. No disassembly of equipment, opening of walls, moving of furniture, appliances or stored items, or excavation was performed. This inspection is a limited visual examination of the readily accessible systems and components of the home only.

This inspection is conducted in compliance with the standards of practice of the International Association of Certified Home Inspectors (Inter-NACHI), a copy of which is available at <u>www.citywidehomeinspectors.com/sop</u>.

Systems and conditions which are not within the scope of the building inspection include, but are not limited to: pools spas or their related equipment, formaldehyde, lead paint, asbestos, toxic or flammable materials, and other environmental hazards; pest infestation, playground equipment, efficiency measurement of insulation or heating and cooling equipment, internal or underground drainage or plumbing, any systems which are shut down or otherwise secured; water wells (water quality and quantity) zoning ordinances; intercom; security systems; heat sensors; central vacuum systems, cosmetics or building code conformity. Any general comments about these systems and conditions are informational only and are not within the scope of this inspection.

The inspection report should not be construed as a compliance inspection of any governmental or non-governmental codes or regulations. The report is not intended to be a warranty or guarantee of the present or future adequacy or performance of the structure, its systems, or their component parts. This report does not constitute any express or implied warranty of merchantability or fitness for use regarding the condition of the property and it should not be relied upon as such. Any opinions expressed regarding adequacy, capacity, or expected life of components are general estimates based on information about similar components and occasional wide variations are to be expected between such estimates and actual experience. We recommend that any deficiencies noted in this report be repaired or corrected after consultation with reputable qualified contractors. It is suggested that more than one quote be obtained before commencing with repairs.

The sellers' property information sheet (SPIS) may be referred to in this document. This item is a statement that is often completed by the seller regarding the condition of the subject property. The buyer is urged to obtain and review this document, if available, as it contains crucial information. Photographs, taken at the time of this inspection, are to be considered part of this inspection report.

We certify that our inspectors have no interest, present or contemplated, in this property or its improvement and no involvement with tradespeople or benefits derived from any sales or improvements. To the best of our knowledge and belief, all statements and information in this report are true and correct.

We assume no liability for the cost of repair or replacement of unreported defects or deficiencies either current or arising in the future. You agree that in all cases our liability shall be limited to liquidated damages in an amount not greater than the fee you paid us. You waive any claim for consequential, exemplary, special or incidental damages or for the loss of the use of the home/building. You acknowledge that the liquidated damages are not a penalty, but that we intend them to (i) reflect the fact that actual damages may be difficult and impractical to ascertain; (ii) allocate risk between us; and (iii) enable us to perform the inspection for the agreed upon fee.

Should any disagreement or dispute arise as a result of this inspection or report, it shall be decided by arbitration and shall be submitted for binding, non-appealable arbitration unless the parties mutually agree otherwise. In the event of a claim, the Client will allow City Wide Home Inspectors to inspect the claim prior to any repairs or waive the right to make the claim. Client agrees not to disturb or repair or have repaired anything which may constitute evidence relating to the complaint, except in the case of an emergency.

Report Table of Contents

BUILDING DATA	3
REPORT LIMITATIONS	4
SUMMARY*	6
GROUNDS	7
ROOF COVERING	B
CHIMNEY / GUTTERS / SIDING / TRIM	9
EXTERIOR / ELECTRICAL / AC / GARAGE10	D
KITCHEN1 [,]	1
BASEMENT KITCHEN	2
LAUNDRY	2
BATHROOMS1	3
INTERIOR ROOMS1	5
WINDOWS / FIREPLACES / ATTIC18	B
BASEMENT	9
PLUMBING	D
HEATING SYSTEM2 ²	1
COOLING SYSTEM	2
ELECTRICAL	2
PHOTOS	3
GENERAL REMARKS2	5

SUMMARY*

ITEMS NOT OPERATING

None

MAJOR CONCERNS

None

POTENTIAL SAFETY HAZARDS

DEFERRED COST ITEMS

Items that have reached or are reaching their normal life expectancy or show indications that they may require repair or replacement <u>anytime during the next five (5) years</u>.

Smoke detector over 5 years old

* Items listed in this report may inadvertently have been left off the Summary Sheet. Customer should read the entire report, including the Remarks.

DEFINITIONS

SATISFACTORY (Sat.) - Indicates the component is functionally consistent with its original purpose but may show signs of normal wear and tear and deterioration.

MARGINAL(Marg.) - Indicates the component will probably require repair or replacement anytime within five years.

POOR - Indicates the component will need repair or replacement now or in the very near future.

MAJOR CONCERNS - A system or component that is considered significantly deficient or is unsafe.

SAFETY HAZARD - Denotes a condition that is unsafe and in need of prompt attention.

		GROUNDS	5	
Service Walks		🗹 None	□ Public sidev	valk needs repair
	□ Concrete	□ Flagstone	□ Brick	□ Other
Condition:	□ Satisfactory	□ Marginal	□ Poor	🗆 Trip Hazard
	\Box Pitched towards home	\Box Settling cracks	□ Not visible	
Driveway		□ None		
	□ Concrete	🗹 Asphalt	□ Gravel	□ Other
Condition:	☑ Satisfactory	□ Marginal	□ Poor	🗆 Trip hazard
	\Box Fill cracks and seal	\Box Pitched towards home	□ Settling crack	\square Not visible
Patio/Lanai		☑ None		
	\Box Concrete \Box F	lagstone 🗆 Brick	□ Kool-De	
Condition:	□ Satisfactory	□ Marginal	\Box Poor	🗆 Trip Hazard
	□ Pitched towards home	e (See Remarks page)	□ Settling crack	\square Not visible
Deck		☑ None □ Wood		
	□ Treated	□ Painted/Stained	🗆 Railing/balus	sters recommended
Condition:	□ Satisfactory	□ Marginal	□ Poor	\Box Not visible
Deck/Patio/Por	ch Covers	☑ None □ Earth	to wood contact	□ Moisture/insect damage
Lacks:	□ Metal straps/bolts/nai	ls 🗆 Improp	per attachment to h	nouse
Porch (covered	entrance)	☑ None	🗆 Railing/bal	usters recommended
Support Pier:	□ Wood	□ Concrete	□ Other	□ Not visible
Condition:	□ Satisfactory	□ Marginal	□ Poor	
Floor:	□ Satisfactory	\Box Marginal	□ Poor	□ Safety Hazard
Balcony (2nd fl	oor platform)	☑ None □ Wood	d 🗆 Metal	□ Other
Railing:	□ Yes	\Box No	🗆 Railing/balus	sters recommended
Condition:	□ Satisfactory	\Box Marginal	□ Poor	□ Safety Hazard
Stoops/Steps		□ None	Uneven rise	rs 🗆 Safety Hazard
	☑ Concrete	□ Wood	□ Other	Railing recommended
Condition:	✓ Satisfactory	□ Marginal	□ Poor	□ Recommend baluster
	□ Cracked	□ Settled	□ Damaged wo	od
Fencing		□ None	□ Туре:	☑ Not evaluated
Landscaping Af	fecting Foundation	(See Remarks page)		
Negative grade at:		\Box North \Box South	☑ Satisfactory	
r (eguar e grade au	□ Recommend addition			window wells/covers
	Trim back trees/shrub			act/too close to soil
	□ Yard drains observed		\Box N/A	
Retaining Wall:		□ Yes	☑ No	
U	□ Concrete	□ Wood	□ Other	□ Safety Hazard
Visual Condition:		□ Marginal	□ Poor	e
Hose Bibs		☑ Yes	□ No	□ No anti-siphon valve
Operates:	☑ Yes	□ No	□ Not tested	\Box Not on
General Comm	ients			

Fencing is not part of a home inspection. General site drainage was properly sloping away from the house. Maintain a positive drainage slope away from the foundation.

ROOF COVERING

General Inform	nation					
Roof Visibility		All				
		-				
Inspected Fro	m	Ground with b	oinoculars			
Style of Roof						
	bination: 🗹 Gable] □ Hip	□ Mansard	□ Shed □ 1	Flat 🗆 Other	
	bination: 🗆 Cable	\square Medium		\Box Flat		
			_ ~r			
Roof Covering]	A	·	5 to 10 own own	
Type: Asphalt	Estimated Lay	ers: 1 layer	Approx	imate age of cover:	5 to 10 yrs yrs	
Ventilation Sys	stem					
Combination:	☑ Soffit	□ Ridge		□ Gable	🗹 Roof	
	□ Powered	□ Eaves		□ Other		
Flashing Mate	rial					
Combination:	Galv./Aluminum	☐ Asphalt	🗆 Lea	d 🗆 Rubb	er 🗆 Not v	isible
□ Copper		□ Other				
Valley Materia						
Combination:	☑ Galv./Aluminum	☐ Asphalt		□ Copper	□ N/A	
	\Box Not visible	□ Other				
Apparent Con	dition of the Following a	at Time of Inspe	ection (condi	tions reported refle	ect <u>visible</u> portio	n only)
Roof Covering		☑ Satisfac		□ Marginal	D Poor	
Condition:	□ Curling	□ Cupping		□ Missing tabs/sh		
	□ Moss Buildup	□ Nail Popp □ Other	oing	□ Ponding	🗆 Burn	Spots
	□ Exposed Felt					
Ventilation		(See Rema	rks page)	(See Attic page))	
Flashings		□ Not visi		atisfactory \Box	Marginal C] Poor
Tidshings	□ Rusted		end Sealing	Pulled away fro	U	
			Ű	•	•	
Valleys	□ Not visible	☐ ⊠ Satisfac □ N/A	tory	□ Marginal □ Rusted	D Poor	r
	□ Holes	$\Box \mathbf{N}/\mathbf{A}$	end Sealing			
			0			
Skylights		\Box Yes	🗹 No	□ Satisfactory	□ Marginal	□ Poor
Plumbing Ven	ts	☑ Yes	□ No	☑ Satisfactory	□ Marginal	□ Poor
				E Satisfactory		
General Comr	nents					

Roof was showing normal wear, but was in overall adequate condition.

CHIMNEY / C	GUTTERS /	SIDING /	TRIM
-------------	------------------	----------	------

Chimney(s) Viewed from: □ Roof Chase: □ Brick □ Stone Evidence of: □ Cr.	□ None □ Ladder at ☑ Metal acked chimney c	eaves □ Fram	s): Middle of the ro ☑ Ground	01	
Chase: Brick Stone	☑ Metal acked chimney o	□ Fram			
	acked chimney o			□ Stucco	
Evidence of:	•				
				\Box Loose brick	
	les in metal	□ Rust	\mathcal{O}		
Flue: \Box Tile \Box Me			\Box Not visibl	e	
Evidence of: \Box Sc.		□ Cracks	Creosote		
	ve flue(s) cleaned			ated (See Remarks page)	
□ Recommend cricket/saddle flashing		□ Spark arre	estor/rain cap recom	mended	
Gutters & Downspouts	□ None	(See Rem	arks page)		
□ Insides need to be cleaned	Ponding				
☑ Galvanized/Alum.	□ Copper		□ Vinyl	□ Other	
Condition: 🗹 Satisfactory	□ Marginal		D Poor	□ Rusting	
\Box Hole in main run	-	Leaking:	□ Corners	□ Joints	
Extension needed:	□ South □ East □ West				
Siding					
Material: Brick & Siding	-				
Condition: 🗹 Satisfactory	□ Marginal	□ Poor	□ Recomme	end repair/painting	
Window Frames					
Material: Vinyl	-				
Condition: 🗹 Satisfactory	□ Marginal		□ Poor		
□ Recommend paintin	g	🗆 Dam	aged wood		
Trim, Soffit, Fascia					
Trim Material: Metal	Condition: S	atisfactory			
Soffit Material: Metal	Condition: S	atisfactory			
Fascia Material: Metal	Condition: Satisfactory				
Caulking					
Condition: 🗹 Satisfactory	□ Marginal		□ Poor		
□ Recommend around		masonry ledg	ges/corners/utility per	netrations	
General Comments					

Gutters were in overall adequate condition. Siding appeared to be in overall adequate condition. Trim appeared to be intact and in overall maintained condition.

Subject Property: 197 Lisa Cres, Vaughan, Ontario

EXTERIOR / ELECTRICAL / AC / GARAGE

Exterior Wall C	Construction							
Construction Style	e: Wood frame	☑ Satis:	factory 🗆	Marginal	□ Poor			
Exterior Doors	;		🗹 Entr	rance (1);	Storm (2);	Patio (3)		
Weather stripping	: 🗹 Satisfactory		🗆 Marg	inal	D P	Poor		
Condition:	☑ Satisfactory		□ Marg	inal	□ P	oor		
Exterior Electr	ical Service							
	□ Overhead	🗹 Un	derground	Servi	ce drop:	🗆 Satisfa	ctory	□ Needs service
Exterior outlets:	🗹 Yes	🗆 No	•	Oper	ate:	🗹 Yes	•	🗆 No
Reverse polarity:	\Box Yes	🗹 No		Open	ground:	□ Yes		🗹 No
Overhead wires:	□ Low □	Less t	han 1 meter	from balc	ony/deck/wi	indow 🗆 Ex	tension con	rd/exposed Romex
Potential safety	hazard:	□ Ye	S	🗹 No) (See	e Remarks p	age)	
A/C Condenser/	Heat Pump		□ None	Approx	imate age: 7	to 12 yrs		
#1 Brand: Amer	rican Standard							Shutoff: No
Condition:	☑ Satisfactory	□ Ma	rginal	D Poor	□ Ruste	d/dirty	Level: 🗹	Yes 🗆 No
Garage								
Garage Type:	None							
General Comn	nents							

Doors were reviewed and found to be in working order. Lights appeared to be in normal condition: not all lights were tested.

				ГСПЕН					
Countertops			☑ Satis	factory		Marginal		D Poor	r
Cabinets									
Condition:	☑ Satisfactory		□ Marginal		□ Poor		□ Recommend repairs		repairs
Plumbing Cor	nments								
Faucet leaks:	□ Yes	🗹 No		Pipes leak/corro	ded:	□ Yes		🗹 No	
Drainage:	☑ Adequate	D Po	or	Water pressure:		☑ Adequat	te	□ Poor	
Walls & Ceilin	g								
Condition	☑ Satisfactory	□ Ma	rginal	□ Poor		□ Typical	cracks	□ Moist	ure stains
Heat Source F	Present		🗹 Yes	□ No					
			-						
Floor									
Condition	☑ Satisfactory	🗆 Ma	rginal	□ Poor		□ Sloping		🗆 Squea	ıks
Appliances			(See Re	emarks page)					
Dishwasher:	🗹 Yes	🗆 No		Operates :		🗹 Yes		🗆 No	\Box N/A
Range:	🗹 Yes	🗆 No		Operates :		🗹 Yes		🗆 No	\Box N/A
Oven:	☑ Yes	🗆 No		Operates:		🗹 Yes		🗆 No	□ N/A
Exhaust fan:	☑ Yes	🗆 No		Operates:		🗹 Yes		🗆 No	\Box N/A
Refrigerator:	🗹 Yes	🗆 No		Operates :		🗹 Yes		🗆 No	\Box N/A
Other:	\Box Yes	□ No		Operates:		\Box Yes		□ No	\Box N/A
Electrical									
Outlets present:	☑ Yes	🗆 No	-	Operates :		🗹 Yes		🗆 No	
GFCI protected:	🗹 Yes	🗹 No		Operates :		□ Yes		🗆 No (F	Remarks)
Open ground/rev	verse polarity with	in 1 me	ter of water:	\square Yes \square Sa	afety l	Hazard 🗹 🛛	No		·
General Com	ments:								

KITCHEN

Counter top has normal wear. Cabinets have normal wear. Water flow was normal with several fixtures operated at the same time. There were no visible active piping leaks at the time of the inspection. Drain lines had no visible leaks or signs of backup at the time of inspection. Outlets were randomly tested and had correct polarity, except as noted. 15 amp GFCI outlets present in the kitchen caution is advised not to use 2 major counter appliances in the same outlet to prevent tripping of the breaker.

BASEMENT KITCHEN

Countertops		☑ Satis	sfactory	□ Marginal	rginal 🗆 Poor		r	
Cabinets								
Condition:	☑ Satisfactory		🗆 Margi	nal 🗆] Poor		ommend r	repairs
Plumbing Con	nments							
Faucet leaks:	□ Yes	🗹 No		Pipes leak/corrode	d: 🗆 Yes		🗹 No	
Drainage:	🗹 Adequate	□ Poo	or	Water pressure:	🗹 Adequa	ate	D Poor	
Walls & Ceiling	9							
Condition	☑ Satisfactory	□ Ma	rginal	□ Poor	□ Typical	l cracks	□ Moist	ure stains
Heat Source P	resent		🗹 Yes	□ No				
F lass								
Floor Condition	☑ Satisfactory	□ Ma	rainal	□ Poor	Sloping	-	C Sauce	1.0
Condition			rginai		□ Sloping	\$	□ Squea	IKS
Appliances			(See Re	emarks page)				
Dishwasher:	\Box Yes	🗹 No		Operates :	🗹 Yes		🗆 No	\Box N/A
Range:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	□ N/A
Oven:	☑ Yes	🗆 No		Operates :	🗹 Yes		🗆 No	\Box N/A
Exhaust fan:	☑ Yes	🗆 No		Operates :	🗹 Yes		🗆 No	\Box N/A
Refrigerator:	☑ Yes	🗆 No		Operates :	☑ Yes		🗆 No	□ N/A
Other:	□ Yes	□ No		Operates:	\Box Yes		□ No	\Box N/A
Electrical								
Outlets present:	☑ Yes	□ No		Operates :	☑ Yes		□ No	
GFCI protected:	□ Yes	🗹 No		Operates:	\Box Yes		🗆 No (F	(Remarks
-	erse polarity with	in 1 me	ter of water:	1	ety Hazard 🛛	No	,	<i>,</i>
General Comn	nents:							

Counter top has normal wear. Cabinets have normal wear. Water flow was normal with several fixtures operated at the same time. There were no visible active piping leaks at the time of the inspection. Drain lines had no visible leaks or signs of backup at the time of inspection

LAUNDRY

Room Components						
Laundry sink:	\Box N/A	Faucet leaks:	□ Yes	🗹 No	Pipe leaks:	🗆 Yes 🗹 No
Cross connections:	\Box Yes	☑ None apparent	Heat source	ce present	t: 🗹 Yes	□ No
Room appears vented:	\Box Yes	🗹 No	□ Not vis	ible		
Dryer vented:	\Box N/A	🗹 Wall	Ceiling		\Box Not vented	
Electrical: Open ground	reverse pola	rity within 1 meter of wa	ater:	Yes 🗆 S	Safety Hazard	🗹 No
Appliances present:	🗹 Washer	🗹 Dryer	□ Water I	neater	□ Furnace	□ Other
Gas pipe:	⊠ N/A	Valve shutoff:	□ Yes	□ No	\Box Cap Needed	🗆 Safety Hazard
General Comments						

At the time of the inspection the laundry facilities were in satisfactory condition.

BATHROOMS										
Bath: Second	floor									
Sinks	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No				
Tubs	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No				
Showers	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No				
Toilet:	Bowl loose	□ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	□ No □ Cracked bowl □ Toilet leal					
Whirlpool:		□ Yes	🗹 No	<i>Operates</i> : \Box Yes	□ No					
Shower/Tub area	a:	🗹 Ceram	nic/Plastic	☐ Fiberglass	□ Masonite	□ Other				
	Condition:	🗹 Satisfa	actory	□ Marginal	□ Poor	□ Rotted floors				
	Caulk/Grouting	needed:	□ Yes	🗹 No	Where:					
Drainage:	☑ Satisfactory		🗆 Margii	nal	□ Poor					
Water flow:	☑ Satisfactory		🗆 Margii	nal	□ Poor					
Moisture stains p	present:	□ Walls	Ceiling	gs 🗹 No						
Outlets present:	🗹 Yes 🛛	No	GFCI prote	cted: 🗹 Yes 🗆 No) Operates: 🗹 Y	ĭes □No				
-	Open ground/rev	verse polari	ity within 1	meter of water:	🗆 Yes 🗹 No					
	Potential safety	hazards p	oresent:	□ Yes ☑ No (Se	e Remarks page)					
Heat source pres	ent:	Yes		□ No						
Exhaust fan:	🗹 Yes 🛛	No	Operates:	☑ Yes	□ No □ Nois	y .				
Door:	☑ Sat. □ Marg.	□ Poor	☐ Holes □	Does not latch \Box H	Hardware broken	None				
General Comr	nents									

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted.

Bath: Main floo	or							
Sinks	Faucet leaks:	□ Yes	🗹 No			Pipes leak:	□ Yes	🗹 No
Toilet:	Bowl loose	\Box Yes	🗹 No	Operates:	🗹 Yes	□ No □ Cracked	bowl 🗆 To	ilet leaks
Drainage:	☑ Satisfactory		□ Margina	al		□ Poor		
Water flow:	☑ Satisfactory		□ Margina	al		□ Poor		
Moisture stains p	resent: 🗆 Yes	□ Walls	Ceiling:	s 🗹 No				
Outlets present:	🗹 Yes 🛛 No	GFCI prot	ected:	□ Yes	🗹 No	Operates:	🗹 Yes	🗆 No
	Open ground/rev	erse polarit	y within 6'	of water:	□ Yes	☑ No		
	Potential safety	hazards pr	esent:	□ Yes	🗹 No	(See Remarks pa	ge)	
Heat source prese	ent:	🗹 Yes		🗆 No				
Exhaust fan:	\Box Yes \blacksquare	No O	perates:	□ Yes		□ No □ Nois	sy	
Windows:	☑ Sat. □ Marg.	□ Poor □	Cracked g	lass 🗆 Non	ie 🗆 Evid	lence of leaking ins	sulated glas	S
Door:	☑ Sat. □ Marg.	□ Poor □	Holes	Does not la	tch 🗆 H	Iardware broken	□ None	
General Comm	nents							

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted. Outlets within 3 feet of the sink should be considered for upgrading to GFCI protected outlets.

Bath: Basemer	nt						
Sinks	Faucet	leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Showers	Faucet	leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Toilet:	Bowl lo	ose	□ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	□ No □ Cracked	bowl 🛛 Toilet leaks
Shower area:	🗹 Cera	mic/Plast	ic	□ Fibergl	ass	□ Masonite	□ Other
	Conditi	on:	🗹 Satis	sfactory	□ Marginal	□ Poor	□ Rotted floors
	Caulk/C	Grouting r	needed:	\Box Yes	🗹 No	Where:	
Drainage:	🗹 Satis	factory		🗆 Margin	al	□ Poor	
Water flow:	🗹 Satis	factory		🗆 Margin	al	□ Poor	
Moisture stains p	resent:	□ Yes	□ Wal	ls 🛛 Ceiling	s 🗹 No		
Outlets present:	🗹 Yes		No	GFCI protec	ted: 🗹 Yes 🗆 No	Operates: 🗹	Yes 🗆 No
	Open g	round/rev	erse pol	arity within 1 r	neter of water:	🗆 Yes 🛛 No	
	Potenti	al safety	hazards	s present:	\Box Yes \blacksquare No (Se	e Remarks page)	
Heat source prese	ent:	\checkmark	Yes		🗆 No		
Exhaust fan:	🗹 Yes		No	Operates:	☑ Yes	\Box No \Box Nois	sy
Windows:	🗹 Sat.	\Box Marg.	D Poor	r 🛛 Cracked g	lass 🗆 None 🗆 Ev	idence of leaking in	sulated glass
Door:	☑ Sat.	\Box Marg.	□ Poo	r 🗆 Holes 🗆	Does not latch \Box I	Hardware broken	□ None
General Comm	General Comments						

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted.

INTERIOR ROOMS

Ν	Л.	Δ	S	т	F	R	В	F	D	R	n	n	N	Л

Location: Seco	nd floor								
Walls & Ceiling:	☑ Satisfac	tory	\Box M	arginal		□ Poor	□ Typical	Cracks	□ Holes
	Moisture s	tains:	\Box Ye	□ Yes		🗹 No			
Flooring:	☑ Satisfactory		\Box M	□ Marginal		□ Poor	\Box Squeaks \Box Slop		□ Slopes
Ceiling fan:	⊠ N/A		🗆 Sa	tisfactory		□ Marginal	□ Poor		-
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open grou	nd/reverse	polarity:	□Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🛛	Marg. 🛛	Poor 🗆 Cra	cked glass	□ None [□ Evidence of	leaking insu	lated glas	ss
Door:	🗹 Sat. 🛛	Marg. 🛛	Poor 🗆 Ho	les 🗆 Does	s not latch	1 🛛 Hardware	e broken 🛛	None	
Closet Doors: \square Sat. \square Marg. \square P			Poor 🗆 Ho	les 🗆 Miss	sing 🗆 T	racks broken	□ None		
General Comm	ents:								

At the time of the inspection the room was found to be in overall satisfactory condition.

BEDROOM #2

Location: Seco	nd floor								
Walls & Ceiling:	☑ Satisfac	tory		arginal		□ Poor	□ Typical (Cracks	□ Holes
	Moisture st	tains:	$\Box Y$	es		🗹 No			
Flooring:	☑ Satisfactory		\Box M	□ Marginal		□ Poor	Poor 🗆 Squeaks 🗆		□ Slopes
Ceiling fan:	⊠ N/A		🗆 Sa	atisfactory		□ Marginal			
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open group	nd/reverse	polarity:	□ Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🗆	Marg. 🛛	Poor 🗆 Cra	acked glass	□ None [□ Evidence of	leaking insu	lated glas	ss
Door:	☑ Sat. □	Marg. 🛛	Poor 🗆 Ho	les 🗆 Does	s not latch	1 🛛 Hardware	broken 🛛	None	
Closet Doors: ☑ Sat. □ Marg. □ Po				oles 🗆 Miss	sing 🗆 T	racks broken	□ None		
General Comments:									

At the time of the inspection the room was found to be in overall satisfactory condition.

BEDROOM #3

Location: Seco	ond floor								
Walls & Ceiling:	☑ Satisfa	ctory		arginal		□ Poor	□ Typical	Cracks	□ Holes
Moisture stains:		\Box Ye	□ Yes		🗹 No				
Flooring:	oring: 🗹 Satisfactory		\Box M	\Box Marginal		🗆 Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sa	tisfactory		🗆 Marginal		🗆 Poor	
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	\Box No
	Open grou	und/reverse	polarity:	\Box Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	ers missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🗆	Marg. 🗆	Poor Cr	acked glass	□ None	□ Evidence of	f leaking inst	ulated gla	ISS
Door:	🗹 Sat. 🗆	Marg. 🗆	Poor 🗆 He	oles 🛛 Doe	s not late	h 🛛 Hardwar	e broken 🗆] None	
Closet Doors: Ø Sat. □ Marg. □ P			Poor 🗆 H	oles 🛛 Mis	sing 🗆 🛛	Fracks broken	□ None		
General Comments:									

At the time of the inspection the room was found to be in overall satisfactory condition.

LIVING / DINING ROOM

Location: First	floor							
Walls & Ceiling:	✓ Satisfactory	□ Mar	ginal		□ Poor	□ Typical ●	Cracks	□ Holes
-	Moisture stains:	□ Yes	-		🗹 No			
Flooring:	✓ Satisfactory	🗆 Mar	ginal		🗆 Poor	□ Squeaks		□ Slopes
Ceiling fan:	☑ N/A	🗆 Sati	sfactory		□ Marginal		□ Poor	
Electrical:	Switches: ☑ Yes □	No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open ground/reverse po	olarity:	🗆 Yes	🗆 Safety	y Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹 Yes 🛛 Not vi	sible						
Windows:	☑ Sat. □ Marg. □ Po	oor 🗆 Crac	cked glass	□ Evide	nce of leaking	insulated gla	ass	
Door:	\Box Sat. \Box Marg. \Box Po	oor 🗆 Hol	les 🗆 Does	s not latch	n 🗆 Hardware	e broken 🗹	None	
General Comm	nents:							

At the time of the inspection the room was found to be in overall satisfactory condition.

Location: First	floor							
					Deen	□ T:1	Cue eles	
walls & Celling:	Walls & Ceiling: 🗹 Satisfactory		larginal		□ Poor	□ Typical	Cracks	\Box Holes
	Moisture stains:	$\Box Y$	es		🗹 No			
Flooring:	☑ Satisfactory	\Box M	□ Marginal		□ Poor	□ Squeaks □		□ Slopes
Ceiling fan:	⊠ N/A	\Box Sa	atisfactory		□ Marginal		🗆 Poor	
Electrical:	Switches: Zes	\Box No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	🗆 No
	Open ground/reverse	se polarity:	□Yes	□ Safet	ty Hazard	🗹 No	□ Cove	ers missing
Heat source prese	ent: 🗹 Yes 🗆 N	ot visible			-			-
Windows:	□ Sat. □ Marg. [□ Poor □ C	racked glas	s 🗆 Ević	lence of leakin	g insulated g	glass	
Door: Ø Sat. ☐ Marg. ☐ Poor ☐ Holes ☐ Does not latch ☐ Hardware broken ☐ None								

At the time of the inspection the room was found to be in overall satisfactory condition.

FAMILY ROOM

Location: First	floor						
Walls & Ceiling:	✓ Satisfactory	□ Marginal		□ Poor	□ Typical (Cracks	□ Holes
	Moisture stains:	□ Yes		🗹 No			
Flooring:	✓ Satisfactory	□ Marginal		🗆 Poor	□ Squeaks		□ Slopes
Ceiling fan:	☑ N/A	□ Satisfactory		🗆 Marginal		□ Poor	
Electrical:	Switches: Ø Yes □	No Outlets:	🗹 Yes	🗆 No	Operates:	🗹 Yes	□ No
	Open ground/reverse po	olarity: □Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹 Yes 🛛 Not vi	sible					
Windows:	☑ Sat. □ Marg. □ Po	oor 🛛 Cracked gla	ss 🗆 Evic	lence of leaking	g insulated g	lass	
Door:	\Box Sat. \Box Marg. \Box Po	oor \Box Holes \Box D	pes not late	ch 🛛 Hardwar	e broken	1 None	
General Comm	General Comments:						

At the time of the inspection the room was found to be in overall satisfactory condition.

BASEMENT I	ROOM							
Location: Base	ment							
Walls & Ceiling:	☑ Satisfactory	□ M	arginal		□ Poor	□ Typical	Cracks	□ Holes
	Moisture stains:	\Box Ye	es		🗹 No			
Flooring:	☑ Satisfactory	\Box M	arginal		🗆 Poor	□ Squeaks		□ Slopes
Ceiling fan:	⊠ N/A	🗆 Sa	tisfactory		□ Marginal		🗆 Poor	
Electrical:	Switches: Yes	🗆 No	Outlets:	🗹 Yes	🗆 No	Operates:	🗹 Yes	□ No
	Open ground/rever	se polarity:	□Yes	□ Safet	y Hazard	🗹 No	\Box Cove	ers missing
Heat source prese	ent: 🗹 Yes 🗆 N	ot visible						-
Windows:	☑ Sat. □ Marg. I	\Box Poor \Box C	racked glass	s 🗆 Evid	ence of leakin	g insulated g	lass	
Door:	Door: \Box Sat. \Box Marg. \Box Poor \Box Holes \Box Does not latch \Box Hardware broken \Box None							
General Comm	nents:							

At the time of the inspection the room was found to be in overall satisfactory condition.

WINDOWS / FIREPLACES / ATTIC

Interior Windows/Glass									
General condition:	☑ Satisfactory	\square Marginal	□ Poor	\Box Painted shut					
□ Hardware missing		ũ		Broken counter-balance mech.					
\Box Surface deterioration:	(See Remarks			er of windows operated					
Evidence of leaking insulat		\Box Yes \Box No	□ Not determin						
Safety glazing:	⊠ N/A	\Box Safety issue	Where:						
Security bars present:	\Box Yes	•		mechanism before moving in					
Fireplace		□None Location	(s): Family room						
	☑ Wood	□ Wood burner stove	•	70)					
	\Box Metal insert		Electric	ge)					
\Box Blower built-in	Operates: [
\Box Open joints or cracks in fi	*		D Pro fabricato	d panels damaged/worn					
Hearth: Satisfactory:	\square Yes	□ No		atisfactory \Box Loose					
□ Recommend having flue				□ Direct Vent					
Stairs		☑ Satisfactory	Marginal	\Box Poor \Box None					
Handrail:	☑ Satisfactory		\Box Poor	🗆 Safety Hazard					
Risers/Treads:	☑ Satisfactory	□ Marginal	□ Poor	□ Risers/treads uneven					
Smoke/CO Detectors		(See Remarks page)							
Present: 🗹 Yes	Present: If Yes INO Note: Working smoke detectors are required on all levels of a home. Working CO detectors are required on all levels of a home with sleeping								
U	hould be tested mor	nthly and batteries changed ser	ni annually. <mark>À</mark> ost batte	a all levels of a home with sleeping ery operated units should be replaced					
Attic									
Access: Access panel Ac	cess Location:	Bedroom closet Ins	pected from: Acce	ss panel					
Flooring: Comp	olete	□ Partial	🗹 None						
Insulation: Type: Fibergla	SS	Average thickness: 6 to	9 inches R	Rating: R28					
Installed	in: 🗹 Floor	r 🛛 Rafters	□ Walls	□ Not Visible					
Vent fans:	nt 🛛 Not t	ested Thermostat	controlled 🛛 Safe	ety Hazard					
Ventilation: Margina									
Roof structure: Wooden									
Roof sheathing: Plywood									
Roof Sheathing Condition:									
	∃Yes ☑No	Outside: \square Yes \square No	\Box Not visible	□ N/A (See Remarks page)					
Chimney chase: Satisfact	•								
Structural problems observed		\square No \square See commer	nts below						
Vapour barriers: \square Not v		□ Improperly installed							
□ Kraft			Remarks page)						
Electrical:	iunction hov(e)	a) 🗌 Uanduman i	viring	□ Visible knob-and-tube					
	Junction box(c	s) 🗆 Handyman v	winng						

Trusses showed no major defects or damage at the time of inspection. Roof sheathing, examined from the attic, showed no major defects or moisture damage. Insulation level is low by today's standards recommend upgrading the insulation level in the attic. Attic ventilation is marginal recommend improving the attic ventilation.

BASEMENT

(See Remarks page)

Stairs						
Condition:	☑ Satisfactor	у	🗹 Marginal	□ Poor	🗆 Safety Haz	zard
Handrail: 🗹 Yes	□ No Cor	ndition:	☑ Satisfactory	Marginal	□ Poor	
Headway over stairs:	☑ Satisfactor	у	Marginal	Department Poor		
Under carriage:	☑ Satisfactor	у	□ Marginal	□ Poor	□ Not visible	
Foundation						
Wall Material:	Poured Conc	rete				
Condition:	Satisfactory					
Foundation Cracks:		lone Vis	ible Visib	ble from: \Box Exter	rior 🗆 Interior	•
Movement apparent:	\Box Yes \blacksquare N					
Partially/Covered walls:	\square Yes \square N	0				
	Condition re	ported	above reflects <u>visi</u> l	ole portion only		
Floor			(See vapour bar	rier remarks)		
Material:	Concrete		(See vapour bar	fier remarks)		
Condition:	Satisfactory					
Seismic Bolts	~		Nat annlinghla			
Seismic Doits			Not applicable			
Basement Drainage						
Indication of moisture:	No					
Sump Pump:		imp Pun	np Operates: Not a	pplicable		
Floor drain(s) present:	Yes	ľ	r - r	II		
Drain Tile (See Remarks	page)	□P	almer valve present	□ Not Visible	(See Remar	ks page)
			r / A			
Girders (1), Columns (2)	☑ Steel	\Box N		□ Block		D Natariaih la
Conditions			□ Wood		Concrete	\Box Not visible
Condition:	☑ Satisfactor	y	□ Marginal	□ Poor	□ Stained/rus	ted
Joists /Trusses						
🗹 Joist 🛛 Trusses	🗆 I-Joist		□ Steel	🗹 Wood	□Concrete	□ Not visible
	$\Box 2x6$		☑ 2x8	$\Box 2x10$	$\Box 2x12$	
Sub Floor						
			ture stains/rotting			
	** Areas	around s	hower stalls, etc., as	s viewed from bas	sement or craw	l space
General Comments						

Foundation appeared to be in overall satisfactory condition. Foundation walls were covered/partially covered with paneling/drywall/insulation and were not visible. No representation can be made to the conditions of the covered/partially covered walls. Floor appeared to be in overall satisfactory condition. No active seepage visible at the time of the inspection. No representation can be made to future leaking of the basement walls. Basement stairs have an uneven rise, caution is advised while traveling the stairs.

PLUMBING									
Water Service		Shut off location:	Basement						
Water entry piping: Co	opper Water	lines: Copper							
	Lead (other than	solder joints):	🗆 Yes 🗹 No	□ Service entry	Unknown				
	Water flow:	☑ Satisfactory	□ Poor	Cross connection:	\Box Yes \Box No				
	Water pressure:	✓ Satisfactory	□ Poor □ Aboy	ve 80 psi (Needs eva	luation)				
	Pipes: Corroc	led 🗆 Leaking	□ Valves broker	n/missing 🛛 🗆 Di	ssimilar metal				
Drain/waste/vent pipe:	Plastic								
	Condition:	☑ Satisfactory	□ Marginal	□ Poor	□ Not visible				
	Waste discharge:	☑ Satisfactory	□ Slow drain						
Gas Lines	ines Dot visible Shutoff missing								
	□ Copper	□ Brass	☑ Black iron	□ Stainless steel	\Box CSST				
Water Heater									
Brand name: GSW									
Energy Source: Gas	Approx. age:1	1 yrs		Capacity: 50 gallo	n				
Rental Unit: Yes		Seismic restraints n	eeded: 🗹 N/A 🗆	Yes 🗆 No					
Relief valve:	🗹 Yes 🛛 No	Extension pr	oper: 🗹 Yes	□ No □ Miss	ing				
Vent pipe:	□ N/A ☑ Satisf	actory Improper	pitch 🗆 Rusted	🗆 Safety Hazard					
Water Softener		(Unit not evaluat	ted)						
	□Yes ☑ No	Plumbing hoc	oked up: 🗆 Yes	□No					
General Comments									

Overall the plumbing system, faucets, water pressure and drain rates were found to be in satisfactory condition at the time of the inspections.

HEATING SYSTEM

	n Devil alian an		1	2 / 1			
Fuel Shutoff for Building		Main fuel shutoff location: Outside at gas meter					
Forced Air Sys	tem	☑ Central Unit		Wall Furnace		□ Floor Furnace	
	Brand name: An	nerican Standard			Approximate age: 7 to 12 yrs		
Energy source:	Gas Furna	ce Efficiency:	: High Efficiency			·	
Hot air systems:		•	c i				
Heat exchanger:	Sealed unit, not visible View is extremely limited - See Remarks page about options					about options	
Distribution:	Metal Ducts Flue piping: Plastic					_	
Filter: Standard	Filter Condition: Sa	tisfactory					
Operated:	When turned on b	y thermostat:	: 🗹 Fired		□ Did not fire	2	
Operation:	Satisfactory: 🗹	Yes 🗆 No	□ Recommend	HVAC t	echnician exan	ine 🗆 Before closing	
Controls:	□ Disconnect		☑ Normal opera	ating and	d safety control	ls observed	
Heat pump:	\Box Aux. Elec.	□ Aux. Gas	□ Aux. geother	mal	🗹 N/A		
	Emergency heat t	ested:	\Box Yes \Box	No	☑ N/A		
Others		☑ N/A					
	□ Electric baseb	oard	□ Radiant ceiling	g cable	□ Gas space 1	neater	
	□ Radiant in floor	heating	□ Wood burnin	g stove	(See Remark	s page)	
General Comm	nents						

Furnace was in normal working order at the time of the inspection. Heat exchanger had limited visibility due to its high-efficiency design. Flue was drafting properly at the time of the inspection. Filter should be changed /cleaned on regular bases.

COOLING SYSTEM

System Components		□ None		Approximate age: 7 to 12 yrs		
Energy source: Electric	Central air: Air C	Cooled			11	0
Operated: Yes	Operation: Satisfactory					
Refrigerant lines:	Leak	Damaged		□ Insulation missing		☑ Satisfactory
Through wall unit(s):	☑ N/A	Operated:	□ Yes	□ No	□ Satisfactory	\Box Needs service
General Comments						

A/C unit was operating in satisfactory condition.

		ELECTR	ICAL				
Main Panel		Location: Basem	ent				
	Amps: 100 ampsVolts:120/240 voltsPanel Type: Breakers						
Appears grounded:	🗹 Yes 🛛 No	GFCI present:	🗆 Yes 🛛 No	Operates:	\Box Yes \Box No		
Main Wire:	Not visible						
Branch Wire:	Copper						
	\square Romex \square BX cable		Conduit	□ Knob & tube			
	Multiple tapping Branch wires undersized Federal Pacific panel (see Remarks)						
	□ Multiple tapping of main disconnect □ Safety Hazard						
	\Box Arc fault present <i>Operates</i> : \Box Yes \Box No \Box N/A (see Remarks)						
	□ Panel not acce	ssible \Box Not e	evaluated Reason:				
Electrical Fixtures							
A representative number	r of installed light	ng fixtures, switches,	and receptacles loca	ated inside the	house, garage, and		
exterior walls were test	ed and found to be		-				
	☑ Satisfactory	□ Marginal	□ Poor				
	□ Open grounds	□ Reverse polarity	GFCIs not oper	ating 🛛 Ungro	ounded 3-prong outlets		
	□ Solid conduct	or aluminum branch	wiring circuits	(See Rema	arks page)		
	□ Recommend a	licensed electrician	evaluate the servic	e			
General Comments:							

Panel size appeared to be compatible to service size. Branch breaker distribution appeared normal except for a double of breakers which are double tapped, have reviewed and corrected as necessary. No signs of overheating were evident at the time of the inspection. Outlets were randomly tested and had correct polarity, except as noted.

PHOTOS



Pic. 1: Front view



Pic. 4: AC unit 2012



Pic. 7: Attic – more insulation advised



Pic. 10: Bed 3



Pic. 13: Eating area



Pic. 16: Kitchen



Pic. 2: Roof covering



Pic. 5: Back vie



Pic. 8: Master bedroom



Pic. 11: Living room



Pic. 14: Family room



Pic. 17: Powder room



Pic. 3: Sings of warping of the roof sheathing due to lack of ventilation in the attic



Pic. 6: Attic



Pic. 9: Bed 2



Pic. 12: Dining room



Pic. 15: Kitchen



Pic. 18: Powder room



Pic. 19: Basement stairwell – stairs have an uneven rise



Pic. 22: Basement bath



Pic. 25: Gas furnace 2012



Pic. 20: Basement room



Pic. 23: Laundry



Pic. 26: 100 amp breaker panel



Pic. 21: Basement kitchen



Pic. 24: Rental hot water tank 2008

GENERAL REMARKS

List below are general remarks about the different areas and components of a home. These remarks are for general information purposes only and some of the information provided may not be specific to the home inspected.

GROUNDS REMARKS

Service Walks/Driveways

Spalling concrete cannot be patched with concrete because the new will not bond with the old. Water will freeze between the two layers, or the concrete will break up from movement or wear. Replacement of the damaged section is recommended. Walks or driveways that are close to the property should be properly pitched away to direct water away from the foundation. Asphalt driveways should be kept sealed and larger cracks filled so as to prevent damage from frost.

Patios that have settled towards the structure should be mudjacked or replaced to assure proper pitch. Improperly pitched patios are one source of wet basements.

Exterior Wood Surfaces

All surfaces of untreated wood need regular applications of paint or special chemicals to resist damage. Porch or deck columns and fence posts which are buried in the ground and made of untreated wood will become damaged within a year or two.

Decks should always be nailed with galvanized or aluminium nails. Decks that are not painted or stained should be treated with a water sealer.

Grading and Drainage

Any system of grading or landscaping that creates positive drainage (moving water away from the foundation walls) will help to keep a basement dry. Where negative grade exists and additional backfill is suggested, it may require digging out around the property to get a proper pitch. Dirt shall be approximately 15 cm below the bottom sill and should not touch wood surfaces.

Flower beds, loose mulched areas, railroad ties and other such landscaping items close to the foundation trap moisture and contribute to wet basements. To establish a positive grade, a proper slope away from the house is 2.5 cm per meter for approximately 1.5 to 2 meters. Recommend ground cover planting or grass to foundation.

Roof and Surface Water Control

Roof and surface water must be controlled to maintain a dry basement. This means keeping gutters cleaned out and aligned, extending downspouts, installing splash blocks, and building up the grade so that roof and surface water is diverted away from the building.

Window Wells

The amount of water which enters a window well from falling rain is generally slight, but water will accumulate in window wells if the yard is improperly graded. Plastic window well covers are useful in keeping out leaves and debris.

Retaining Walls

Retaining walls deteriorate because of excessive pressure build-up behind them, generally due to water accumulation. Often, conditions can be improved by excavating a trench behind the retaining wall and filling it with coarse gravel. Drain holes through the wall will then be able to relieve the water pressure.

Retaining walls sometime suffer from tree root pressure or from general movement of topsoil down the slope. Normally, these conditions require rebuilding the retaining wall.

Railings

It is recommended that railings be installed for any stairway over 3 steps and porches over 75 cm for safety reasons. Balusters for porches, balconies, and stairs should be close enough to assure children cannot squeeze through.

ROOF COVERING REMARKS

Valleys & Flashings

Valleys and flashings that are covered with shingles and/or tar or any other material are considered not visible and are not part of the inspection.

Stone Roofs - Coverings

This type of covering on a pitched roof requires ongoing annual maintenance. We recommend that a roofing contractor evaluate this type of roof. Infra-red photography is best used to determine areas of potential leaks.

Flat Roofs

Flat roofs are very vulnerable to leaking. It is very important to maintain proper drainage to prevent ponding of water. We recommend that a roofing contractor evaluate this type of roof.

ROOF TYPE	LIFE EXPECTANCY	SPECIAL REMARKS			
Asphalt Shingles	15-20 years	Used on nearly 80% of all residential roofs; requires little maintenance			
Asphalt 20-30 years Multi-Thickness Shingles*		Heavier and more durable than regular asphalt shingles			
Asphalt Interlocking Shingles*	15-25 years	Especially good in high-wind areas			
Asphalt Rolls	10 years	Used on low slope roofs			
Built-up Roofing	10-20 years	Used on low slope roofs; 2 to 3 times as costly as asphalt shingles			
Wood Shingles*	10-40 years ¹	Treat with preservative every 5 years to prevent decay			
Clay Tiles* Cement Tiles*	20 + years 20 + years	Durable, fireproof, but not watertight, requiring a good subsurface base			
Slate Shingles*	30-100 years ²	Extremely durable, but brittle and expensive			
Asbestos Cement Shingles*	30-75 years	Durable, but brittle and difficult to repair			
Metal Roofing	15-40 + years	Comes in sheets & shingles; should be well grounded for protection from lightning; certain metals must be painted			
Single Ply Membrane	15-25 years (mfgr's claim)	New material; not yet passed test of time			

* Not recommended for use on low slope roof ¹ Depending on local conditions and proper installation ² Depending on quality of slate

Roof covering should be visually checked in spring and fall for any visible missing shingles, damaged coverings or other defects. Before re-roofing, the underside of the roof structure and roof sheathing should be inspected to determine that the roof structure can support the additional weight of the shingles.

Wood shakes and shingles will vary in aging, due to quality of the material, installation, maintenance, and surrounding shade trees. Ventilation and drying of the wood material is critical in extending the life expectancy of the wood. Commercial preservatives are available on the market, which could be applied to wood to impede deterioration.

CHIMNEY / GUTTERS / SIDING / TRIM REMARKS

Chimneys

Chimneys built of masonry will eventually need tuck pointing. A cracked chimney top that allows water and carbonic acid to get behind the surface brick/stone will accelerate the deterioration. Moisture will also deteriorate the clay flue liner. Periodic chimney cleaning will keep you apprised of the chimney's condition. The flashing around the chimney may need resealing and should be inspected every year or two. Fireplace chimneys should be inspected and evaluated by a chimney professional before using. Chimneys must be adequate height for proper drafting. Spark arrestors are recommended for wood burning chimney and chimney caps for fossil fuels

Unlined Chimney - should be re-evaluated by a chimney technician.

Have flue cleaned and re-evaluated. The flue lining is covered with soot or creosote and no representation can be made as to the condition.

NOT EVALUATED- The flue was not evaluated due to inaccessibility such as roof pitch, cap, cleanout not accessible, etc.

Cricket Flashing

Small, sloped structure made of metal and designed to drain moisture away from a chimney. Crickets are usually placed at the back of a chimney.

Gutters and Downspouts

This is an extremely important element in basement dampness control. Keep gutters clean and downspout extensions in place (1.25 meters or more). Paint the inside of galvanized gutters, which will extend the life. Shortly after a rain or thaw in winter, look for leaks at seams in the gutters. These can be re-caulked before they cause damage to fascia or soffit boards. If no gutters exist, it is recommended that they be added.

Siding

Wood siding should not come in contact with the ground. The moisture will cause rotting to take place and can attract carpenter ants.

EIFS - This type of siding has experienced serious problems and requires a certified EIFS inspector to determine condition.

Brick and stone veneer must be monitored for loose or missing mortar. Some brick and stone are susceptible to spalling. This can be caused when moisture is trapped and a freeze/thaw situation occurs. There are products on the market that can be used to seal out the moisture. This holds true for brick and stone chimneys also.

Metal sidings will dent and scratch. Oxidation is a normal reaction in aluminum. There are good cleaners on the market and it is recommended that they be used occasionally. Metal siding can be painted.

Doors and Windows

These can waste an enormous amount of energy. Maintain the caulking around the frames on the exterior. Check for drafts in the winter and improve the worst offenders first. Windows that have leaky storm windows will usually have a lot of sweating. Likewise, well-sealed storms that sweat indicate a leaky window. It is the tighter unit that will sweat (unless the home has excess humidity to begin with.)

Wood that exhibits blistering or peeling paint should be examined for possible moisture sources: roof leaks, bad gutters, interior moisture from baths or laundry or from a poorly vented crawl space. Some paint problems have no logical explanation, but many are a symptom of an underlying problem. A freshly painted house may mask these symptoms, but after you have lived in the home for a year or two, look for localized paint blistering (peeling). It may be a clue.

New glazing will last longer if the raw wood is treated with boiled linseed oil prior to glazing. It prevents the wood from drawing the moisture out of the new glazing.

Caulking

Many different types of caulk are available on the market today. Check with a paint or hardware store for the kind of application you need.

EXTERIOR / ELECTRICAL / AC / GARAGE REMARKS

Exterior Doors

The exposed side of wood exterior doors needs to be painted or stained and varnished to prevent discolouring and delamination. Weather-stripping is a must to prevent drafts.

Electrical

Overhead wires from the mast to the main panel that are exposed to the weather may fray and crack. If this occurs, wires should be replaced by a licensed electrician.

Any outdoor overhead service conductor wires should have adequate clearance above the ground (3 meters) and from balcony and windows (1 meter), for safety reasons.

Underground system - Some exterior boxes that are at ground level have a grade line on them. You should insure that the grade remains below this line to prevent moisture from entering the main panel.

Overhead Door Openers

We recommend that a separate electrical outlet be provided. Openers that do not have a safety reverse are considered a safety hazard. Small children and pets are especially vulnerable. We recommend the operating switches be set high enough so children cannot reach them. If an electric sensor is present, it should be tested occasionally to ensure it is working.

Garage Sill Plates

Sill plates within the garage should be elevated or treated lumber should be used. If this is not the case, try to direct water away to prevent rotting.

A/C Compressors

They should not become overgrown with foliage. Clearance requirements vary, but 60 cm on all sides should be considered minimal with up to 2 meters of air discharge desirable. If a clothes dryer vent is within five to ten feet, either relocate the vent or do not run when the A/C is running. The lint will quickly reduce the efficiency of the A/C unit.

Burners

Any appliance such as a water heater, furnace, etc. should have the flame a minimum of 45 cm above the floor. Any open flame less than 45 cm from the floor is a potential safety hazard. The appliance should also be protected from vehicle damage.

KITCHEN / LAUNDRY / UTILITY ROOM REMARKS

Plaster on Wood Lath

Plaster on wood lath is an old technique and is no longer in general use. Wood lath shrinks with time and the nails rust and loosen. As a result, the plaster may become fragile and caution is needed in working with this type of plastering system. Sagging ceilings are best repaired by laminating drywall over the existing plaster and screwing it to the ceiling joists.

Plaster on Gypsum Lath (Rock Lath)

Plaster on gypsum lath will sometimes show the seams of the 40 cm wide gypsum lath, but this does not indicate a structural fault. The scalloping appearance can be levelled with drywall joint compound and fibreglass mesh joint tape or drywall can be laminated over the existing plaster on the ceiling.

Wood Flooring

Always attempt to clean wood floors first before making the decision to refinish the floor. Wax removers and other mild stripping agents plus a good waxing and buffing will usually produce satisfactory results. Mild bleaching agents help remove deep stains. Sanding removes some of the wood in the floor and can usually be done safely only once or twice in the life of the floor.

Nail Pops

Drywall nail pops are due to normal expansion and contraction of the wood members to which the drywall is nailed, and are usually of no structural significance.

Carpeting

Where carpeting has been installed, the materials and condition of the floor underneath cannot be determined.

Appliances

Dishwashers are tested to see if the motor operates and water sprays properly (full cycles are not run). Stoves are tested to see that burners are working and oven and broiler get hot. Timer and controls are not tested. Refrigerators are not tested.

No representation is made to continued life expectancy of any appliance.

Asbestos and Other Hazards

Asbestos fibres in some form are present in many homes, but are often not visible and cannot be identified without testing.

If there is reason to suspect that asbestos may be present and if it is of particular concern, a sample of the material in question may be removed and analyzed in a laboratory. *However, detecting or inspecting for the presence or absence of asbestos is not a part of our inspection.*

Also excluded from this inspection and report are the possible presence of, or danger from, radon gas, lead-based paint, urea formaldehyde, toxic or flammable chemicals and all other similar or potentially harmful substances and environmental hazards.

Windows

A representative number of windows are inspected.

BATHROOM REMARKS

Stall Shower

The metal shower pan in a stall shower has a potential or probable life of 10-20 years depending on quality of the pan installed. Although a visible inspection is made to determine whether a shower pan is currently leaking, it cannot be stated with certainty that no defect is present or that one may not soon develop. Shower pan leaks often do not show except when the shower is in actual use.

Ceramic Tile

Bathroom tile installed in a mortar bed is excellent. It is still necessary to keep the joint between the tile and the tub/shower caulked or sealed to prevent water spillage from leaking through and damaging the ceilings below.

Ceramic tile is often installed in mastic. It is important to keep the tile caulked or water will seep behind the tile and cause deterioration in the wallboard. Special attention should be paid to the area around faucets and other tile penetrations.

Exhaust Fans

Bathrooms with a shower should have exhaust fans where possible. This helps to remove excess moisture from the room, preventing damage to the ceiling and walls and wood finishes. The exhaust fan should not be vented into the attic. The proper way to vent the fans is to the outside. Running the vent pipe horizontally and venting into a gable end or soffit is preferred. Running the vent pipe vertically through the roof may cause condensation to run down the vent pipe, rusting the fan and damaging the wallboard. Insulating the vent pipe in the attic will help to reduce this problem.

SLOW DRAINS on sinks, tubs, and showers are usually due to build-up of hair and soap scum. Most sink pop-ups can be easily removed for cleaning. Some tubs have a spring attached to the closing lever that acts as a catch for hair. It may require removing a couple of screws to disassemble. If you cannot mechanically remove the obstruction, be kind to your pipes. Don't use a caustic cleaner. There are several bacteria drain cleaners available. They are available at hardware stores in areas where septic tanks are used. These drain cleaners take a little longer to work, but are safe for you and your pipes.

Safety Hazards

Typical safety hazards found in bathrooms are open grounds or reverse polarity by water. Replacing these outlets with G.F.C.I.'s are recommended. (See Electrical section)

Whirlpool Tubs

This relates to interior tubs hooked up to interior plumbing. Where possible, the motor will be operated to see that the jets are working. Hot tubs and spas are not inspected.

ROOMS (INTERIOR) REMARKS

Door Stops

All swinging doors should be checked for door stops. Broken or missing door stops can result in door knobs breaking through drywall or plaster.

Closet Guides

Sliding closet doors should be checked to see that closet guides are in place. Missing or broken closet guides can cause scratches and damage to doors.

Cold Air Returns

Bedrooms that do not have cold air returns in them should have a 1.75 cm gap under the doors to allow cold air to be drawn into the hall return.

AN INSPECTION VERSUS A WARRANTY

A home inspection is just what the name indicates, an inspection of a home...usually a home that is being purchased. The purpose of the inspection is to determine the condition of the various systems and structures of the home. While an inspection performed by a competent inspection firm will determine the condition of the major components of the home, no inspection will pick up every minute latent defect. The inspector's ability to find all defects is limited by access to various parts of the property, lack of information about the property and many other factors. A good inspector will do his or her level best to determine the condition of the home and to report it accurately. The report that is issued is an opinion as to the condition of the home. This opinion is arrived at by the best technical methods available to the home inspection industry. It is still only an opinion.

A warranty is a policy sold to the buyer that warrants that specific items in the home are in sound condition and will remain in sound condition for a specified period of time. Typically, the warranty company never inspects the home. The warranty company uses actuarial tables to determine the expected life of the warranted items and charges the customer a fee for the warranty that will hopefully cover any projected loss and make a profit for the warranty seller. It is essentially an insurance policy.

The service that we have provided you is an inspection. We make no warranty of this property. If you desire warranty coverage, please see your real estate agent for details about any warranty plan to which their firm may have access.

WINDOWS / FIREPLACES / ATTIC REMRKS

Window Frames and Sills

Window frames and sills often are found to have surface deterioration due to condensation that has run off the window and damaged the varnish. Usually this can be repaired with a solvent style refinisher and fine steel wool. This is sometimes a sign of excess humidity in the house.

See comments regarding caulking doors and windows above (Chimneys/Gutters/Siding).

Fireplaces

It is important that a fireplace be cleaned on a routine basis to prevent the build-up of creosote in the flue, which can cause a chimney fire.

Masonry fireplace chimneys are normally required to have a terra cotta flue liner or 8 inches of masonry surrounding each flue in order to be considered safe and to conform to most building codes.

During visual inspections, it is not uncommon to be unable to detect the absence of a flue liner either because of stoppage at the firebox, a defective damper or lack of access from the roof.

Wood burners

Once installed, it can be difficult to determine proper clearances for wood burning stoves. Manufacturer specifications, which are not usually available to the inspector, determine the proper installation. We recommend you ask the owner for paperwork verifying that it was installed by a professional contractor.

Ventilation

Ventilation is recommended at the rate of one square foot of vent area to 300 square feet of attic floor space, this being divided between soffit and rooftop. Power vents should ideally have both a humidistat and a thermostat, since ventilation is needed to remove winter moisture as well as summer heat. Evidence of condensation, such as blackened roof sheathing, frost on nail heads, etc. is an indication that ventilation may have been or is blocked or inadequate.

Insulation

The recommended insulation in the attic area is R-38, approximately 30cm. If insulation is added, it is important that the ventilation is proper.

Smoke Detectors

Smoke detectors should be tested monthly. At least one detector should be on each level.

Vapour Barriers

The vapour barrier should be on the warm side of the surface. Older homes were often built without vapour barriers. If the vapour barrier is towards the cold side of the surface, it should be sliced or removed. Most vapour barriers in the attic are covered by insulation and therefore, not visible.

Safety Glazing

Safety glazing requirements vary depending on the age of the home. Every attempt is made to identify areas where the lack of safety glazing presents an immediate safety hazard, such as a shower door. In some older homes it is difficult to determine if safety glazing is present, since the glass is not marked. Therefore, no representation is made that safety glazing exists in all appropriate areas.

Insulated Glass

The broken seals are not always detectable due to dirty windows, covered windows, etc. In most cases, leaking glass seals take some time before they are evident.

BASEMENT REMARKS

Basement

Any basement that has cracks or leaks is technically considered to have failed. Most block basements have step cracks in various areas. If little or no movement has occurred, and the step cracks are uniform, this is considered acceptable. Horizontal cracks in the third or fourth block down indicate the block has moved due to outside pressure. They can be attributed to many factors, such as improper grading, improperly functioning gutter and downspout system, etc. Normally, if little or no movement has taken place and proper grading and downspouts exist, this is considered acceptable. If the wall containing the stress crack(s) has moved considerably, this will require some method of reinforcement. Basements that have been freshly painted or tuck-pointed should be monitored for movement. This will be indicated by cracks reopening. If cracks reappear, reinforcement may be necessary. Reinforcing a basement wall can become expensive.

Foundation (Covered Walls)

Although an effort has been made to note any major inflections or weaknesses, it is difficult at best to detect these areas when walls are finished off, or basement storage makes areas inaccessible. *No representation is made as to the condition of these walls.*

Monitor indicates that the walls have stress cracks, but little movement has occurred. In our opinion, the cracks should be filled with mortar and the walls monitored for further movement and cracking. If additional movement or cracking occurs, re-enforcements may be necessary.

Have Evaluated — we recommend that the walls be re-evaluated by a structural engineer or basement repair company and estimates be obtained if work is required.

Vapour Barrier

Floors that are dirt or gravel should be covered with a vapour barrier.

Moisture Present

Basement dampness is frequently noted in houses and in most cases the stains, moisture or efflorescence present is a symptom denoting that a problem exists outside the home. Usual causes are improper downspout extensions or leaking gutters and/or low or improper grade (including concrete surfaces) at the perimeter of the house. A proper slope away from the house is one inch per foot for four to six feet.

Expensive solutions to basement dampness are frequently offered, and it is possible to spend thousands of dollars on solutions such as pumping out water that has already entered or pumping of chemical preparations into the ground around the house, when all that may be necessary are a few common sense solutions at the exterior perimeter. However, this is not intended to be an exhaustive list of causes and solutions to the presence of moisture. *No representation is made to future moisture that may appear.*

Palmer Valve

Many older homes have a valve in the floor drain. This drain needs to remain operational.

Drain Tile

We offer no opinion about the existence or condition of the drain tile, as it cannot be visibly inspected.

Basement Electrical Outlets

We recommend that you have an outlet within 2 meters of each appliance. The appliance you plan to install may be different than what exists; therefore the inspection includes testing a representative number of receptacles that exist. It is also recommended to have ground fault circuit interrupts for any outlet in the unfinished part of the basement and crawl spaces.

PLUMBING REMARKS

Wells

Examination of wells is not included in this visual inspection. It is recommended that you have well water checked for purity by the local health authorities and, if possible, a check on the flow of the well in periods of drought. A well pit should have a locked cover on it to prevent anyone from falling into the pit.

Septic Systems

The check of septic systems is not included in our visual inspection. You should have the local health authorities or other qualified experts check the condition of a septic system.

In order for the septic system to be checked, the house must have been occupied within the last 30 days.

Water Pipes

Galvanized water pipes rust from the inside out and may have to be replaced within 20 to 30 years. This is usually done in two stages: horizontal piping in the basement first and vertical pipes throughout the house later as needed.

Copper pipes usually have more life expectancy and may last as long as 60 years before needing to be replaced.

Polybutylene pipes are grey pipes that have a history of failure and should be examined by a licensed plumber.

Hose Bibs

During the winter months it is necessary to make sure the outside faucets are winterized. This can be done by means of a valve located in the basement. Leave the outside faucets open to allow any water standing in the pipes to drain, preventing them from freezing. Hose bibs cannot be tested when winterized.

Water Heater

The life expectancy of a water heater is 5-10 years. Water heaters generally need not be replaced unless they leak. It is a good maintenance practice to drain 5-10 gallons from the heater several times a year. *Missing relief valves or improper extension present a safety hazard.*

Water Softeners

During a visual inspection, it is not possible to determine if water is being properly softened.

Plumbing

The temperature/pressure valve should be tested several times a year by lifting the valve's handle. Caution: very hot water will be discharged. If no water comes out, the valve is defective and must be replaced.

Shut-Off Valves

Most shut-off valves have not been operated for long periods of time. We recommend operating each shutoff valve to: toilet bowl, water heater, under sinks, main shut-off, hose faucets, and all others. We recommend you have a plumber do this, as some of the valves may need to be repacked or replaced. Once the valves are in proper operating order, we recommend opening and closing these valves several times a year.

Polybutylene Piping

This type of piping has a history of problems and should be examined by a licensed plumber and repaired or replaced as necessary.

MECHANICAL DEVICES MAY OPERATE AT ONE MOMENT AND LATER MALFUNCTION; THEREFORE, LIABILITY IS SPECIFICALLY LIMITED TO THOSE SITUATIONS WHERE IT CAN BE CONCLUSIVELY SHOWN THAT THE MECHANICAL DEVICE INSPECTED WAS INOPERABLE OR IN THE IMMEDIATE NEED OF REPAIR OR NOT PERFORMING THE FUNCTION FOR WHICH IS IT WAS INTENDED AT THE TIME OF INSPECTION.

HEATING SYSTEM REMARKS

HEATING AND AIR CONDITIONING units have limited lives. Normal lives are:

GAS-FIRED HOT AIR15-25 years
OIL-FIRED HOT AIR
CAST IRON BOILER 30-50 years
(Hot water or steam) or more
STEEL BOILER 30-40 years
(Hot water or steam) or more
COPPER BOILER 10-20 years
(Hot water or steam)
CIRCULATING PUMP (Hot water) 10-15 years
AIR CONDITIONING COMPRESSOR8-12 years
HEAT PUMP8-12 years

Gas-fired hot air units that are close to or beyond their normal lives have the potential of becoming a source of carbon monoxide in the home. You may want to have such a unit checked every year or so to assure yourself that it is still intact. Of course, a unit of such an age is a good candidate for replacement with one of the new, high efficiency furnaces. The fuel savings alone can be very attractive.

Boilers and their systems may require annual attention. If you are not familiar with your system, have a heating contractor come out in the fall to show you how to do the necessary things. *Caution: do not add water to a hot boiler!*

Forced air systems should have filters changed every 30 to 60 days of the heating and cooling season. This is especially true if you have central air conditioning. A dirty air system can lead to premature failure of your compressor - a \$1,500 machine.

Oil-fired furnaces and boilers should be serviced by a professional each year. Most experts agree you will pay for the service cost in fuel saved by having a properly tuned burner.

Read the instructions for maintaining the humidifier on your furnace. A malfunctioning humidifier can rust out a furnace rather quickly. It is recommended that the humidifier be serviced at the same time as the furnace, and be cleaned regularly. *During a visual inspection it is not possible to determine if the humidifier is working.*

Have HVAC Technician Examine - A condition was found that suggests a heating contractor should do a further analysis. We suggest doing this before closing.

Heat exchangers cannot be examined nor their condition determined without being disassembled. Since this is not possible during a visual, non-technically exhaustive inspection, you may want to obtain a service contract on the unit or contact a furnace technician regarding a more thorough examination.

Testing pilot safety switch requires blowing out the pilot light. Checking safety limit controls requires disconnecting blower motor or using other means beyond the scope of this inspection. If furnace has not been serviced in last 12 months, you may want to have a furnace technician examine.

CO Test - This is not part of a non-technical inspection.

Combustible Gas Test (Potential Safety Hazard) - If a combustible gas detector was used during the inspection of the furnace and evidence of possible combustible gases was noted, we caution you that our test instrument is sensitive to many gases and not a foolproof test. None-the-less, this presents the <u>possibility</u> that a hazard exists and could indicate that the heat exchanger is, or will soon be, defective.

COOLING SYSTEM / ELECTRICAL REMARKS

Electrical

Every effort has been made to evaluate the size of the service. Three wires going into the home indicate 240 volts. The total amps are sometimes difficult to determine. We highly recommend that ground fault circuit interrupters (G.F.C.I.) be connected to all outlets around water. This device automatically opens the circuit when it senses a current leak to ground. This device can be purchased in most hardware stores. G.F.C.I.'s are recommended by all outlets located near water, outside outlets, or garage outlets. Pool outlets should also be protected with a G.F.C.I.

The G.F.C.I. senses the flow of electricity through a circuit. If more current is flowing through the black ("hot") wire than the white ("neutral") wire, there is a current leakage. The G.F.C.I., which can sense a ground leak of as little as .005 amps, will shut off the current in 1/40 of a second, which is fast enough to prevent injury.

If you do have G.F.C.I.'s, it is recommended that you test (and reset) them monthly. When you push the test button, the reset button should pop out, shutting off the circuit. If it doesn't, the breaker is not working properly. If you don't test them once a month, the breakers have a tendency to stick, and may not protect you when needed.

Knob and tube wiring found in older homes should be checked by an electrician to insure that the wire cover is in good condition. Under no circumstances should this wire be covered with insulation. Recess light fixtures should have a baffle around them so that they are not covered with insulation. The newer recessed fixtures will shut off if they overheat.

Federal Pacific electrical panels may be unsafe. See www.google.com and search for "Federal Pacific" for additional and up-to-date information.

Aluminum wiring in general lighting circuits has a history of overheating, with the potential of a fire. If this type of wiring exists, a licensed electrical contractor should examine the whole system.

Arc Faults

In some areas, arc faults are required in new homes, starting in 2002. These control outlets in the bedrooms.

Reverse Polarity

A common problem that surfaces in many homes is reverse polarity. This is a potentially hazardous situation in which the hot and neutral wires of a circuit are reversed at the outlet, thereby allowing the appliance to incorrectly be connected. This is an inexpensive item to correct.

Each receptacle has a brass and silver screw. The black wire should be wired to the brass screw and the white wire should go to the silver screw. When these wires are switched, this is called "reverse polarity". Turning off the power and switching these wires will correct the problem.

Main service wiring for housing is typically 240 volts. The minimum capacity for newer homes is 100 amps, though many older homes still have 60 amp service. Larger homes or all electric homes will likely have a 200 amp service.

Main service wiring may be protected by one or more circuit breakers or fuses. While most areas allow up to six main turnoffs, expanding from these panels is generally not allowed.

Cooling

Testing A/C System and Heat Pump - The circuit breakers to A/C should be on for a minimum of 24 hours and the outside temperature at least 15 ° C for the past 24 hours or an A/C system cannot be operated without possible damage to the compressor. Check the instructions in your A/C manual or on the outside compressor before starting up in the summer. Heat pump can only be tested in the mode it's running in. Outside temperature should be at least 15 ° C for the past 24 hours to run in cooling mode.

Temperature differential, between 7°-15°, is usually acceptable. If out of this range, have an HVAC contractor examine it. It is not always feasible to do a differential test due to high humidity, low outside temperature, etc.