# **CITY WIDE HOME INSPECTORS**

## PRE-LISTING HOME INSPECTION REPORT



### 277 Worth Blvd, Thornhill, Ontario

<b>Report Number :</b>	20050090
Inspection Date:	2020-05-04
Prepared by:	City Wide Home Inspectors
	PO Box 325
	Tottenham, Ontario, L0G 1W0
Phone:	(416)203-0333
Toll Free :	1-877-203-0474
Website:	www.citywidehomeinspectors.com
Inspector:	Michael Fournier
Email:	info@citywidehomeinspectors.com

Copyright © 2020 2061490 Ontario Inc. o/a City Wide Home Inspectors

Subject Property: 277 Worth Blvd, Thornhill, Ontario

City Wide Home Inspectors PO Box 325 Tottenham, Ontario, L0G 1W0 Office: (416)203-0333 Toll free: 1-877-203-0474 info@citywidehomeinspectors.com www.citywidehomeinspectors.com



May 4, 2020

Inspection Address: 277 Worth Blvd, Thornhill, Ontario Report Number: 20050090

At your request, an inspection of the above property was performed on 2020-05-04. **City Wide Home Inspectors** is pleased to submit the enclosed report. This report is a professional opinion based on a visual inspection of the accessible components of the home. This report is not an exhaustive technical evaluation. An evaluation of this nature would cost many times more.

Please understand that there are limitations to this inspection. Many components of the home are not visible during the inspection and very little historical information is provided in advance of the inspection. While we can reduce your risk of purchasing a home, we cannot eliminate it, nor can we assume it. Even the most comprehensive inspection cannot be expected to reveal every condition you may consider significant to ownership. In addition to those improvements recommended in our report, we recommend that you budget for unexpected repairs. On average, we have found that setting aside roughly one percent of the value of the home on an annual basis is sufficient to cover unexpected repairs.

The Standards of Practice prohibits us from making any repairs or referring any contractors. We are not associated with any other party to the transaction of this property, except as may be disclosed to you.

The information provided in this report is solely for your use. **City Wide Home Inspectors** will not release a copy of this report without your written consent.

Thank you for selecting our company. We appreciate the opportunity to be of service. Should you have any questions about the general condition of the house in the future, we would be happy to answer these. There is no fee for this telephone or email consulting. Our fees are based on a single visit to the property. If additional visits are required for any reason, additional fees may be assessed.

Sincerely,

Michael Fournier, Owner City Wide Home Inspectors Certified Master Inspector, CMI Certified Mould Inspector, IAC2 Certified Commercial Property Inspector, CCPI Certified Infrared Camera Property Inspector, CICPI

Page 2

## **BUILDING DATA**

## **BUILDING DATA**

Approximate Age:	20 to 25 yrs
Building Type:	Single Family Detached
Building Style:	Two Story
General Appearance:	Satisfactory
Main Entrance Faces:	For the sake of this report North
Weather Condition:	Clear
Temperature:	15 to 20 C
Ground cover:	Dry
Occupancy:	Occupied

This confidential report is prepared exclusively for Dave Elfassy Copyright © 2020 2061490 Ontario Inc. o/s *City Wide Home Inspectors* 

## **REPORT LIMITATIONS**

This report is intended only as a general guide to help the client make his own evaluation of the overall condition of the home, and is not intended to reflect the value of the premises, nor make any representation as to the advisability of purchase. The report expresses the personal opinions of the inspector, based upon his visual impressions of the conditions that existed at the time of the inspection only. The inspection and report are not intended to be technically exhaustive, or to imply that every component was inspected, or that every possible defect was discovered. No disassembly of equipment, opening of walls, moving of furniture, appliances or stored items, or excavation was performed. This inspection is a limited visual examination of the readily accessible systems and components of the home only.

This inspection is conducted in compliance with the standards of practice of the International Association of Certified Home Inspectors (Inter-NACHI), a copy of which is available at <u>www.citywidehomeinspectors.com/sop</u>.

Systems and conditions which are not within the scope of the building inspection include, but are not limited to: pools spas or their related equipment, formaldehyde, lead paint, asbestos, toxic or flammable materials, and other environmental hazards; pest infestation, playground equipment, efficiency measurement of insulation or heating and cooling equipment, internal or underground drainage or plumbing, any systems which are shut down or otherwise secured; water wells (water quality and quantity) zoning ordinances; intercom; security systems; heat sensors; central vacuum systems, cosmetics or building code conformity. Any general comments about these systems and conditions are informational only and are not within the scope of this inspection.

The inspection report should not be construed as a compliance inspection of any governmental or non-governmental codes or regulations. The report is not intended to be a warranty or guarantee of the present or future adequacy or performance of the structure, its systems, or their component parts. This report does not constitute any express or implied warranty of merchantability or fitness for use regarding the condition of the property and it should not be relied upon as such. Any opinions expressed regarding adequacy, capacity, or expected life of components are general estimates based on information about similar components and occasional wide variations are to be expected between such estimates and actual experience. We recommend that any deficiencies noted in this report be repaired or corrected after consultation with reputable qualified contractors. It is suggested that more than one quote be obtained before commencing with repairs.

The sellers' property information sheet (SPIS) may be referred to in this document. This item is a statement that is often completed by the seller regarding the condition of the subject property. The buyer is urged to obtain and review this document, if available, as it contains crucial information. Photographs, taken at the time of this inspection, are to be considered part of this inspection report.

We certify that our inspectors have no interest, present or contemplated, in this property or its improvement and no involvement with tradespeople or benefits derived from any sales or improvements. To the best of our knowledge and belief, all statements and information in this report are true and correct.

We assume no liability for the cost of repair or replacement of unreported defects or deficiencies either current or arising in the future. You agree that in all cases our liability shall be limited to liquidated damages in an amount not greater than the fee you paid us. You waive any claim for consequential, exemplary, special or incidental damages or for the loss of the use of the home/building. You acknowledge that the liquidated damages are not a penalty, but that we intend them to (i) reflect the fact that actual damages may be difficult and impractical to ascertain; (ii) allocate risk between us; and (iii) enable us to perform the inspection for the agreed upon fee.

Should any disagreement or dispute arise as a result of this inspection or report, it shall be decided by arbitration and shall be submitted for binding, non-appealable arbitration unless the parties mutually agree otherwise. In the event of a claim, the Client will allow City Wide Home Inspectors to inspect the claim prior to any repairs or waive the right to make the claim. Client agrees not to disturb or repair or have repaired anything which may constitute evidence relating to the complaint, except in the case of an emergency.

## **Report Table of Contents**

BUILDING DATA	3
REPORT LIMITATIONS	4
SUMMARY*	6
GROUNDS	7
ROOF COVERING	8
CHIMNEY / GUTTERS / SIDING / TRIM	9
EXTERIOR / ELECTRICAL / AC / GARAGE	10
KITCHEN	11
LAUNDRY	11
BATHROOMS	12
INTERIOR ROOMS	14
BASEMENT APARTMENT KITCHEN	17
LAUNDRY	17
BATHROOM	18
INTERIOR ROOMS	19
WINDOWS / FIREPLACES / ATTIC	21
BASEMENT	22
PLUMBING	23
HEATING SYSTEM	24
COOLING SYSTEM	25
ELECTRICAL	25
PHOTOS	26
GENERAL REMARKS	

## SUMMARY\*

### **ITEMS NOT OPERATING**

Powder room GFCI outlet

### MAJOR CONCERNS

AC unit at or near the end of its useful life

### POTENTIAL SAFETY HAZARDS

No smoke detetctor on main floor

### **DEFERRED COST ITEMS**

Items that have reached or are reaching their normal life expectancy or show indications that they may require repair or replacement <u>anytime during the next five (5) years</u>.

A/C unit older than 13 years

\* Items listed in this report may inadvertently have been left off the Summary Sheet. Customer should read the entire report, including the Remarks.

#### DEFINITIONS

**SATISFACTORY** (Sat.) - Indicates the component is functionally consistent with its original purpose but may show signs of normal wear and tear and deterioration.

MARGINAL(Marg.) - Indicates the component will probably require repair or replacement anytime within five years.

**POOR** - Indicates the component will need repair or replacement now or in the very near future.

**MAJOR CONCERNS** - A system or component that is considered significantly deficient or is unsafe.

**SAFETY HAZARD** - Denotes a condition that is unsafe and in need of prompt attention.

	GROUNDS						
Service Walks		☑ None		□ Public sidev	valk needs	s repair	
	□ Concrete	□ Flagstone		□ Brick		□ Other	
Condition:	□ Satisfactory	□ Marginal		□ Poor		🗆 Trip Hazard	
	$\Box$ Pitched towards hom	e $\Box$ Settling cracks		□ Not visible			
Driveway		□ None					
	□ Concrete	$\blacksquare$ Asphalt		Gravel		□ Other	
Condition:	☑ Satisfactory	□ Marginal		□ Poor		□ Trip hazard	
	$\Box$ Fill cracks and seal	$\Box$ Pitched towards he	ome	□ Settling crack	S	□ Not visible	
Patio/Lanai		$\Box$ None					
a		lagstone ☑ Br		C Kool-Dee	ck®	□ Other	
Condition:	☑ Satisfactory	□ Marginal		Poor		□ Trip Hazard	
	□ Pitched towards hom	e (See Remarks page)		□ Settling crack	S	□ Not visible	
Deck			Wood	□ Other			
~		□ Painted/Stained		□ Railing/balus	sters reco		
Condition:	□ Satisfactory	□ Marginal		□ Poor		□ Not visible	
Deck/Patio/Por	ch Covers	$\square$ None $\square$ E	Earth t	o wood contact	□ Mo	isture/insect damage	
Lacks:	□ Metal straps/bolts/nat	ils 🗆 Im	nprope	er attachment to h	nouse		
Porch (covered	entrance)	☑ None		🗆 Railing/bal	usters rec	commended	
Support Pier:	□ Wood	□ Concrete		□ Other		□ Not visible	
Condition:	□ Satisfactory	□ Marginal		□ Poor			
Floor:	□ Satisfactory	□ Marginal		□ Poor		□ Safety Hazard	
Balcony (2nd f	loor platform)	☑ None □ V	Wood	□ Metal		□ Other	
Railing:	$\Box$ Yes	□ No		□ Railing/balus	sters reco	ommended	
Condition:	□ Satisfactory	□ Marginal		□ Poor		□ Safety Hazard	
Stoops/Steps		□ None		Uneven rise	rs	🗆 Safety Hazard	
	☑ Concrete	□ Wood		□ Other		ing recommended	
Condition:	☑ Satisfactory	□ Marginal		□ Poor		ommend baluster	
	□ Cracked	□ Settled		□ Damaged wo	od		
Fencing		□ None		☑ Type: Wood	1	□ Not evaluated	
	ffecting Foundation	(See Remarks page)		<b>-</b>			
Negative grade at:		□ North □ South		☑ Satisfactory			
□ Recommend addition □ Trim back trees/shrul				□ Recommend			
				$\Box$ Wood in cont	act/too cl	ose to soll	
	□ Yard drains observed			□ N/A			
Retaining Wall		□ Yes		☑ No			
		□ Wood		□ Other	⊔ Safet	ty Hazard	
Visual Condition:	□ Satisfactory	□ Marginal		Poor			
Hose Bibs		☑ Yes		□ No		anti-siphon valve	
Operates:	□ Yes	□ No		$\Box$ Not tested	🗹 Not o	on	
General Comm	nents						

Fencing is not part of a home inspection. General site drainage was properly sloping away from the house. Maintain a positive drainage slope away from the foundation.

## **ROOF COVERING**

General Inform	nation						
Roof Visibility		All					
		<u> </u>					
Inspected From	n	Ground with b	onoculars				
Style of Roof							
	oination:	🗹 Hip	□ Mansard	□ Shed □ I	Flat D Other	r	
Pitch: Comb	oination: DLow	□ Medium	🗹 Steep	□ Flat			
Roof Covering							
Type: Asphalt	Estimated Laye	ers: 1 layer	Approx	imate age of cover:	5 to 10 yrs		
Ventilation Sys	stem						
Combination:	☑ Soffit	□ Ridge		□ Gable	🗹 Roof		
	□ Powered	$\Box$ Eaves		□ Other			
Flashing Mate							
Combination:	☑ Galv./Aluminum	$\Box$ Asphalt	🗆 Lea	d 🗆 Rubb	er 🗆 Not v	visible	
	□ Copper	□ Other					
Valley Material				_	_		
Combination:	☑ Galv./Aluminum □ Not visible	□ Asphalt □ Other		□ Copper	□ N/A		
	dition of the Following a						
Roof Covering	$\Box$ Curling	☑ Satisfac □ Cupping	tory	□ Marginal □ Missing tabs/sh	Poo 🗆	Г	
Condition.	$\square$ Moss Buildup	$\Box$ Nail Popping		□ Ponding		Burn Spots	
	□ Exposed Felt	$\Box$ Other	8	8		~1	
Ventilation		(See Rema	arks page)	(See Attic page)			
Flashings		□ Not visi	ble 🗹 S	atisfactory 🛛	Marginal [	] Poor	
ge	□ Rusted		end Sealing	$\Box$ Pulled away from	U	_ 1 001	
Valleys		☑ Satisfac	tory	□ Marginal	D Poo	r	
	□ Not visible	$\square$ N/A		□ Rusted			
	$\Box$ Holes	C Recomm	end Sealing				
Skylights		□ Yes	🗹 No	□ Satisfactory	□ Marginal	□ Poor	
Plumbing Ven	ts	🗹 Yes	□ No	☑ Satisfactory	□ Marginal	D Poor	
General Com	nents						

Roof covering appeared in overall satisfactory condition at the time of the inspection.

CHIMNEY /	<b>GUTTERS</b> /	/ TRIM

Chimney(s)		□ None	Location(s	s): West	
Viewed from:	□ Roof	□ Ladder at ea	aves	Ground w/binocu	lars
Chase:	Brick      Stone	□ Metal	🗆 Frame	ed 🛛 Blocks	□ Stucco
	Evidence of: $\Box$ Cra	cked chimney ca	p 🗆 Loose	e mortar joints	□ Loose brick
		les in metal	□ Rust	🖞 Flaking	
Flue:	🗹 Tile 🛛 Me	tal 🛛	□ Unlined	□ Not visible	
	Evidence of: $\Box$ Sca	ling D	□ Cracks	□ Creosote	
		ve flue(s) cleaned a	nd re-evalua	ted 🛛 🗆 Not evaluat	ted (See Remarks page)
□ Recommend c	ricket/saddle flashing	C	□ Spark arre	stor/rain cap recomm	nended
Gutters & Dow	nspouts	□ None	(See Rem	arks page)	
□ Insides need to	b be cleaned	Ponding			
	☑ Galvanized/Alum.	□ Copper		□ Vinyl	□ Other
Condition:	☑ Satisfactory	Marginal		□ Poor	□ Rusting
	□ Hole in main run	L	.eaking:	□ Corners	□ Joints
Extension needed:	$\Box$ North	$\Box$ South		□ East	□ West
Siding					
Material:	Brick				
Condition:	☑ Satisfactory	$\Box$ Marginal	□ Poor	□ Recomme	nd repair/painting
Window Frame	es				
Material:	Vinyl				
Condition:	☑ Satisfactory	Marginal		□ Poor	
	□ Recommend painting	g	🗆 Dama	aged wood	
Trim, Soffit, Fa	ascia				
Trim Material:	Metal	Condition: Sat	isfactory		
Soffit Material:	Metal	Condition: Sat	isfactory		
Fascia Material:	Metal	Condition: Satisfactory			
Caulking					
Condition:	☑ Satisfactory	□ Marginal		□ Poor	
	Recommend around	windows/doors/m	asonry ledg	es/corners/utility pen	etrations
General Comm	nents				

Gutters were in overall adequate condition. Siding appeared to be in overall adequate condition. Trim appeared to be intact and in overall maintained condition.

Subject Property: 277 Worth Blvd, Thornhill, Ontario

## EXTERIOR / ELECTRICAL / AC / GARAGE

Exterior Wall C	onstruction							
Construction Style	: Wood frame	Z Satisf	actory 🗆 I	Marginal	□ Poor			
Exterior Doors			🗹 Entra	ance (1);	Storm (2);	Patio (3)		
Weather stripping:	☑ Satisfactory		🗆 Margi	nal		Poor		
Condition:	☑ Satisfactory		🗆 Margi	nal		Poor		
Exterior Electri	cal Service							
	□ Overhead		lerground		ce drop:	□ Satisf	actory	$\Box$ Needs service
Exterior outlets:		🗆 No		Oper		🗹 Yes		$\Box$ No
GFCI protected:		🗆 No		Oper		🗹 Yes		$\Box$ No
Reverse polarity:	$\Box$ Yes	🗹 No		Open	ground:	□ Yes		☑ No
Overhead wires:	$\Box$ Low $\Box$	Less th	an 1 meter	from balc	ony/deck/w	vindow 🛛 E	xtension	cord/exposed Romex
Potential safety	hazard:	$\Box$ Yes		🗹 No	o (Se	e Remarks	page)	
A/C Condenser/	Heat Pump		□ None	Approx	imate age: 2	20 to 25 yrs		
#1 Brand: Keepi	rite							Shutoff: Yes
Condition:	□ Satisfactory	🗹 Mar	rginal	🗆 Poor	🗹 Rust	ed/dirty	Level:	IYes 🗹 No
Garage								
Garage Type:	Attached	Garag	e Size: Do	ouble Car				
Automatic open	er: Yes	Opera	tional: Yes					
Safety reverse: I	Present: 🗹 Yes	🗆 No	Operates	: 🗆 Yes	🗆 No	🗹 Needs adj	usting	□Safety Hazard
<b>Electric sensor:</b>	Present: 🗹 Yes	🗆 No	Operates	: 🗹 Yes	🗹 No	🗆 Too low		□Safety Hazard
Roofing:	☑ Same as house	<b>.</b>	Condition	n:	🗹 Satisfa	actory	Marginal	□ Poor
Gutters:	☑ Satisfactory		🗆 Margi	nal		Poor	-	□ None
Siding:	☑ Same as house		□ Wood			Metal		$\Box$ Vinyl
-	□ Stucco		□ Masor	nry		Slate		□ Fiberboard
Trim:	☑ Same as house	<b>,</b>	□ Wood			Aluminum		□ Vinyl
Floor:	☑ Concrete		□ Grave	1		Asphalt		□ Dirt
	Burners less than	45 cm al	bove garage	floor:	☑ N/A □		No 🗆 S	afety hazard
	Condition:		sfactory		pical crack	s 🗆 Large		
Overhead door:	☑ Wood	🗆 Fibe			asonite	□ Metal		□ Other
	Condition:		sfactory	$\Box$ M	arginal	□ Poor	🗆 Ren	air, replace, paint
Service door:	☑ Satisfactory	🗆 Mar		🗆 Po	0	□ None	1	, <b>, , , , , , , , , ,</b>
Sill plates:	□ Elevated		or level	🗆 Bo	oth	☑ Not v	isible	□ Rotted
Electricity prese		□ No	GFCI Pr				Operates:	
	Reverse polarity/o	pen gro			fety Hazar			yman/ext. cord wiring
Firewall:	(Between garage			□ N/A		Present	□ Miss	• •
Fire door:	□ Not verifiable		0 /		eds repair	☑ Satisf		
Auto closure:	$\square$ N/A		sfactory				Missing	□ Needs repair
General Comm	nents							

Doors were reviewed and found to be in working order. Lights appeared to be in normal condition: not all lights were tested. Exterior outlets tested were in normal working order. West side garage door sensor need adjusting to allow the door to close properly. Junction box in garage requires a proper cover plate. Handyman / homeowner wiring in garage for light fixture should be reviewed and corrected as necessary by a qualified electrician.

Countertops			🗹 Satis	factory [	□ Marginal		🗆 Poor	ſ
Cabinets								
Condition:	☑ Satisfactory		🗆 Margi	nal 🛛	Poor		commend repairs	
Plumbing Con	nments							
Faucet leaks:	□ Yes	🗹 No		Pipes leak/corroded	d: 🗆 Yes		🗹 No	
Drainage:	☑ Adequate	🗆 Poo	or	Water pressure:	🗹 Adequat	e	D Poor	
Walls & Ceiling	g							
Condition	☑ Satisfactory	🗆 Ma	rginal	□ Poor	□ Typical	cracks	□ Moist	ure stains
Heat Source P	resent		🗹 Yes	□ No				
Floor								
Condition	☑ Satisfactory	□ Ma	rginal	□ Poor	□ Sloping		□ Squea	ıks
Appliances			(See Re	emarks page)				
Dishwasher:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	□ N/A
Range:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	□ N/A
Oven:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	D N/A
Exhaust fan:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	□ N/A
Refrigerator:	🗹 Yes	🗆 No		<b>Operates</b> :	🗹 Yes		🗆 No	D N/A
Other:	$\Box$ Yes	🗆 No		Operates:	$\Box$ Yes		□ No	$\Box$ N/A
Electrical								
Outlets present:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	
GFCI protected:	□ Yes	🗹 No		Operates:	$\Box$ Yes		🗆 No (R	(emarks
Open ground/rev	verse polarity with	nin 1 me	ter of water:	TYes Safe	ety Hazard 🗹 🛛	No		
General Com	nents:							

**KITCHEN** 

Counter top has normal wear. Cabinets have normal wear. Water flow was normal with several fixtures operated at the same time. There were no visible active piping leaks at the time of the inspection. Drain lines had no visible leaks or signs of backup at the time of inspection. Outlets were randomly tested and had correct polarity, except as noted.

## LAUNDRY

Room Components						
Laundry sink:	$\Box$ N/A	Faucet leaks:	🗆 Yes 🛛 No	Pipe leaks:	🗆 Yes 🗹 No	
Cross connections:	□ Yes	☑ None apparent	Heat source presen	nt: 🗹 Yes	□ No	
Room appears vented:	□ Yes	🗹 No	□ Not visible			
Dryer vented:	$\Box$ N/A	🗹 Wall	□ Ceiling	□ Not vented		
Electrical: Open ground	/reverse pola	rity within 1 meter of w	vater: 🗆 Yes 🗆	Safety Hazard	🗹 No	
Appliances present:	🗹 Washer	Dryer	□ Water heater	□ Furnace	□ Other	
Gas pipe:	☑ N/A	Valve shutoff:	$\Box$ Yes $\Box$ No	$\Box$ Cap Needed	□ Safety Hazard	
<b>General Comments</b>						

At the time of the inspection the laundry facilities were in satisfactory condition.

	DAIRKUUNIS							
Bath: Master E	Bedroom							
Sinks	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No		
Tubs	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No		
Showers	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No		
Toilet:	Bowl loose	□ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	$\Box$ No $\Box$ Cracked b	owl 🛛 Toilet leaks		
Whirlpool:		□ Yes	🗹 No	<i>Operates</i> : $\Box$ Yes	□ No			
Shower/Tub area	l:	🗹 Ceran	nic/Plastic	□ Fiberglass	□ Masonite	□ Other		
	Condition:	🗹 Satisfa	actory	□ Marginal	□ Poor	□ Rotted floors		
	Caulk/Grouting 1	needed:	$\Box$ Yes	🗹 No	Where:			
Drainage:	☑ Satisfactory		🗆 Margin	al	□ Poor			
Water flow:	☑ Satisfactory		🗆 Margin	al	□ Poor			
Moisture stains p	oresent: 🗆 Yes	□ Walls	🗆 Ceiling	s 🗹 No				
Outlets present:	☑ Yes □	No	GFCI protec	ted: 🗹 Yes 🗆 No	Operates: 🗹 Y	es 🗆 No		
	Open ground/rev	erse polar	ity within 1	meter of water:	🗆 Yes 🛛 No			
	<b>Potential safety</b>	hazards p	present:	$\Box$ Yes $\blacksquare$ No (Se	e Remarks page)			
Heat source pres	ent: 🗹	Yes		□ No				
Exhaust fan:	$\Box$ Yes $\blacksquare$	No	Operates:	$\Box$ Yes	$\Box$ No $\Box$ Nois	у		
Windows:	☑ Sat. □ Marg.	🗆 Poor	Cracked g	glass 🗆 None 🗆 Ev	vidence of leaking in	sulated glass		
Door:	$\square$ Sat. $\square$ Marg.	□ Poor	□ Holes □	Does not latch $\Box$ H	Hardware broken □	] None		
General Comments								

DATHDOOMC

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted. Recommend the addition of an exhaust fan vented to the exterior of the home to improve ventilation in the home and prevent moisture build up especially in the winter months.

Bath: Second f	loor					
Sinks	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Tubs	Faucet leaks:	$\Box$ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Showers	Faucet leaks:	$\Box$ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Toilet:	Bowl loose	$\Box$ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	$\Box$ No $\Box$ Cracked b	owl 🛛 Toilet leaks
Whirlpool:		$\Box$ Yes	🗹 No	<i>Operates</i> : $\Box$ Yes	□ No	
Shower/Tub area	:	🗹 Cera	mic/Plastic	□ Fiberglass	□ Masonite	□ Other
	Condition:	🗹 Satis	sfactory	□ Marginal	□ Poor	□ Rotted floors
	Caulk/Grouting r	needed:	$\Box$ Yes	☑ No	Where:	
Drainage:	✓ Satisfactory		🗹 Margina	al	□ Poor	
Water flow:	✓ Satisfactory			□ Marginal □ Poo		
Moisture stains p	resent: 🗆 Yes	□ Wall	ls 🛛 Ceiling	s 🗹 No		
Outlets present:		No		ted: 🗹 Yes 🗆 No	Operates: 🗹 Y	′es □ No
	Open ground/rev	erse pola	arity within 1 r	neter of water:	🗆 Yes 🛛 No	
	Potential safety	hazards	present:	$\Box$ Yes $\blacksquare$ No (Se	e Remarks page)	
Heat source prese	ent: 🗹	Yes		□ No		
Exhaust fan:	$\Box$ Yes $\blacksquare$	No	Operates:	$\Box$ Yes	$\Box$ No $\Box$ Nois	У
Windows:				lass 🗆 None 🗆 Evi		
Door:	☑ Sat. □ Marg.	□ Poor	$\square$ Holes $\square$	Does not latch $\Box$ H	Hardware broken □	] None
General Comm	nents					

Left sink drain is slow, review and repair, as necessary. Recommend the addition of an exhaust fan vented to the exterior of the home to improve ventilation in the home and prevent moisture build up especially in the winter months.

Bath: Main floo	or									
Sinks	Faucet 1	eaks:	□ Yes	🗹 No			Pipes leak	:	□ Yes	🗹 No
Toilet:	Bowl lo	ose	□ Yes	🗹 No	<b>Operates:</b>	🗹 Yes	□ No □	Cracked b	owl 🗆 To	oilet leaks
Drainage:	☑ Satis	factory		🗹 Margin	al		□ Poor			
Water flow:	☑ Satis	factory		🗆 Margin	al		🗆 Poor			
Moisture stains p	resent:	□ Yes	□ Wall	s 🛛 Ceiling	s 🗹 No					
Outlets present:	🗹 Yes	🗆 No	GFCI pr	rotected:	🗹 Yes	🗆 No	<b>Operates:</b>		□ Yes	🗹 No
	Open gr	ound/rev	erse pola	rity within 6'	of water:	□ Yes	🗹 No			
	Potenti	al safety	hazards	present:	$\Box$ Yes	🗹 No	(See Rem	arks pag	ge)	
Heat source prese	ent:		🗹 Yes		🗆 No					
Exhaust fan:	□ Yes		No	Operates:	$\Box$ Yes		🗆 No	🗆 Nois		
Windows:	🗹 Sat.	□ Marg.	□ Poor	□ Cracked g	glass 🗆 Noi	ne 🗆 Evi	dence of le	aking inst	ulated gla	SS
Door: ☑ Sat. □ Marg. □ Po				$\Box$ Holes $\Box$	Does not la	ttch □ H	Hardware b	roken 🗆	l None	
General Comments										

GFCI outlet is defective and needs to be replaced, will not reset. Sink drain is slow, review and repair, as necessary

## **INTERIOR ROOMS**

MASTER BEDROOM
----------------

Location: Seco	nd floor								
Walls & Ceiling:	☑ Satisfac	ctory		arginal		□ Poor	□ Typical (	Cracks	□ Holes
	Moisture s	stains:	$\Box$ Ye	es		🗹 No			
Flooring:	☑ Satisfac	ctory	$\Box$ M	arginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sa	tisfactory		🗆 Marginal		□ Poor	
Electrical:	Switches:	🗹 Yes	□ No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	🗆 No
	Open grou	ind/reverse	e polarity:	□Yes	🗆 Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🛛	Marg. $\Box$	Poor 🗆 Cra	icked glass	□ None l	□ Evidence of	leaking insu	lated glas	38
Door:	🗹 Sat. 🛛	Marg. $\Box$	Poor 🗆 Ho	les 🛛 Does	not latch	🛛 🗆 Hardware	e broken 🛛	None	
Closet Doors: $\square$ Sat. $\square$ Marg. $\square$ Poor $\square$ Holes $\square$ Missing $\square$ Tracks broken $\square$ None									
General Comments:									

At the time of the inspection the room was found to be in overall satisfactory condition.

#### **BEDROOM #2**

Location: Seco	ond floor								
Walls & Ceiling:	☑ Satisfac	tory		arginal		□ Poor	□ Typical (	Cracks	□ Holes
	Moisture s	tains:	$\Box$ Y	es		☑ No			
Flooring:	☑ Satisfac	tory	$\Box$ M	arginal		□ Poor	□ Squeaks	□ Slopes	
Ceiling fan: $\square$ N/A			🗆 Sa	□ Satisfactory		□ Marginal		D Poor	
Electrical: Switches: Z Yes			🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
Open ground/reverse p			polarity:	$\Box$ Yes	□ Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	☑ Sat. □	Marg. 🛛	Poor 🗆 Cra	acked glass	□ None l	□ Evidence of	leaking insu	lated glas	38
Door:	🗹 Sat. 🗆	Marg. 🛛	Poor 🗆 Ho	les 🗆 Does	s not latch	1 🛛 Hardware	broken 🛛	None	
Closet Doors: Zat. Darg. Poor Holes Missing Tracks broken None									
General Comments:									

At the time of the inspection the room was found to be in overall satisfactory condition.

#### **BEDROOM #3**

Location: Seco	nd floor									
Walls & Ceiling:	☑ Satisf	actory			arginal		□ Poor	□ Typical	Cracks	□ Holes
	Moisture	stains:		🗆 Ye	s		🗹 No			
Flooring:	☑ Satisf	actory		$\Box$ Ma	arginal		□ Poor	$\Box$ Squeaks $\Box$ Slo		□ Slopes
Ceiling fan:	🗹 N/A			□ Satisfactory			🗆 Marginal	□ Poor		
Electrical: Switches: Z Yes			es 🗆	No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
Open ground/reverse j			erse po	larity:	$\Box$ Yes	□ Safet	y Hazard	🗹 No	$\Box$ Cove	ers missing
Heat source prese				t visible						
Windows:	🗹 Sat. 🛛	□ Marg.	🗆 Po	or 🗆 Cra	acked glass	$\Box$ None	□ Evidence of	f leaking insu	lated gla	ISS
Door:	🗹 Sat. 🛛	□ Marg.	🗆 Po	or 🗆 Ho	oles 🗆 Doe	s not late	h 🛛 Hardwar	e broken 🛛	None	
Closet Doors: Ø Sat. □ Marg. □ Po				or 🗆 Ho	oles 🗆 Mis	sing 🛛 T	Tracks broken	□ None		
General Comments:										

RFI		OM	#4
DEL	JKU		#4

Location: Seco	Location: Second floor								
Walls & Ceiling:	☑ Satisfac	tory		arginal		□ Poor	□ Typical	Cracks	□ Holes
-	Moisture s	tains:	$\Box$ Ye	es		🗹 No			
Flooring:	☑ Satisfac	tory	$\Box$ M	arginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sa	tisfactory		□ Marginal		D Poor	
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open grou	nd/reverse	polarity:	□ Yes	🗆 Safet	y Hazard	🗹 No	$\Box$ Cove	ers missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🛛	Marg. 🗆	Poor Cr	acked glass	$\Box$ None	□ Evidence of	leaking inst	ulated gla	ISS
Door:	🗹 Sat. 🛛	Marg. 🛛	Poor 🗆 Ho	oles Does	s not latch	n 🛛 Hardware	e broken 🛛	None	
Closet Doors: Ø Sat. □ Marg. □ Poor □ Holes □ Missing □ Tracks broken □ None									
General Comments:									

At the time of the inspection the room was found to be in overall satisfactory condition.

#### LIVING ROOM

Location: First	floor							
Walls & Ceiling:	✓ Satisfactory	□ Marginal		□ Poor	□ Typical (	Cracks	□ Holes	
-	Moisture stains:	□ Yes		🗹 No	•••			
Flooring:	✓ Satisfactory	□ Marginal		□ Poor	□ Squeaks		□ Slopes	
Ceiling fan:	⊠ N/A	□ Satisfactory		□ Marginal	-	□ Poor	-	
Electrical:	Switches: ☑ Yes □	No Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	$\Box$ No	
	Open ground/reverse po	larity: 🗆 Yes	□ Safety	Hazard	🗹 No	$\Box$ Cove	rs missing	
Heat source prese	ent: 🗹 Yes 🗆 Not vi	sible	-				-	
Windows:	☑ Sat. □ Marg. □ Po	or  Cracked glass	□ Evider	nce of leaking	insulated gla	ass		
Door:	boor: $\Box$ Sat. $\Box$ Marg. $\Box$ Poor $\Box$ Holes $\Box$ Does not latch $\Box$ Hardware broken $\Box$ None							
General Comm	nents:							

At the time of the inspection the room was found to be in overall satisfactory condition.

#### **DINING ROOM**

Location: First	floor							
Walls & Ceiling:	✓ Satisfactory	□ Ma	rginal		□ Poor	□ Typical (	Cracks	□ Holes
-	Moisture stains:	□ Ye	s		🗹 No			
Flooring:	☑ Satisfactory	$\Box$ Ma	rginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	⊠ N/A	🗆 Sat	isfactory		□ Marginal		□ Poor	
Electrical:	Switches:   Yes	No	Outlets:	🗹 Yes	🗆 No	Operates:	🗹 Yes	□ No
	Open ground/reverse po	olarity:	□Yes	🗆 Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing
Heat source prese	ent: 🗹 Yes 🗆 Not vi	sible						
Windows:	☑ Sat. □ Marg. □ Po	oor 🗆 Cr	acked glass	🗆 Evid	ence of leaking	g insulated gl	lass	
Door:	oor: $\Box$ Sat. $\Box$ Marg. $\Box$ Poor $\Box$ Holes $\Box$ Does not latch $\Box$ Hardware broken $\overline{\Box}$ None							
General Comm	General Comments:							

EATING ARE	Α								
Location: First	floor								
Walls & Ceiling:	☑ Satisfactory	□ Ma	arginal		□ Poor	□ Typical	Cracks	□ Holes	
	Moisture stains:	□ Ye	s		🗹 No				
Flooring:	☑ Satisfactory	$\Box$ Ma	arginal		□ Poor	□ Squeaks		□ Slopes	
Ceiling fan:	☑ N/A	🗆 Sa	tisfactory		🗆 Marginal		D Poor		
Electrical:	Switches:   Yes	] No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	🗆 No	
	Open ground/reverse p	olarity:	□Yes	□ Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing	
Heat source prese	ent: 🗹 Yes 🛛 Not w	visible							
Windows:	$\Box$ Sat. $\Box$ Marg. $\Box$ P	oor 🗆 Cr	acked glass	Evid	ence of leaking	g insulated g	lass		
Door:	oor: $\square$ Sat. $\square$ Marg. $\square$ Poor $\square$ Holes $\square$ Does not latch $\square$ Hardware broken $\square$ None								
General Comm	nents:								

At the time of the inspection the room was found to be in overall satisfactory condition.

FAMILY ROO	M									
Location: First	floor									
Walls & Ceiling:	✓ Satisfactory		arginal		□ Poor	□ Typical (	Cracks	□ Holes		
	Moisture stains:	$\Box$ Yes			🗹 No					
Flooring:	☑ Satisfactory	$\Box$ Ma	arginal		D Poor	□ Squeaks		□ Slopes		
Ceiling fan:	⊠ N/A	$\Box$ Sa	tisfactory		□ Marginal		□ Poor			
Electrical:	Switches: Z Yes	] No	Outlets:	🗹 Yes	🗆 No	Operates:	🗹 Yes	□ No		
	Open ground/reverse p	olarity:	□Yes	□ Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing		
Heat source press	ent: 🗹 Yes 🗆 Not v	visible								
Windows:	☑ Sat. □ Marg. □ F	oor 🗆 Cr	acked glass	🛛 🗆 Evid	ence of leaking	g insulated g	lass			
Door:	Door: $\square$ Sat. $\square$ Marg. $\square$ Poor $\square$ Holes $\square$ Does not latch $\square$ Hardware broken $\square$ None									
General Comm	General Comments:									

At the time of the inspection the room was found to be in overall satisfactory condition.

#### **STORAGE ROOM**

Location: Baser	ment						
Walls & Ceiling:	☑ Satisfactory	□ Marginal		□ Poor	□ Typical (	Cracks	□ Holes
	Moisture stains:	□ Yes		🗹 No			
Flooring:	☑ Satisfactory	□ Marginal		🗆 Poor	□ Squeaks	□ Slopes	
Ceiling fan:	☑ N/A	□ Satisfactory		□ Marginal		□ Poor	
Electrical:	Switches: ☑ Yes □	No Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open ground/reverse po	olarity:  □Yes	🗆 Safety	v Hazard	🗹 No	$\Box$ Cove	rs missing
Heat source prese	ent: 🗹 Yes 🛛 Not vi	sible					
Windows:	$\Box$ Sat. $\Box$ Marg. $\Box$ Po	or Cracked glass	s 🗆 Evide	ence of leaking	g insulated gl	lass	
Door:	oor: $\square$ Sat. $\square$ Marg. $\square$ Poor $\square$ Holes $\square$ Does not latch $\square$ Hardware broken $\square$ None						
General Comm	ents:						

#### Page 17

## **BASEMENT APARTMENT**

## **KITCHEN**

Countertops			☑ Satis	factory	□ Marginal		D Poor	
Cabinets								
Condition:	☑ Satisfactory		🗆 Margi	nal E	⊐ Poo	or 🗆 Rec	□ Recommend repairs	
Plumbing Con	nments							
Faucet leaks:	□ Yes	🗹 No		Pipes leak/corrode	ed:	□ Yes	🗹 No	
Drainage:	☑ Adequate	□ Poo	or	Water pressure:		☑ Adequate	□ Poor	
Walls & Ceiling	9							
Condition	☑ Satisfactory	□ Ma	rginal	□ Poor		□ Typical cracks	□ Moist	ure stains
Heat Source P	resent		☑ Yes	□ No				
Floor								
Condition	☑ Satisfactory	□ Ma	rginal	□ Poor		□ Sloping	🗆 Squea	ks
Appliances			(See Re	emarks page)				
Dishwasher:	□ Yes	🗹 No		<b>Operates</b> :		□ Yes	🗆 No	$\Box$ N/A
Range:	🗹 Yes	🗆 No		<b>Operates</b> :		🗹 Yes	🗆 No	$\Box$ N/A
Oven:	🗹 Yes	🗆 No		<b>Operates</b> :		🗹 Yes	🗆 No	$\Box$ N/A
Exhaust fan:	🗹 Yes	🗆 No		<b>Operates</b> :		🗹 Yes	🗆 No	$\Box$ N/A
Refrigerator:	🗹 Yes	🗆 No		Operates:		🗹 Yes	🗆 No	$\Box$ N/A
Other:	□ Yes	□ No		Operates:		□ Yes	□ No	$\Box$ N/A
Electrical								
Outlets present:	🗹 Yes	🗆 No		<b>Operates</b> :		🗹 Yes	🗆 No	
GFCI protected:	🗹 Yes	🗆 No		<b>Operates</b> :		🗹 Yes	🗆 No ( <b>R</b>	(emarks)
Open ground/rev	erse polarity with	in 1 me	ter of water:	$\Box$ Yes $\Box$ Sat	fety H	azard 🗹 No		
General Comn	nents:							

General Comments:

Counter top has normal wear. Cabinets have normal wear. Water flow was normal with several fixtures operated at the same time. There were no visible active piping leaks at the time of the inspection. Drain lines had no visible leaks or signs of backup at the time of inspection. Outlets were randomly tested and had correct polarity, except as noted.

## LAUNDRY

Room Components						
Laundry sink:	☑ N/A	Faucet leaks:	□ Yes	🗆 No	Pipe leaks:	$\Box$ Yes $\Box$ No
Cross connections:	□ Yes	☑ None apparent				
Room appears vented:	□ Yes	⊠ No	$\Box$ Not vis	ible		
Dryer vented:	$\Box$ N/A	🗹 Wall	□ Ceiling		□ Not vented	
Electrical: Open ground	/reverse pola	rity within 1 meter of	water:	Yes 🗆	Safety Hazard	🗹 No
Appliances present:	🗹 Washer	Dryer	□ Water h	neater	□ Furnace	□ Other
Gas pipe:	☑ N/A	Valve shutoff:	$\Box$ Yes	$\Box$ No $\Box$ Cap Needed		□ Safety Hazard
General Comments						

At the time of the inspection the laundry facilities were in satisfactory condition.

Sinks	Faucet le	aks:	□ Yes	🗹 No		Pipes leal	k:	🗆 Yes 🗹	No
Showers	Faucet le	aks:	□ Yes	🗹 No		Pipes leal	k:	🗹 Yes 🗹	No
Toilet:	Bowl loc	ose	□ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	$\Box$ No $\Box$	Cracked b	oowl 🛛 Toilet	leaks
Shower area:	🗹 Ceran	nic/Plasti	с	□ Fibergl	ass	□ Mason	nite	□ Other	
	Conditio	n:	☑ Satis	factory	□ Marginal	□ Poor		□ Rotted fl	oors
	Caulk/G	routing n	eeded:	□ Yes	⊠ No	Where:			
Drainage:	☑ Satisfa	actory		🗆 Margin	🗆 Poor				
Water flow:	☑ Satisfa	actory		□ Margin	□ Poor				
Moisture stains p	present:	□ Yes	□ Wal	ls 🗆 Ceiling	s ☑ No				
Outlets present:	☑ Yes		No	GFCI protec	ted: 🗹 Yes 🗆 N	o Opera	tes: ☑ Y	Yes 🗆 No	
-	Open gro	ound/reve	erse pola	arity within 1	meter of water:	□ Yes	🗹 No		
	Potentia	l safety ]	hazards	present:	□ Yes ☑ No (S	ee Remark	s page)		
Heat source pres	ent:	V	Yes	_	□ No				
Exhaust fan:	□ Yes	$\checkmark$	No	<b>Operates</b> :	□ Yes	🗆 No	🗆 Nois	y	
Windows:	□ Sat. □	□ Marg.	D Poor	□ Cracked g	glass 🗹 None 🗆 E	vidence of	leaking in	sulated glass	
Door:	☑ Sat. [	□ Marg.		$\square$ Holes $\square$	Does not latch $\Box$	Hardware b	oroken 🗆	None	
General Comments									

**BATHROOM** 

Shower head is leaking inside the shower area, additional plumbers taping of the shower head threads advised.

## **INTERIOR ROOMS**

BEDROOM #	1						
Location: Seco	ond floor						
Walls & Ceiling:  Satisfactory		□ Marginal		□ Poor	□ Typical Cracks □ Holes		□ Holes
	Moisture stains:	□ Yes		🗹 No			
Flooring:	✓ Satisfactory	🗆 Marginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	⊠ N/A	□ Satisfactor	у	$\Box$ Marginal			
Electrical:	Switches: ☑ Yes □	No Outlet	s: 🗹 Yes	🗆 No	Operates:	🗹 Yes	🗆 No
	Open ground/reverse po	larity:  □Yes	🗆 Safet	y Hazard	🗹 No	$\Box$ Cove	ers missing
Heat source prese	ent: 🗹 Yes 🗆 No	t visible					
Windows:	☑ Sat. □ Marg. □ Po	or 🗆 Cracked gl	ass 🗆 None	□ Evidence of	leaking insu	lated gla	SS
Door:	☑ Sat. □ Marg. □ Po	or 🗆 Holes 🗆 🛙	oes not latch	n 🛛 Hardware	e broken 🛛	None	
Closet Doors:	☑ Sat. □ Marg. □ Po	or $\Box$ Holes $\Box$ N	∕lissing □ T	racks broken	□ None		
General Comm	nents:						

At the time of the inspection the room was found to be in overall satisfactory condition.

#### **BEDROOM #2**

Location: Seco	nd floor								
Walls & Ceiling:	☑ Satisfac	tory	□ M	arginal		□ Poor	□ Typical Cracks □ Holes		
	Moisture st	tains:	$\Box$ Ye	es		🗹 No			
Flooring:	☑ Satisfac	tory	$\Box$ M	arginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	☑ N/A	-	$\Box$ Sa	tisfactory		Marginal	□ Poor		-
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open group	nd/reverse	polarity:	$\Box$ Yes	🗆 Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🗆	Marg. 🛛	Poor 🗆 Cra	acked glass	🗆 None 🛛	□ Evidence of	leaking insu	lated glas	ss
Door:	☑ Sat. □	Marg. 🛛	Poor 🗆 Ho	les 🗆 Does	s not latch	🛛 🗆 Hardware	broken 🛛	None	
Closet Doors:	☑ Sat. □	Marg. 🛛	Poor 🗆 Ho	oles 🗆 Miss	sing 🗆 Ti	racks broken	□ None		
General Comm	ents:								

LIVING ROO	Μ							
Location: First	floor							
Walls & Ceiling:	☑ Satisfactory	□ Ma	arginal		□ Poor	□ Typical (	Cracks	□ Holes
	Moisture stains:	□ Ye	S		🗹 No			
Flooring:	✓ Satisfactory	□ Marginal			□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	☑ N/A	🗆 Sat	tisfactory		🗆 Marginal		□ Poor	
Electrical:	Switches:  Yes	No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	🗆 No
	Open ground/reverse po	olarity:	$\Box$ Yes	□ Safet	y Hazard	🗹 No	$\Box$ Cove	ers missing
Heat source press	ent: 🗹 Yes 🗆 Not vi	sible						
Windows:	$\Box$ Sat. $\Box$ Marg. $\Box$ Po	oor 🗆 Cra	acked glass	🗆 Evide	ence of leaking	insulated gl	ass	
Door:	$\Box$ Sat. $\Box$ Marg. $\Box$ Po	oor 🗆 Ho	oles 🗆 Does	s not late	h 🗆 Hardwar	e broken 🗹	None	
General Comm	nents:							

At the time of the inspection the room was found to be in overall satisfactory condition.

EATING ARE	Α						
Location: First	floor						
Walls & Ceiling: ☑ Satisfactory		□ Marginal	□ Marginal		□ Typical (	Cracks	□ Holes
	Moisture stains:	$\Box$ Yes		🗹 No			
Flooring:	✓ Satisfactory	□ Marginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	☑ N/A	□ Satisfactory		□ Marginal		□ Poor	
Electrical:	Switches: ☑ Yes □	No Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open ground/reverse po	olarity:  □Yes	🗆 Safet	y Hazard	🗹 No	$\Box$ Cove	rs missing
Heat source press	ent: 🗹 Yes 🛛 Not vi	sible					
Windows:	□ Sat. □ Marg. □ Po	or 🗆 Cracked glass	s 🗆 Evid	ence of leaking	g insulated g	lass	
Door:	☑ Sat. □ Marg. □ Po	oor 🗆 Holes 🗆 Doe	es not late	ch 🛛 Hardwar	re broken	] None	
General Comm	nents:						

## WINDOWS / FIREPLACES / ATTIC

Interior Windows/Glass         General condition:       ☑ Satisfactory       □ Marginal       □ Poor       □ Painted shut         □ Hardware missing       □ Glazing compound needed       □ Cracked glass       □ Broken counter-balance mech.         □ Surface deterioration:       (See Remarks page)       ☑ Representative number of windows operated         Evidence of leaking insulated glass:       □ Yes       ☑ No       □ Not determinable       □ N/A
<ul> <li>□ Hardware missing</li> <li>□ Glazing compound needed</li> <li>□ Surface deterioration:</li> <li>□ Glazing compound needed</li> <li>□ Cracked glass</li> <li>□ Broken counter-balance mech.</li> <li>□ Representative number of windows operated</li> </ul>
□ Surface deterioration: (See Remarks page) ☑ Representative number of windows operated
Safety glazing: $\square$ N/A $\square$ Safety issue Where:
Security bars present:  Yes  No  Not tested Test release mechanism before moving in
Fireplace         DNone         Location(s): Family room
□ Gas ☑ Wood □ Wood burner stove (See Remarks page)
□ Masonry insert □ Metal insert □ Metal □ Electric
□ Blower built-in Operates: □ Yes □ No ☑ Damper operates □ Damper missing
□ Open joints or cracks in firebrick should be sealed □ Pre-fabricated panels damaged/worn
Hearth: Satisfactory: 🗹 Yes 🗆 No Mantle: 🗹 Satisfactory 🗆 Loose
□ Recommend having flue cleaned and re-examined □ Vent less □ Direct Vent
Stairs     Image: Statisfactory     Image: Marginal     Image: Poor     Image: None
Handrail: 🛛 Satisfactory 🗋 Marginal 🖓 Poor 🖓 Safety Hazard
Risers/Treads:Image: SatisfactoryImage: MarginalImage: PoorImage: Risers/treads uneven
Smoke/CO Detectors     (See Remarks page)
Present: 🗹 Yes 🗹 No
Note: Working smoke detectors are required on all levels of a home. Working CO detectors are required on all levels of a home with sleeping
areas. Battery operated detectors should be tested monthly and batteries changed semi annually. Most battery operated units should be replaced every 5 yrs and most hardwired units replaced every 10 yrs (see manufactures recommendations).
Access: Access panel Access Location: Bedroom closet Inspected from: Access panel
Flooring:  Complete  Partial  None
Insulation: Type: Loose fill fiberglass Average thickness: Over 12 inches R Rating: R40
Installed in:  Floor  Rafters  Walls  Not Visible
Vent fans:  Present  Not tested  Thermostat controlled  Safety Hazard
Ventilation: Satisfactory
Roof structure: Wooden trusses
Roof sheathing:       Plywood         Roof Sheathing Condition:       ☑ Satisfactory □ Marginal □ Poor □ Rotted □ Stained □ Delaminated
Roof Sheathing Condition: $\square$ Satisfactory $\square$ Marginal $\square$ Poor $\square$ Rotted $\square$ Stained $\square$ Delaminated Fans exhausted to: Attic: $\square$ Yes $\square$ No $\square$ Outside: $\square$ Yes $\square$ No $\square$ Not visible $\square$ N/A (See Remarks page)
Chimney chase:
Structural problems observed:          Yes         Yes         Yes         Yes         Ono         See comments below         Improperly installed          Vapour barriers:          Yes         No         Visible         Improperly installed
$\Box \text{ Kraft faced} \Box \text{ Plastic} (See Remarks page)$
Electrical: Open junction box(es) Handyman wiring Visible knob-and-tube
General Comments

Trusses showed no major defects or damage at the time of inspection. Roof sheathing, examined from the attic, showed no major defects or moisture damage. Insulation was sufficient for homes in this area. Ventilation was normal. Vapour barrier not visible. Smoke detector required on main floor.

## BASEMENT

### (See Remarks page)

Stairs						
Condition:	☑ Satisfactor	у	□ Marginal	□ Poor	🗆 Safety Haz	ard
Handrail: 🗹 Yes	□ No Con	dition:	☑ Satisfactory	□ Marginal	D Poor	
Headway over stairs:	☑ Satisfactor	у	□ Marginal	□ Poor		
Under carriage:	☑ Satisfactor	У	□ Marginal	□ Poor	□ Not visible	
Foundation						
Wall Material:	Poured Concr	ete				
Condition:	Satisfactory					
Foundation Cracks:		one Vis	ible Visib	le from: 🗹 Exter	ior 🗆 Interior	
Movement apparent:	$\Box$ Yes $\blacksquare$ N	•				
Partially/Covered walls:	Ø Yes □N	0				
	Condition re	ported	above reflects <u>visib</u>	le portion only		
Floor			(See vapour bar	rier remarks)		
Material:	Concrete					
Condition:	Satisfactory					
Seismic Bolts			Not applicable			
Basement Drainage						
Indication of moisture:	No					
Sump Pump:	Yes Su	mp Pun	np Operates: Yes			
Floor drain(s) present:	Yes					
Drain Tile (See Remarks	page)	□P	almer valve present	□ Not Visible	(See Remar	ks page)
Girders (1), Columns (2)			[/A			
	☑ Steel		□ Wood	□ Block	□ Concrete	□ Not visible
Condition:	☑ Steel ☑ Satisfactor	v	$\square$ Marginal	$\square$ Poor	□ Stained/rus	
		<i>,</i>				
Joists /Trusses						
$\square$ Joist $\square$ Trusses	I-Joist		□ Steel	☑ Wood		□ Not visible
	$\Box 2x6$		☑ 2x8	$\Box 2x10$	$\Box 2x12$	
Sub Floor						
			ture stains/rotting			
	** Areas a	round s	hower stalls, etc., as	viewed from bas	sement or crawl	space
General Comments						

Foundation appeared to be in overall satisfactory condition. Foundation walls were covered/partially covered with paneling/drywall/insulation and were not visible. No representation can be made to the conditions of the covered/partially covered walls. Floor appeared to be in overall satisfactory condition. No active seepage visible at the time of the inspection. No representation can be made to future leaking of the basement walls. Recommend extending the sump pump drain line on the exterior of the home to ensure proper water drainage away from the foundation.

PLUMBING								
Water Service		Shut off location:	Basement					
Water entry piping: Co	opper Water	lines: Copper						
	Lead (other than	solder joints):	🗆 Yes 🗹 No	□ Service entry	Unknown			
	Water flow:	☑ Satisfactory	□ Poor	Cross connection:	$\Box$ Yes $\Box$ No			
	Water pressure:	☑ Satisfactory	□ Poor □ Aboy	ve 80 psi (Needs eva	luation)			
	Pipes: Corroc	led 🛛 Leaking	□ Valves broker	n/missing 🛛 🗆 Di	ssimilar metal			
Drain/waste/vent pipe:	Plastic							
	Condition:	☑ Satisfactory	□ Marginal	□ Poor	□ Not visible			
	Waste discharge:	☑ Satisfactory	□ Slow drain					
Gas Lines		□ Not visible	□ Shutoff miss	sing				
	□ Copper	$\Box$ Brass	☑ Black iron	□ Stainless steel	$\Box$ CSST			
Water Heater								
Brand name: Bradford	White							
Energy Source: Gas	Approx. age:6	yrs		Capacity: 60 gallo	n			
Rental Unit: Yes		Seismic restraints n	eeded: 🗹 N/A 🗆	l Yes □ No				
Relief valve:	☑ Yes □ No	Extension pr	oper: 🗹 Yes	□ No □ Missi	ing			
Vent pipe:	□ N/A ☑ Satisf	actory  Improper	pitch 🗆 Rusted	□ Safety Hazard				
Water Softener		(Unit not evaluat	ted)					
	□Yes ☑ No	Plumbing hoc	oked up:	□No				
General Comments								

Overall the plumbing system, faucets, water pressure and drain rates were found to be in satisfactory condition at the time of the inspections.

	HEATING SYSTEM							
Fuel Shutoff fo	r Building	Main fuel s	shutoff location: Out	tside at gas n	neter			
Forced Air Sys	tem	☑ Central	Unit 🗆 V	Vall Furnace	□ Floor Furnace			
<b>y</b>	Brand name: Go	odman		Approx	ximate age: 5 to 10 yrs			
Energy source:	Gas Furna	ce Efficiency:	: High Efficiency					
Hot air systems:	Direct drive							
Heat exchanger:	Sealed unit, not visible	View is ex	tremely limited - S	See Remarks	s page about options			
Distribution:	Metal Ducts	Flue pipin	g: Plastic					
Filter: Standard	Filter Condition: Sa	tisfactory						
Operated:	When turned on I	by thermostat	: 🗹 Fired	🗆 Did	not fire			
Operation:	Satisfactory: 🗹	Yes 🗆 No	Recommend HV	AC technicia	an examine 🗆 Before closing			
Controls:	□ Disconnect		☑ Normal operatin	ng and safety	controls observed			
Heat pump:	$\Box$ Aux. Elec.	🗆 Aux. Gas	□ Aux. geotherma	l ⊠ N/A				
	Emergency heat	tested:	$\Box$ Yes $\Box$ No	o ☑ N/A				
Others		☑ N/A						
	□ Electric baseb	oard	□ Radiant ceiling ca	able 🛛 Gas	space heater			
	□ Radiant in floor	heating	$\Box$ Wood burning s	tove (See R	emarks page)			
General Comm	nents							

Furnace was in normal working order at the time of the inspection. Heat exchanger had limited visibility due to its high-efficiency design. Flue was drafting properly at the time of the inspection. Filter should be changed /cleaned on regular bases.

## **COOLING SYSTEM**

System Components		□ None		Approximate age: 20 to 25 yrs				
Energy source: Electric	Central air: Air C	Cooled						
Operated: No	Operation: Not operated							
Refrigerant lines:	🗆 Leak	🗆 Damag	ged	🗆 Insulat	ion missing	☑ Satisfactory		
Through wall unit(s):	☑ N/A	Operated:	□ Yes	□ No	□ Satisfactory	$\Box$ Needs service		
General Comments								

A/C was not operated due to the outside temperature being too cold. AC unit is aged and past its useful life expectancy; budget for replacement.

		ELEC	CTR	CAL				
Main Panel		Location	n: Baseme	ent				
	Amps: 100 amps		Volts:12	0/240 volt	ts Pan	el Type: Brea	akers	
Appears grounded:	$\square$ Yes $\square$ No			□ Yes		Operates:		□ No
Main Wire:	Not visible							
Branch Wire:	Copper	pper						
	$\begin{tabular}{lllllllllllllllllllllllllllllllllll$					& tube		
	□ Multiple tapping □ Branch wires undersized □ Federal Pacific panel (see Remarks)							
	□ Multiple tapping of main disconnect □ Safety Hazard							
	□ Arc fault prese			s: 🗆	Yes 🗆 l	No 🗆 N/A	(see Ren	arks)
	$\Box$ Panel not accessible $\Box$ Not evaluated Reason:							
Sub Panel(s)								
Location 1: Basement A	Apartment L	ocation 2:			Loc	cation 3:		
	Panel not acce	ssible	🗆 Not e	valuated	Reason:			
Branch Wiring:	🗹 Copper	🗆 Alumi			er clad alı	ıminum		
	Neutral/ground se							
	Neutral isolated: $\Box$ Yes $\Box$ No $\Box$ Have electrician				an isolate			
	□ Multiple tapping □ Branch wires undersized □ Safety Hazard							
<b>Electrical Fixtures</b>								
A representative number	er of installed light	ng fixtures,	switches, a	and recept	acles loca	ted inside the	house, ga	rage, and
exterior walls were test		-						0
	☑ Satisfactory	🗆 Margir	nal	□ Poor				
			☑ GFCIs not operating □ Ungrounded 3-prong outlets				ong outlets	
□ Solid conductor aluminum branch wiring circuits (See Remarks page)								
□ Recommend a licensed electrician evaluate the service								
General Comments:								

Panel size appeared to be compatible to service size. Branch breaker distribution appeared normal. No signs of overheating were evident at the time of the inspection. Outlets were randomly tested and had correct polarity, except as noted. The basement is metered separately with its own 100 amp service. Front panel of the basement panel could not be removed as it is sealed (caulked in place) and the interior of the panel could not be reviewed.

## **PHOTOS**



Pic. 1: Front view



Pic. 2: Updated roof covering

Pic. 6: Chimney

Pic. 10: Garage



**Pic. 3: Basement entrance** 



Pic. 7: AC unit - 1997



Pic. 11: Junction box in garage needs a cover plate



Pic. 15: Master bedroom



Pic. 19: Bed 3





Pic. 27: Powder room



Pic. 4: Sump pump drain line - recommend extending away from foundation







Pic. 12: Homeowner / handyman wiring for light in garage



Pic. 16: Master bath







Pic. 24: Living room



Pic. 28: Powder room GFCI outlet needs repair / replacement





Pic. 9: Garagte



Pic. 13: Attic



Pic. 17: Master bath



Pic. 21: 2<sup>nd</sup> floor bath



Pic. 25: Dining room





Pic. 18: Bed 2



Pic. 22: 2<sup>nd</sup> floor bath



Pic. 26: Family room



Subject Property: 277 Worth Blvd, Thornhill, Ontario



Pic. 29: Laundry



Pic. 33: Basement kitchen



Pic. 37: Basement bath



Pic. 30: Basement living room



Pic. 34: Basement kitchen



Pic. 38: Basement bath



Pic. 31: Basement eating area



Pic. 35: Basement bed #1



Pic. 39: Basement bath shower head leaking at threads




Pic. 43: Gas furnace 2014



Page 27

Pic. 32: Basement kitchen







Pic. 40: Basement laundry



Pic. 41: Storage room



Pic. 45: Sump pump



Pic. 42: Rental hot water tank



Pic. 46: Main electrical panel 100 amp service



Pic. 44: Apartment electrical panel 100 amp service

## **GENERAL REMARKS**

### **GROUNDS REMARKS**

#### Service Walks/Driveways

Spalling concrete cannot be patched with concrete because the new will not bond with the old. Water will freeze between the two layers, or the concrete will break up from movement or wear. Replacement of the damaged section is recommended. Walks or driveways that are close to the property should be properly pitched away to direct water away from the foundation. Asphalt driveways should be kept sealed and larger cracks filled so as to prevent damage from frost.

**Patios** that have settled towards the structure should be mudjacked or replaced to assure proper pitch. Improperly pitched patios are one source of wet basements.

#### **Exterior Wood Surfaces**

All surfaces of untreated wood need regular applications of paint or special chemicals to resist damage. Porch or deck columns and fence posts which are buried in the ground and made of untreated wood will become damaged within a year or two.

Decks should always be nailed with galvanized or aluminium nails. Decks that are not painted or stained should be treated with a water sealer.

#### **Grading and Drainage**

Any system of grading or landscaping that creates positive drainage (moving water away from the foundation walls) will help to keep a basement dry. Where negative grade exists and additional backfill is suggested, it may require digging out around the property to get a proper pitch. Dirt shall be approximately 15 cm below the bottom sill and should not touch wood surfaces.

Flower beds, loose mulched areas, railroad ties and other such landscaping items close to the foundation trap moisture and contribute to wet basements. To establish a positive grade, a proper slope away from the house is 2.5 cm per meter for approximately 1.5 to 2 meters. Recommend ground cover planting or grass to foundation.

#### **Roof and Surface Water Control**

Roof and surface water must be controlled to maintain a dry basement. This means keeping gutters cleaned out and aligned, extending downspouts, installing splash blocks, and building up the grade so that roof and surface water is diverted away from the building.

#### Window Wells

The amount of water which enters a window well from falling rain is generally slight, but water will accumulate in window wells if the yard is improperly graded. Plastic window well covers are useful in keeping out leaves and debris.

#### **Retaining Walls**

Retaining walls deteriorate because of excessive pressure build-up behind them, generally due to water accumulation. Often, conditions can be improved by excavating a trench behind the retaining wall and filling it with coarse gravel. Drain holes through the wall will then be able to relieve the water pressure.

Retaining walls sometime suffer from tree root pressure or from general movement of topsoil down the slope. Normally, these conditions require rebuilding the retaining wall.

#### Railings

It is recommended that railings be installed for any stairway over 3 steps and porches over 75 cm for safety reasons. Balusters for porches, balconies, and stairs should be close enough to assure children cannot squeeze through.

### **ROOF COVERING REMARKS**

#### Valleys & Flashings

Valleys and flashings that are covered with shingles and/or tar or any other material are considered not visible and are not part of the inspection.

#### **Stone Roofs - Coverings**

This type of covering on a pitched roof requires ongoing annual maintenance. We recommend that a roofing contractor evaluate this type of roof. Infra-red photography is best used to determine areas of potential leaks.

#### Flat Roofs

Flat roofs are very vulnerable to leaking. It is very important to maintain proper drainage to prevent ponding of water. We recommend that a roofing contractor evaluate this type of roof.

ROOF TYPE	LIFE EXPECTANCY	SPECIAL REMARKS
Asphalt Shingles	15-20 years	Used on nearly 80% of all residential roofs; requires little maintenance
Asphalt Multi-Thickness Shingles*	20-30 years	Heavier and more durable than regular asphalt shingles
Asphalt Interlocking Shingles*	15-25 years	Especially good in high-wind areas
Asphalt Rolls	10 years	Used on low slope roofs
Built-up Roofing	10-20 years	Used on low slope roofs; 2 to 3 times as costly as asphalt shingles
Wood Shingles*	10-40 years <sup>1</sup>	Treat with preservative every 5 years to prevent decay
Clay Tiles* Cement Tiles*	20 + years 20 + years	Durable, fireproof, but not watertight, requiring a good subsurface base
Slate Shingles*	30-100 years <sup>2</sup>	Extremely durable, but brittle and expensive
Asbestos Cement Shingles*	30-75 years	Durable, but brittle and difficult to repair
Metal Roofing	15-40 + years	Comes in sheets & shingles; should be well grounded for protection from lightning; certain metals must be painted
Single Ply Membrane	15-25 years (mfgr's claim)	New material; not yet passed test of time

\* Not recommended for use on low slope roof <sup>1</sup> Depending on local conditions and proper installation <sup>2</sup> Depending on quality of slate

Roof covering should be visually checked in spring and fall for any visible missing shingles, damaged coverings or other defects. Before re-roofing, the underside of the roof structure and roof sheathing should be inspected to determine that the roof structure can support the additional weight of the shingles.

Wood shakes and shingles will vary in aging, due to quality of the material, installation, maintenance, and surrounding shade trees. Ventilation and drying of the wood material is critical in extending the life expectancy of the wood. Commercial preservatives are available on the market, which could be applied to wood to impede deterioration.

### **CHIMNEY / GUTTERS / SIDING / TRIM REMARKS**

#### Chimneys

Chimneys built of masonry will eventually need tuck pointing. A cracked chimney top that allows water and carbonic acid to get behind the surface brick/stone will accelerate the deterioration. Moisture will also deteriorate the clay flue liner. Periodic chimney cleaning will keep you apprised of the chimney's condition. The flashing around the chimney may need resealing and should be inspected every year or two. Fireplace chimneys should be inspected and evaluated by a chimney professional before using. Chimneys must be adequate height for proper drafting. Spark arrestors are recommended for wood burning chimney and chimney caps for fossil fuels

Unlined Chimney - should be re-evaluated by a chimney technician.

Have flue cleaned and re-evaluated. The flue lining is covered with soot or creosote and no representation can be made as to the condition.

## NOT EVALUATED- The flue was not evaluated due to inaccessibility such as roof pitch, cap, cleanout not accessible, etc.

#### **Cricket Flashing**

Small, sloped structure made of metal and designed to drain moisture away from a chimney. Crickets are usually placed at the back of a chimney.

#### **Gutters and Downspouts**

This is an extremely important element in basement dampness control. Keep gutters clean and downspout extensions in place (1.25 meters or more). Paint the inside of galvanized gutters, which will extend the life. Shortly after a rain or thaw in winter, look for leaks at seams in the gutters. These can be re-caulked before they cause damage to fascia or soffit boards. If no gutters exist, it is recommended that they be added.

#### Siding

Wood siding should not come in contact with the ground. The moisture will cause rotting to take place and can attract carpenter ants.

**EIFS** - This type of siding has experienced serious problems and requires a certified EIFS inspector to determine condition.

Brick and stone veneer must be monitored for loose or missing mortar. Some brick and stone are susceptible to spalling. This can be caused when moisture is trapped and a freeze/thaw situation occurs. There are products on the market that can be used to seal out the moisture. This holds true for brick and stone chimneys also.

Metal sidings will dent and scratch. Oxidation is a normal reaction in aluminum. There are good cleaners on the market and it is recommended that they be used occasionally. Metal siding can be painted.

#### **Doors and Windows**

These can waste an enormous amount of energy. Maintain the caulking around the frames on the exterior. Check for drafts in the winter and improve the worst offenders first. Windows that have leaky storm windows will usually have a lot of sweating. Likewise, well-sealed storms that sweat indicate a leaky window. It is the tighter unit that will sweat (unless the home has excess humidity to begin with.)

Wood that exhibits blistering or peeling paint should be examined for possible moisture sources: roof leaks, bad gutters, interior moisture from baths or laundry or from a poorly vented crawl space. Some paint problems have no logical explanation, but many are a symptom of an underlying problem. A freshly painted house may mask these symptoms, but after you have lived in the home for a year or two, look for localized paint blistering (peeling). It may be a clue.

New glazing will last longer if the raw wood is treated with boiled linseed oil prior to glazing. It prevents the wood from drawing the moisture out of the new glazing.

#### Caulking

Many different types of caulk are available on the market today. Check with a paint or hardware store for the kind of application you need.

### **EXTERIOR / ELECTRICAL / AC / GARAGE REMARKS**

#### **Exterior Doors**

The exposed side of wood exterior doors needs to be painted or stained and varnished to prevent discolouring and delamination. Weather-stripping is a must to prevent drafts.

#### Electrical

Overhead wires from the mast to the main panel that are exposed to the weather may fray and crack. If this occurs, wires should be replaced by a licensed electrician.

Any outdoor overhead service conductor wires should have adequate clearance above the ground (3 meters) and from balcony and windows (1 meter), for safety reasons.

Underground system - Some exterior boxes that are at ground level have a grade line on them. You should insure that the grade remains below this line to prevent moisture from entering the main panel.

#### **Overhead Door Openers**

We recommend that a separate electrical outlet be provided. Openers that do not have a safety reverse are considered a safety hazard. Small children and pets are especially vulnerable. We recommend the operating switches be set high enough so children cannot reach them. If an electric sensor is present, it should be tested occasionally to ensure it is working.

#### **Garage Sill Plates**

Sill plates within the garage should be elevated or treated lumber should be used. If this is not the case, try to direct water away to prevent rotting.

#### A/C Compressors

They should not become overgrown with foliage. Clearance requirements vary, but 60 cm on all sides should be considered minimal with up to 2 meters of air discharge desirable. If a clothes dryer vent is within five to ten feet, either relocate the vent or do not run when the A/C is running. The lint will quickly reduce the efficiency of the A/C unit.

#### **Burners**

Any appliance such as a water heater, furnace, etc. should have the flame a minimum of 45 cm above the floor. Any open flame less than 45 cm from the floor is a potential safety hazard. The appliance should also be protected from vehicle damage.

### **KITCHEN / LAUNDRY / UTILITY ROOM REMARKS**

#### **Plaster on Wood Lath**

Plaster on wood lath is an old technique and is no longer in general use. Wood lath shrinks with time and the nails rust and loosen. As a result, the plaster may become fragile and caution is needed in working with this type of plastering system. Sagging ceilings are best repaired by laminating drywall over the existing plaster and screwing it to the ceiling joists.

#### Plaster on Gypsum Lath (Rock Lath)

Plaster on gypsum lath will sometimes show the seams of the 40 cm wide gypsum lath, but this does not indicate a structural fault. The scalloping appearance can be levelled with drywall joint compound and fibreglass mesh joint tape or drywall can be laminated over the existing plaster on the ceiling.

#### Wood Flooring

Always attempt to clean wood floors first before making the decision to refinish the floor. Wax removers and other mild stripping agents plus a good waxing and buffing will usually produce satisfactory results. Mild bleaching agents help remove deep stains. Sanding removes some of the wood in the floor and can usually be done safely only once or twice in the life of the floor.

#### **Nail Pops**

Drywall nail pops are due to normal expansion and contraction of the wood members to which the drywall is nailed, and are usually of no structural significance.

#### Carpeting

Where carpeting has been installed, the materials and condition of the floor underneath cannot be determined.

#### Appliances

Dishwashers are tested to see if the motor operates and water sprays properly (full cycles are not run). Stoves are tested to see that burners are working and oven and broiler get hot. Timer and controls are not tested. Refrigerators are not tested.

No representation is made to continued life expectancy of any appliance.

#### Asbestos and Other Hazards

Asbestos fibres in some form are present in many homes, but are often not visible and cannot be identified without testing.

If there is reason to suspect that asbestos may be present and if it is of particular concern, a sample of the material in question may be removed and analyzed in a laboratory. *However, detecting or inspecting for the presence or absence of asbestos is not a part of our inspection.* 

Also excluded from this inspection and report are the possible presence of, or danger from, radon gas, lead-based paint, urea formaldehyde, toxic or flammable chemicals and all other similar or potentially harmful substances and environmental hazards.

#### Windows

A representative number of windows are inspected.

### **BATHROOM REMARKS**

#### Stall Shower

The metal shower pan in a stall shower has a potential or probable life of 10-20 years depending on quality of the pan installed. Although a visible inspection is made to determine whether a shower pan is currently leaking, it cannot be stated with certainty that no defect is present or that one may not soon develop. Shower pan leaks often do not show except when the shower is in actual use.

#### **Ceramic Tile**

Bathroom tile installed in a mortar bed is excellent. It is still necessary to keep the joint between the tile and the tub/shower caulked or sealed to prevent water spillage from leaking through and damaging the ceilings below.

Ceramic tile is often installed in mastic. It is important to keep the tile caulked or water will seep behind the tile and cause deterioration in the wallboard. Special attention should be paid to the area around faucets and other tile penetrations.

#### **Exhaust Fans**

Bathrooms with a shower should have exhaust fans where possible. This helps to remove excess moisture from the room, preventing damage to the ceiling and walls and wood finishes. The exhaust fan should not be vented into the attic. The proper way to vent the fans is to the outside. Running the vent pipe horizontally and venting into a gable end or soffit is preferred. Running the vent pipe vertically through the roof may cause condensation to run down the vent pipe, rusting the fan and damaging the wallboard. Insulating the vent pipe in the attic will help to reduce this problem.

SLOW DRAINS on sinks, tubs, and showers are usually due to build-up of hair and soap scum. Most sink pop-ups can be easily removed for cleaning. Some tubs have a spring attached to the closing lever that acts as a catch for hair. It may require removing a couple of screws to disassemble. If you cannot mechanically remove the obstruction, be kind to your pipes. Don't use a caustic cleaner. There are several bacteria drain cleaners available. They are available at hardware stores in areas where septic tanks are used. These drain cleaners take a little longer to work, but are safe for you and your pipes.

#### Safety Hazards

Typical safety hazards found in bathrooms are open grounds or reverse polarity by water. Replacing these outlets with G.F.C.I.'s are recommended. (See Electrical section)

#### Whirlpool Tubs

This relates to interior tubs hooked up to interior plumbing. Where possible, the motor will be operated to see that the jets are working. Hot tubs and spas are not inspected.

### **ROOMS (INTERIOR) REMARKS**

#### **Door Stops**

All swinging doors should be checked for door stops. Broken or missing door stops can result in door knobs breaking through drywall or plaster.

#### **Closet Guides**

Sliding closet doors should be checked to see that closet guides are in place. Missing or broken closet guides can cause scratches and damage to doors.

#### **Cold Air Returns**

Bedrooms that do not have cold air returns in them should have a 1.75 cm gap under the doors to allow cold air to be drawn into the hall return.

#### AN INSPECTION VERSUS A WARRANTY

A home inspection is just what the name indicates, an inspection of a home...usually a home that is being purchased. The purpose of the inspection is to determine the condition of the various systems and structures of the home. While an inspection performed by a competent inspection firm will determine the condition of the major components of the home, no inspection will pick up every minute latent defect. The inspector's ability to find all defects is limited by access to various parts of the property, lack of information about the property and many other factors. A good inspector will do his or her level best to determine the condition of the home and to report it accurately. The report that is issued is an opinion as to the condition of the home. This opinion is arrived at by the best technical methods available to the home inspection industry. It is still only an opinion.

A warranty is a policy sold to the buyer that warrants that specific items in the home are in sound condition and will remain in sound condition for a specified period of time. Typically, the warranty company never inspects the home. The warranty company uses actuarial tables to determine the expected life of the warranted items and charges the customer a fee for the warranty that will hopefully cover any projected loss and make a profit for the warranty seller. It is essentially an insurance policy.

The service that we have provided you is an inspection. We make no warranty of this property. If you desire warranty coverage, please see your real estate agent for details about any warranty plan to which their firm may have access.

### WINDOWS / FIREPLACES / ATTIC REMRKS

#### Window Frames and Sills

Window frames and sills often are found to have surface deterioration due to condensation that has run off the window and damaged the varnish. Usually this can be repaired with a solvent style refinisher and fine steel wool. This is sometimes a sign of excess humidity in the house.

See comments regarding caulking doors and windows above (Chimneys/Gutters/Siding).

#### **Fireplaces**

It is important that a fireplace be cleaned on a routine basis to prevent the build-up of creosote in the flue, which can cause a chimney fire.

Masonry fireplace chimneys are normally required to have a terra cotta flue liner or 8 inches of masonry surrounding each flue in order to be considered safe and to conform to most building codes.

During visual inspections, it is not uncommon to be unable to detect the absence of a flue liner either because of stoppage at the firebox, a defective damper or lack of access from the roof.

#### Wood burners

Once installed, it can be difficult to determine proper clearances for wood burning stoves. Manufacturer specifications, which are not usually available to the inspector, determine the proper installation. We recommend you ask the owner for paperwork verifying that it was installed by a professional contractor.

#### Ventilation

Ventilation is recommended at the rate of one square foot of vent area to 300 square feet of attic floor space, this being divided between soffit and rooftop. Power vents should ideally have both a humidistat and a thermostat, since ventilation is needed to remove winter moisture as well as summer heat. Evidence of condensation, such as blackened roof sheathing, frost on nail heads, etc. is an indication that ventilation may have been or is blocked or inadequate.

#### Insulation

The recommended insulation in the attic area is R-38, approximately 30cm. If insulation is added, it is important that the ventilation is proper.

#### Smoke Detectors

Smoke detectors should be tested monthly. At least one detector should be on each level.

#### Vapour Barriers

The vapour barrier should be on the warm side of the surface. Older homes were often built without vapour barriers. If the vapour barrier is towards the cold side of the surface, it should be sliced or removed. Most vapour barriers in the attic are covered by insulation and therefore, not visible.

#### Safety Glazing

Safety glazing requirements vary depending on the age of the home. Every attempt is made to identify areas where the lack of safety glazing presents an immediate safety hazard, such as a shower door. In some older homes it is difficult to determine if safety glazing is present, since the glass is not marked. Therefore, no representation is made that safety glazing exists in all appropriate areas.

#### **Insulated Glass**

The broken seals are not always detectable due to dirty windows, covered windows, etc. In most cases, leaking glass seals take some time before they are evident.

### **BASEMENT REMARKS**

#### Basement

Any basement that has cracks or leaks is technically considered to have failed. Most block basements have step cracks in various areas. If little or no movement has occurred, and the step cracks are uniform, this is considered acceptable. Horizontal cracks in the third or fourth block down indicate the block has moved due to outside pressure. They can be attributed to many factors, such as improper grading, improperly functioning gutter and downspout system, etc. Normally, if little or no movement has taken place and proper grading and downspouts exist, this is considered acceptable. If the wall containing the stress crack(s) has moved considerably, this will require some method of reinforcement. Basements that have been freshly painted or tuck-pointed should be monitored for movement. This will be indicated by cracks reopening. If cracks reappear, reinforcement may be necessary. Reinforcing a basement wall can become expensive.

#### Foundation (Covered Walls)

Although an effort has been made to note any major inflections or weaknesses, it is difficult at best to detect these areas when walls are finished off, or basement storage makes areas inaccessible. *No representation is made as to the condition of these walls.* 

**Monitor** indicates that the walls have stress cracks, but little movement has occurred. In our opinion, the cracks should be filled with mortar and the walls monitored for further movement and cracking. If additional movement or cracking occurs, re-enforcements may be necessary.

**Have Evaluated** — we recommend that the walls be re-evaluated by a structural engineer or basement repair company and estimates be obtained if work is required.

#### Vapour Barrier

Floors that are dirt or gravel should be covered with a vapour barrier.

#### **Moisture Present**

Basement dampness is frequently noted in houses and in most cases the stains, moisture or efflorescence present is a symptom denoting that a problem exists outside the home. Usual causes are improper downspout extensions or leaking gutters and/or low or improper grade (including concrete surfaces) at the perimeter of the house. A proper slope away from the house is one inch per foot for four to six feet.

Expensive solutions to basement dampness are frequently offered, and it is possible to spend thousands of dollars on solutions such as pumping out water that has already entered or pumping of chemical preparations into the ground around the house, when all that may be necessary are a few common sense solutions at the exterior perimeter. However, this is not intended to be an exhaustive list of causes and solutions to the presence of moisture. *No representation is made to future moisture that may appear.* 

#### **Palmer Valve**

Many older homes have a valve in the floor drain. This drain needs to remain operational.

#### **Drain Tile**

We offer no opinion about the existence or condition of the drain tile, as it cannot be visibly inspected.

#### **Basement Electrical Outlets**

We recommend that you have an outlet within 2 meters of each appliance. The appliance you plan to install may be different than what exists; therefore the inspection includes testing a representative number of receptacles that exist. It is also recommended to have ground fault circuit interrupts for any outlet in the unfinished part of the basement and crawl spaces.

### **PLUMBING REMARKS**

#### Wells

*Examination of wells is not included in this visual inspection.* It is recommended that you have well water checked for purity by the local health authorities and, if possible, a check on the flow of the well in periods of drought. A well pit should have a locked cover on it to prevent anyone from falling into the pit.

#### Septic Systems

*The check of septic systems is not included in our visual inspection.* You should have the local health authorities or other qualified experts check the condition of a septic system.

In order for the septic system to be checked, the house must have been occupied within the last 30 days.

#### Water Pipes

Galvanized water pipes rust from the inside out and may have to be replaced within 20 to 30 years. This is usually done in two stages: horizontal piping in the basement first and vertical pipes throughout the house later as needed.

Copper pipes usually have more life expectancy and may last as long as 60 years before needing to be replaced.

Polybutylene pipes are grey pipes that have a history of failure and should be examined by a licensed plumber.

#### **Hose Bibs**

During the winter months it is necessary to make sure the outside faucets are winterized. This can be done by means of a valve located in the basement. Leave the outside faucets open to allow any water standing in the pipes to drain, preventing them from freezing. Hose bibs cannot be tested when winterized.

#### Water Heater

The life expectancy of a water heater is 5-10 years. Water heaters generally need not be replaced unless they leak. It is a good maintenance practice to drain 5-10 gallons from the heater several times a year. *Missing relief valves or improper extension present a safety hazard.* 

#### Water Softeners

During a visual inspection, it is not possible to determine if water is being properly softened.

#### Plumbing

The temperature/pressure valve should be tested several times a year by lifting the valve's handle. Caution: very hot water will be discharged. If no water comes out, the valve is defective and must be replaced.

#### Shut-Off Valves

Most shut-off valves have not been operated for long periods of time. We recommend operating each shutoff valve to: toilet bowl, water heater, under sinks, main shut-off, hose faucets, and all others. We recommend you have a plumber do this, as some of the valves may need to be repacked or replaced. Once the valves are in proper operating order, we recommend opening and closing these valves several times a year.

#### **Polybutylene Piping**

This type of piping has a history of problems and should be examined by a licensed plumber and repaired or replaced as necessary.

MECHANICAL DEVICES MAY OPERATE AT ONE MOMENT AND LATER MALFUNCTION; THEREFORE, LIABILITY IS SPECIFICALLY LIMITED TO THOSE SITUATIONS WHERE IT CAN BE CONCLUSIVELY SHOWN THAT THE MECHANICAL DEVICE INSPECTED WAS INOPERABLE OR IN THE IMMEDIATE NEED OF REPAIR OR NOT PERFORMING THE FUNCTION FOR WHICH IS IT WAS INTENDED AT THE TIME OF INSPECTION.

### **HEATING SYSTEM REMARKS**

HEATING AND AIR CONDITIONING units have limited lives. Normal lives are:

GAS-FIRED HOT AIR15-25 years
OIL-FIRED HOT AIR
CAST IRON BOILER 30-50 years
(Hot water or steam) or more
STEEL BOILER 30-40 years
(Hot water or steam) or more
COPPER BOILER 10-20 years
(Hot water or steam)
CIRCULATING PUMP (Hot water) 10-15 years
AIR CONDITIONING COMPRESSOR8-12 years
HEAT PUMP8-12 years

Gas-fired hot air units that are close to or beyond their normal lives have the potential of becoming a source of carbon monoxide in the home. You may want to have such a unit checked every year or so to assure yourself that it is still intact. Of course, a unit of such an age is a good candidate for replacement with one of the new, high efficiency furnaces. The fuel savings alone can be very attractive.

Boilers and their systems may require annual attention. If you are not familiar with your system, have a heating contractor come out in the fall to show you how to do the necessary things. *Caution: do not add water to a hot boiler!* 

Forced air systems should have filters changed every 30 to 60 days of the heating and cooling season. This is especially true if you have central air conditioning. A dirty air system can lead to premature failure of your compressor - a \$1,500 machine.

Oil-fired furnaces and boilers should be serviced by a professional each year. Most experts agree you will pay for the service cost in fuel saved by having a properly tuned burner.

Read the instructions for maintaining the humidifier on your furnace. A malfunctioning humidifier can rust out a furnace rather quickly. It is recommended that the humidifier be serviced at the same time as the furnace, and be cleaned regularly. *During a visual inspection it is not possible to determine if the humidifier is working.* 

**Have HVAC Technician Examine** - A condition was found that suggests a heating contractor should do a further analysis. We suggest doing this before closing.

Heat exchangers cannot be examined nor their condition determined without being disassembled. Since this is not possible during a visual, non-technically exhaustive inspection, you may want to obtain a service contract on the unit or contact a furnace technician regarding a more thorough examination.

Testing pilot safety switch requires blowing out the pilot light. Checking safety limit controls requires disconnecting blower motor or using other means beyond the scope of this inspection. If furnace has not been serviced in last 12 months, you may want to have a furnace technician examine.

**CO Test** - This is not part of a non-technical inspection.

**Combustible Gas Test (Potential Safety Hazard)** - If a combustible gas detector was used during the inspection of the furnace and evidence of possible combustible gases was noted, we caution you that our test instrument is sensitive to many gases and not a foolproof test. None-the-less, this presents the <u>possibility</u> that a hazard exists and could indicate that the heat exchanger is, or will soon be, defective.

### **COOLING SYSTEM / ELECTRICAL REMARKS**

#### Electrical

Every effort has been made to evaluate the size of the service. Three wires going into the home indicate 240 volts. The total amps are sometimes difficult to determine. We highly recommend that ground fault circuit interrupters (G.F.C.I.) be connected to all outlets around water. This device automatically opens the circuit when it senses a current leak to ground. This device can be purchased in most hardware stores. G.F.C.I.'s are recommended by all outlets located near water, outside outlets, or garage outlets. Pool outlets should also be protected with a G.F.C.I.

The G.F.C.I. senses the flow of electricity through a circuit. If more current is flowing through the black ("hot") wire than the white ("neutral") wire, there is a current leakage. The G.F.C.I., which can sense a ground leak of as little as .005 amps, will shut off the current in 1/40 of a second, which is fast enough to prevent injury.

If you do have G.F.C.I.'s, it is recommended that you test (and reset) them monthly. When you push the test button, the reset button should pop out, shutting off the circuit. If it doesn't, the breaker is not working properly. If you don't test them once a month, the breakers have a tendency to stick, and may not protect you when needed.

Knob and tube wiring found in older homes should be checked by an electrician to insure that the wire cover is in good condition. Under no circumstances should this wire be covered with insulation. Recess light fixtures should have a baffle around them so that they are not covered with insulation. The newer recessed fixtures will shut off if they overheat.

Federal Pacific electrical panels may be unsafe. See www.google.com and search for "Federal Pacific" for additional and up-to-date information.

Aluminum wiring in general lighting circuits has a history of overheating, with the potential of a fire. If this type of wiring exists, a licensed electrical contractor should examine the whole system.

#### Arc Faults

In some areas, arc faults are required in new homes, starting in 2002. These control outlets in the bedrooms.

#### **Reverse Polarity**

A common problem that surfaces in many homes is reverse polarity. This is a potentially hazardous situation in which the hot and neutral wires of a circuit are reversed at the outlet, thereby allowing the appliance to incorrectly be connected. This is an inexpensive item to correct.

Each receptacle has a brass and silver screw. The black wire should be wired to the brass screw and the white wire should go to the silver screw. When these wires are switched, this is called "reverse polarity". Turning off the power and switching these wires will correct the problem.

Main service wiring for housing is typically 240 volts. The minimum capacity for newer homes is 100 amps, though many older homes still have 60 amp service. Larger homes or all electric homes will likely have a 200 amp service.

Main service wiring may be protected by one or more circuit breakers or fuses. While most areas allow up to six main turnoffs, expanding from these panels is generally not allowed.

#### Cooling

**Testing A/C System and Heat Pump** - The circuit breakers to A/C should be on for a minimum of 24 hours and the outside temperature at least 15 ° C for the past 24 hours or an A/C system cannot be operated without possible damage to the compressor. Check the instructions in your A/C manual or on the outside compressor before starting up in the summer. Heat pump can only be tested in the mode it's running in. Outside temperature should be at least 15 ° C for the past 24 hours to run in cooling mode.

Temperature differential, between 7°-15°, is usually acceptable. If out of this range, have an HVAC contractor examine it. It is not always feasible to do a differential test due to high humidity, low outside temperature, etc.