CITY WIDE HOME INSPECTORS

PRE-LISTING HOME INSPECTION REPORT



53 Gianmarco Way, Maple, Ontario

Report Number :	19085630
Inspection Date:	2019-08-07
Prepared by:	City Wide Home Inspectors
	PO Box 325
	Tottenham, Ontario, L0G 1W0
Phone:	(416)203-0333
Toll Free :	1-877-203-0474
Website:	www.citywidehomeinspectors.com
Inspector:	Michael Fournier
Email:	info@citywidehomeinspectors.com

Copyright © 2019 2061490 Ontario Inc. o/a City Wide Home Inspectors

Subject Property: 53 Gianmarco Way, Maple, Ontario

City Wide Home Inspectors PO Box 325 Tottenham, Ontario, LOG 1W0 Office: (416)203-0333 Toll free: 1-877-203-0474 info@citywidehomeinspectors.com www.citywidehomeinspectors.com



August 11, 2019

Inspection Address: 53 Gianmarco Way, Maple, Ontario Report Number: 19085630

At your request, an inspection of the above property was performed on 2019-08-07. **City Wide Home Inspectors** is pleased to submit the enclosed report. This report is a professional opinion based on a visual inspection of the accessible components of the home. This report is not an exhaustive technical evaluation. An evaluation of this nature would cost many times more.

Please understand that there are limitations to this inspection. Many components of the home are not visible during the inspection and very little historical information is provided in advance of the inspection. While we can reduce your risk of purchasing a home, we cannot eliminate it, nor can we assume it. Even the most comprehensive inspection cannot be expected to reveal every condition you may consider significant to ownership. In addition to those improvements recommended in our report, we recommend that you budget for unexpected repairs. On average, we have found that setting aside roughly one percent of the value of the home on an annual basis is sufficient to cover unexpected repairs.

The Standards of Practice prohibits us from making any repairs or referring any contractors. We are not associated with any other party to the transaction of this property, except as may be disclosed to you.

The information provided in this report is solely for your use. **City Wide Home Inspectors** will not release a copy of this report without your written consent.

Thank you for selecting our company. We appreciate the opportunity to be of service. Should you have any questions about the general condition of the house in the future, we would be happy to answer these. There is no fee for this telephone or email consulting. Our fees are based on a single visit to the property. If additional visits are required for any reason, additional fees may be assessed.

Sincerely,

Michael Fournier, Owner City Wide Home Inspectors Certified Master Inspector, CMI Certified Mould Inspector, IAC2 Certified Commercial Property Inspector, CCPI Certified Infrared Camera Property Inspector, CICPI

Page 2

BUILDING DATA

BUILDING DATA

Approximate Age:15Building Type:FrBuilding Style:TvGeneral Appearance:SaMain Entrance Faces:FoWeather Condition:ChTemperature:20Ground cover:DrOccupancy:Occupancy:

15 to 20 yrs Freehold Townhouse Two Story Satisfactory For the sake of this report North Cloudy 20 to 30 C Dry Occupied

REPORT LIMITATIONS

This report is intended only as a general guide to help the client make his own evaluation of the overall condition of the home, and is not intended to reflect the value of the premises, nor make any representation as to the advisability of purchase. The report expresses the personal opinions of the inspector, based upon his visual impressions of the conditions that existed at the time of the inspection only. The inspection and report are not intended to be technically exhaustive, or to imply that every component was inspected, or that every possible defect was discovered. No disassembly of equipment, opening of walls, moving of furniture, appliances or stored items, or excavation was performed. This inspection is a limited visual examination of the readily accessible systems and components of the home only.

This inspection is conducted in compliance with the standards of practice of the International Association of Certified Home Inspectors (Inter-NACHI), a copy of which is available at <u>www.citywidehomeinspectors.com/sop</u>.

Systems and conditions which are not within the scope of the building inspection include, but are not limited to: pools spas or their related equipment, formaldehyde, lead paint, asbestos, toxic or flammable materials, and other environmental hazards; pest infestation, playground equipment, efficiency measurement of insulation or heating and cooling equipment, internal or underground drainage or plumbing, any systems which are shut down or otherwise secured; water wells (water quality and quantity) zoning ordinances; intercom; security systems; heat sensors; central vacuum systems, cosmetics or building code conformity. Any general comments about these systems and conditions are informational only and are not within the scope of this inspection.

The inspection report should not be construed as a compliance inspection of any governmental or non-governmental codes or regulations. The report is not intended to be a warranty or guarantee of the present or future adequacy or performance of the structure, its systems, or their component parts. This report does not constitute any express or implied warranty of merchantability or fitness for use regarding the condition of the property and it should not be relied upon as such. Any opinions expressed regarding adequacy, capacity, or expected life of components are general estimates based on information about similar components and occasional wide variations are to be expected between such estimates and actual experience. We recommend that any deficiencies noted in this report be repaired or corrected after consultation with reputable qualified contractors. It is suggested that more than one quote be obtained before commencing with repairs.

The sellers' property information sheet (SPIS) may be referred to in this document. This item is a statement that is often completed by the seller regarding the condition of the subject property. The buyer is urged to obtain and review this document, if available, as it contains crucial information. Photographs, taken at the time of this inspection, are to be considered part of this inspection report.

We certify that our inspectors have no interest, present or contemplated, in this property or its improvement and no involvement with tradespeople or benefits derived from any sales or improvements. To the best of our knowledge and belief, all statements and information in this report are true and correct.

We assume no liability for the cost of repair or replacement of unreported defects or deficiencies either current or arising in the future. You agree that in all cases our liability shall be limited to liquidated damages in an amount not greater than the fee you paid us. You waive any claim for consequential, exemplary, special or incidental damages or for the loss of the use of the home/building. You acknowledge that the liquidated damages are not a penalty, but that we intend them to (i) reflect the fact that actual damages may be difficult and impractical to ascertain; (ii) allocate risk between us; and (iii) enable us to perform the inspection for the agreed upon fee.

Should any disagreement or dispute arise as a result of this inspection or report, it shall be decided by arbitration and shall be submitted for binding, non-appealable arbitration unless the parties mutually agree otherwise. In the event of a claim, the Client will allow City Wide Home Inspectors to inspect the claim prior to any repairs or waive the right to make the claim. Client agrees not to disturb or repair or have repaired anything which may constitute evidence relating to the complaint, except in the case of an emergency.

Report Table of Contents

BUILDING DATA	3
	4
SUMMARY*	6
GROUNDS	7
ROOF COVERING	8
CHIMNEY / GUTTERS / SIDING / TRIM	9
EXTERIOR / ELECTRICAL / AC / GARAGE	
KITCHEN	11
LAUNDRY / UTILITY ROOM	11
BATHROOMS	
INTERIOR ROOMS	14
WINDOWS / FIREPLACES / ATTIC	16
BASEMENT	17
PLUMBING	
COOLING SYSTEM	
ELECTRICAL	
PHOTOS	21
GENERAL REMARKS	23



ITEMS NOT OPERATING

Basement bathroom exhaust fan not pulling air

MAJOR CONCERNS

None

POTENTIAL SAFETY HAZARDS

Dryer vent line needs cleaning No CO detector on 2nd floor

DEFERRED COST ITEMS

Items that have reached or are reaching their normal life expectancy or show indications that they may require repair or replacement <u>anytime during the next five (5) years</u>.

Smoke detector over 5 years old

* Items listed in this report may inadvertently have been left off the Summary Sheet. Customer should read the entire report, including the Remarks.

DEFINITIONS

SATISFACTORY (Sat.) - Indicates the component is functionally consistent with its original purpose but may show signs of normal wear and tear and deterioration.

MARGINAL(Marg.) - Indicates the component will probably require repair or replacement anytime within five years.

POOR - Indicates the component will need repair or replacement now or in the very near future.

MAJOR CONCERNS - A system or component that is considered significantly deficient or is unsafe.

SAFETY HAZARD - Denotes a condition that is unsafe and in need of prompt attention.

	GROUNDS							
Service Walks		☑ None	□ Public sidev	walk needs repair				
	□ Concrete	□ Flagstone	□ Brick	Other				
Condition:	□ Satisfactory	□ Marginal	□ Poor	🗆 Trip Hazard				
	□ Pitched towards hom	e \Box Settling cracks	\Box Not visible					
Driveway		□ None						
	□ Concrete	🗹 Asphalt	□ Gravel	□ Other				
Condition:	✓ Satisfactory	□ Marginal	□ Poor	🗆 Trip hazard				
	□ Fill cracks and seal	\Box Pitched towards hom	$\square Settling crack$	\square Not visible				
Patio/Lanai		☑ None						
		Flagstone 🗆 Brick						
Condition:	□ Satisfactory	□ Marginal	Poor	🗆 Trip Hazard				
	□ Pitched towards hom	e (See Remarks page)	□ Settling crack	\Box Not visible				
Deck		\Box None \blacksquare Wo						
	□ Treated	□ Painted/Stained	-	sters recommended				
Condition:	□ Satisfactory	☑ Marginal	□ Poor	\Box Not visible				
Deck/Patio/Por	ch Covers	☑ None □ Ear	th to wood contact	□ Moisture/insect damage				
Lacks:	□ Metal straps/bolts/nat	ils 🗆 Impr	oper attachment to l	house				
Porch (covered	entrance)	☑ None	□ Railing/bal	usters recommended				
Support Pier:	□ Wood	□ Concrete	□ Other	□ Not visible				
Condition:	□ Satisfactory	□ Marginal	□ Poor					
Floor:	□ Satisfactory	□ Marginal	□ Poor	□ Safety Hazard				
Balcony (2nd fl		☑ None □ Wo	ood 🛛 Metal	□ Other				
Railing:	\Box Yes	□ No	🗆 Railing/balu	sters recommended				
Condition:	□ Satisfactory	□ Marginal	\Box Poor	🗆 Safety Hazard				
Stoops/Steps		□ None	Uneven rise	ers 🗆 Safety Hazard				
	☑ Concrete	□ Wood	□ Other	Railing recommended				
Condition:	☑ Satisfactory	Marginal	□ Poor	□ Recommend baluster				
	□ Cracked	□ Settled	□ Damaged wo	od				
Fencing		□ None	□ Туре:	☑ Not evaluated				
Landscaping Af	fecting Foundation	(See Remarks page)						
Negative grade at:		□ North □ South	☑ Satisfactory					
0 0	□ Recommend addition	al backfill	•	window wells/covers				
	□ Trim back trees/shrut	oberies		tact/too close to soil				
	□ Yard drains observed	- not tested	\Box N/A					
Retaining Wall		□ Yes	☑ No					
	□ Concrete	□ Wood	□ Other	🗆 Safety Hazard				
Visual Condition:		□ Marginal	□ Poor	·				
Hose Bibs		☑ Yes	□ No	□ No anti-siphon valve				
Operates:	🗹 Yes	□ No	\Box Not tested	\Box Not on				
General Comm	nents							

Fencing is not part of a home inspection. General site drainage was properly sloping away from the house. Maintain a positive drainage slope away from the foundation. Rear deck is sagging at the outside corner, recommend review and repair as necessary.

ROOF COVERING

General Inform	nation					
Roof Visibility		All				
Inspected Fro	m	Ground with b	oinoculars			
Style of Roof						
	bination: 🗹 Gable	□ Hip	□ Mansard	\Box Shed \Box I	Flat 🛛 Othe	r
	bination: \Box Low	\square Medium		\Box Flat		•
Roof Covering	Y		-			
Type: Asphalt	Estimated Lay	ers: 1 laver	Approx	imate age of cover:	1 to 5 yrs	
i ype. Asphan	Estimated East		пррох	iniate age of cover.	1 to 5 yis	
Ventilation Sys						
Combination:	☑ Soffit	□ Ridge		□ Gable	🗹 Roof	
	□ Powered	\Box Eaves		□ Other		
Flashing Mate						
Combination: 🗹 Galv./Aluminum		□ Asphalt	🗆 Lea	d 🗆 Rubb	er 🗆 Not v	visible
	□ Copper	□ Other				
Valley Materia						
Combination:	☑ Galv./Aluminum	\square Asphalt		□ Copper	□ N/A	
	\Box Not visible	□ Other				
	dition of the Following a					
Roof Covering		☑ Satisfac	tory	□ Marginal	\Box Poo	or
Condition:	Curling	□ Cupping		□ Missing tabs/shingles/tiles		a .
	□ Moss Buildup □ Exposed Felt	□ Nail Popp □ Other	ping	□ Ponding	Spots	
						
Ventilation		(See Rema	arks page)	(See Attic page)		
Flashings		□ Not visi	ble 🗹 S	atisfactory	Marginal [□ Poor
- 1	Rusted		end Sealing	\Box Pulled away from	U	
Valleys		☑ Satisfac	torv	□ Marginal)r
	□ Not visible	$\Box N/A$	lory	\Box Rusted	_ 100	-
	□ Holes	🗆 Recomm	end Sealing			
Skylights		□ Yes	🗹 No	□ Satisfactory	□ Marginal	□ Poor
		-		-	-	
Plumbing Ven	ts	☑ Yes	□ No	☑ Satisfactory	\Box Marginal	\Box Poor
0						
General Comr	nents					

Roof covering appeared in overall satisfactory condition at the time of the inspection.

	$\square \mathbf{N}_{i} = \mathbf{I}_{i} = \mathbf{I}_{i} = \mathbf{I}_{i} = \mathbf{I}_{i}$	
CHIMNEY /	GUTTERS / SIDING /	TRIM

Chimney(s)		□ None	Location(s):		
Viewed from:	□ Roof	□ Ladder at	eaves	Ground w/binocu		
Chase:	\Box Brick \Box Stone	□ Metal	🗆 Fram	ed 🛛 Blocks	□ Stucco	
	Evidence of: \Box Cra	cked chimney c	ap 🛛 Loose	e mortar joints	\Box Loose brick	
		es in metal	🗆 Rust	🗆 Flaking		
Flue:	\Box Tile \Box Me		□ Unlined	□ Not visible	e	
	Evidence of: \Box Sca	0	□ Cracks	□ Creosote		
		ve flue(s) cleaned			ted (See Remarks page)	
□ Recommend c	ricket/saddle flashing		\Box Spark arre	estor/rain cap recomm	nended	
Gutters & Dow	nspouts	□ None	(See Rem	arks page)		
□ Insides need to	b be cleaned	Ponding				
	☑ Galvanized/Alum.	□ Copper		□ Vinyl	□ Other	
Condition:	☑ Satisfactory	Marginal		□ Poor	□ Rusting	
	□ Hole in main run		Leaking: Corners Doin			
Extension needed:	□ North	□ South □ East □ West				
Siding						
Material:	Brick					
Condition:	☑ Satisfactory	\Box Marginal	□ Poor		end repair/painting	
Window Frame	es					
Material:	Vinyl					
Condition:	☑ Satisfactory	Marginal		□ Poor		
	□ Recommend painting	Ş	🗆 Dama	aged wood		
Trim, Soffit, Fa	ascia					
Trim Material:	Metal	Condition: Sa	atisfactory			
Soffit Material:	Metal	Condition: Sa	atisfactory			
Fascia Material:	Metal	Condition: Sa	atisfactory			
Caulking						
Condition:	☑ Satisfactory	□ Marginal		□ Poor		
	Recommend around		masonry ledg	es/corners/utility per	netrations	
General Comm	nents					

Gutters were in overall adequate condition. Siding appeared to be in overall adequate condition. Trim appeared to be intact and in overall maintained condition.

Subject Property: 53 Gianmarco Way, Maple, Ontario

EXTERIOR / ELECTRICAL / AC / GARAGE

Exterior Wall C	onstruction						
Construction Style		Z Satist	factory \Box M	larginal	□ Poor		
Exterior Doors			🗹 Entrar	nce (1);	Storm (2);	Patio (3)	
Weather stripping:	🗹 Satisfactory		🗆 Margin	al	ΠI	Poor	
Condition:	☑ Satisfactory		□ Margin	al	Πŀ	Poor	
Exterior Electri	cal Service						
	□ Overhead	🗹 Un	derground	Servi	ce drop:	□ Satisfactor	\square Needs service
Exterior outlets:	🗹 Yes	🗆 No		Oper	ate:	🗹 Yes	\Box No
GFCI protected:	☑ Yes	🗆 No		Oper	ate:	🗹 Yes	\Box No
Reverse polarity:	\Box Yes	🗹 No		Open	ground:	\Box Yes	☑ No
Overhead wires:	□ Low □	Less th	han 1 meter fi	rom balc	ony/deck/w	indow 🛛 Extens	sion cord/exposed Romex
Potential safety	hazard:	\Box Yes	8	🗹 No) (Se	e Remarks page	.)
A/C Condenser/	Heat Pump		□ None	Approx	imate age: 1	to 3 yrs	
#1 Brand: Rheen	n						Shutoff: No
Condition:	☑ Satisfactory	□ Ma	rginal 🛛	Poor	🗆 Ruste	ed/dirty Lev	vel: 🗹 Yes 🛛 No
Garage							
Garage Type:	Attached	Garag	ge Size: Sing	gle Car			
Automatic open							
Floor:	Concrete		□ Gravel		\Box A	Asphalt	□ Dirt
	Burners less than	45 cm a	above garage f	loor:	☑N/A □ `	Yes 🛛 No	□ Safety hazard
	Condition:	🗹 Sat	isfactory			s 🛛 Large settl	ing cracks
Overhead door:	□ Wood	🗆 Fib	erglass	\Box Ma	asonite	🗹 Metal	□ Other
	Condition:	🗹 Sat	isfactory	\Box Ma	arginal	\Box Poor \Box	Repair, replace, paint
Service door:	☑ Satisfactory	🗆 Ma	rginal	🗆 Po	or	□ None	
Sill plates:	□ Elevated	🗆 Flo	or level	🗆 Bo	oth	🗹 Not visible	e \Box Rotted
Electricity prese	ent: 🗹 Yes	🗆 No	GFCI Pro	otected:	□ Yes	🗹 No 👘 Opera	ates: 🗹 Yes 🗆 No
	Reverse polarity/c	pen gro	ound: 🛛 Yes	🗆 Sa	fety Hazar		Handyman/ext. cord wiring
Firewall:	(Between garage			∃N/A	⊠ I	Present 🗆 1	Missing Damaged
Fire door:	□ Not verifiable	□ No	t a fire door	🗆 Ne	eds repair	☑ Satisfactor	У
Auto closure:	\Box N/A	🗹 Sat	isfactory			ative	ing
General Comm	nents						

Doors were reviewed and found to be in working order. Lights appeared to be in normal condition: not all lights were tested. Exterior outlets tested were in normal working order.

Countertops			☑ Satis	sfactory	□ Marginal		D Poor	r
Cabinets								
Condition:	☑ Satisfactory		🗆 Margi	nal C	Poor		□ Recommend repairs	
Plumbing Con	nments							
Faucet leaks:	□ Yes	☑ No		Pipes leak/corrode	ed: 🗆 Yes		🗹 No	
Drainage:	Adequate 🗹	□ Poo	or	Water pressure:	☑ Ade	quate	□ Poor	
Walls & Ceiling	g							
Condition	☑ Satisfactory	□ Ma	rginal	□ Poor	🗆 Турі	ical cracks	□ Moist	ure stains
Heat Source P	resent		🗹 Yes	□ No				
Floor								
Condition	☑ Satisfactory	□ Ma	rginal	D Poor	□ Slop	ing	□ Squea	ıks
Appliances			(See Re	emarks page)				
Dishwasher:	🗹 Yes	□ No		Operates:	🗹 Yes		🗆 No	\Box N/A
Range:	🗹 Yes	🗆 No		Operates:	🗹 Yes		🗆 No	□ N/A
Oven:	🗹 Yes	🗆 No		Operates :	🗹 Yes		🗆 No	\Box N/A
Exhaust fan:	🗹 Yes	🗆 No		Operates :	🗹 Yes		🗆 No	\Box N/A
Refrigerator:	🗹 Yes	🗆 No		Operates :	🗹 Yes		🗆 No	\Box N/A
Other:	□ Yes	□ No		Operates:	\Box Yes		□ No	\Box N/A
Electrical								
Outlets present:	🗹 Yes	□ No		Operates :	🗹 Yes		🗆 No	
GFCI protected:	□ Yes	🗹 No		Operates:	□ Yes		🗆 No (F	Remarks)
	erse polarity with	in 1 me	ter of water:	\Box Yes \Box Saf	ety Hazard	🗹 No		·
General Comm	nents:							

KITCHEN

Counter top has normal wear. Cabinets have normal wear. Water flow was normal with several fixtures operated at the same time. There were no visible active piping leaks at the time of the inspection. Drain lines had no visible leaks or signs of backup at the time of inspection. Outlets were randomly tested and had correct polarity, except as noted.

LAUNDRY / UTILITY ROOM

Room Components							
Laundry sink:	\Box N/A	Faucet leaks:	□ Yes	🗆 Yes 🛛 No		🗆 Yes 🗹 No	
Cross connections:	□ Yes	☑ None apparent	Heat source	☑ Yes	□ No		
Room appears vented:	□ Yes	⊠ No	🗆 Not visi	ble			
Dryer vented:	\Box N/A	🗹 Wall	☑ Wall □ Ceiling □ Not vented				
Electrical: Open ground	/reverse pola	rity within 1 meter of w	/ater: 🗆 Y	les 🗆 Saf	ety Hazard	🗹 No	
Appliances present:	🗹 Washer	Dryer	🗹 Water h	eater 🗹	I Furnace	□ Other	
Gas pipe:	⊠ N/A	Valve shutoff:	□ Yes	□ No □	Cap Needed	🗆 Safety Hazard	
General Comments							

At the time of the inspection the laundry facilities were in satisfactory condition. Dryer vent line needs to be cleaned.

BATHROOMS										
Bath: Master Bedroom										
Sinks	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No				
Tubs	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No				
Showers	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No				
Toilet:	Bowl loose	□ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	□ No □ Cracked b	owl 🛛 Toilet leaks				
Whirlpool:		□ Yes	🗹 No	<i>Operates</i> : \Box Yes	□ No					
Shower/Tub area	1:	🗹 Cera	amic/Plastic	□ Fiberglass	□ Masonite	□ Other				
	Condition: 🗹 Satisf			□ Marginal	□ Poor	□ Rotted floors				
	Caulk/Grouting 1	needed:	□ Yes	☑ No	Where:					
Drainage:	☑ Satisfactory		🗆 Margin	al	□ Poor					
Water flow:	☑ Satisfactory		🗆 Margin	al	□ Poor					
Moisture stains p	oresent: 🗆 Yes	🗆 Wal	ls 🛛 Ceiling	s 🗹 No						
Outlets present:	☑ Yes □	No	GFCI protec	ted: 🗹 Yes 🗆 No	Operates: 🗹 Y	es 🗆 No				
	Open ground/rev	erse pol	arity within 1 i	meter of water:	🗆 Yes 🛛 No					
	Potential safety	hazards	s present:	□ Yes ☑ No (Se	e Remarks page)					
Heat source pres	ent: 🗹	Yes		□ No						
Exhaust fan:	☑ Yes □	No	Operates:	🗹 Yes	\Box No \Box Nois	у				
Windows:	☑ Sat. □ Marg.	D Poo	r 🛛 Cracked g	glass 🗆 None 🗆 Ev	vidence of leaking in	sulated glass				
Door:	☑ Sat. □ Marg.	D Poo	r □ Holes □	Does not latch \Box H	Hardware broken □] None				
General Comn	nents									

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted.

Bath: Second f	iloor						
Sinks	Faucet leaks:	□ Yes	s 🗹 No		Pipes leak	\Box Yes \square No	
Tubs	Faucet leaks:	□ Yes	s 🗹 No		Pipes leak	: \Box Yes \blacksquare No	
Showers	Faucet leaks:	\Box Yes	s 🗹 No		Pipes leak	\Box Yes \square No	
Toilet:	Bowl loose	□ Yes	s 🗹 No	<i>Operates</i> : 🗹 Yes	\Box No \Box (Cracked bowl 🛛 Toilet leaks	
Whirlpool:		□ Yes	s 🗹 No	<i>Operates</i> : \Box Yes	□ No		
Shower/Tub area	:	🗹 Cer	amic/Plastic	□ Fiberglass	🗆 Masoni	te 🛛 Other	
	Condition:	🗹 Sat	isfactory	□ Marginal	□ Poor	\Box Rotted floors	
	Caulk/Grouting	needed:	\Box Yes	🗹 No	Where:		
Drainage:	☑ Satisfactory		🗆 Margin	al	Poor		
Water flow:	☑ Satisfactory		□ Marginal □ Poor				
Moisture stains p	resent: 🗆 Yes	🗆 Wa	lls 🛛 Ceiling	s 🗹 No			
Outlets present:	⊠ Yes □] No	GFCI protec	ted: 🗹 Yes 🗆 No	<i>Operat</i>	es: 🗹 Yes 🗆 No	
	Open ground/re	verse po	larity within 1 i	meter of water:	□ Yes	🗹 No	
	Potential safety	/ hazard	s present:	□ Yes 🗹 No (Se	e Remarks	page)	
Heat source prese	ent: 🔽	1 Yes		□ No			
Exhaust fan:	⊠ Yes □] No	Operates :	🗹 Yes	🗆 No	□ Noisy	
Windows:	□ Sat. □ Marg	. 🗆 Poc	or 🛛 Cracked g	glass 🗹 None 🗆 Ev	idence of le	aking insulated glass	
Door:	🗹 Sat. 🗆 Marg	. 🗆 Poo	or \Box Holes \Box	Does not latch \Box H	Hardware br	oken 🗆 None	
General Comm	nents						

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted.

Bath: Main floo	or									
Sinks	Faucet 1	leaks:	□ Yes	🗹 No			Pipes leal	k:	□ Yes	🗹 No
Toilet:	Bowl lo	ose	\Box Yes	🗹 No	Operates :	🗹 Yes	□ No □ Cracked bowl □ Toilet leaks			oilet leaks
Drainage:	☑ Satis	factory		□ Marginal		□ Poor				
Water flow:	☑ Satis	factory		🗆 Margii	nal		□ Poor			
Moisture stains p	resent:	□ Yes	□ Wall	ls 🛛 Ceiling	gs ⊠No					
Outlets present:	🗹 Yes	🗆 No	GFCI p	rotected:	🗹 Yes	🗆 No	Operates	:	🗹 Yes	\Box No
	Open gr	round/rev	erse pola	arity within 6 ³	of water:	□ Yes	🗹 No			
	Potenti	al safety	hazards	present:	□ Yes	🗹 No	(See Rem	iarks pag	e)	
Heat source prese	ent:		🗹 Yes		□ No					
Exhaust fan:	🗹 Yes		No	Operates:	🗹 Yes		🗆 No	🗆 Noisy	у	
Windows:	□ Sat.	□ Marg.	□ Poor	Cracked	glass 🗹 Noi	ne 🗆 Evi	dence of le	aking insu	ulated gla	SS
Door:	☑ Sat.	□ Marg.	□ Poor	\Box Holes \Box	Does not la	tch 🗆 H	Hardware b	oroken 🗆	None	
General Comm	nents									

At the time of the inspection, the bathroom and its components were found to be in satisfactory condition except as noted.

Bath: Baseme	nt					
Sinks	Faucet leaks:	□ Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Showers	Faucet leaks:	\Box Yes	🗹 No		Pipes leak:	🗆 Yes 🗹 No
Toilet:	Bowl loose	□ Yes	🗹 No	<i>Operates</i> : 🗹 Yes	\Box No \Box Cracked b	owl 🛛 Toilet leaks
Shower area:	Ceramic/Plast	ic	□ Fibergla	ass	□ Masonite	□ Other
	Condition:	☑ Satisfac	tory	□ Marginal	□ Poor	□ Rotted floors
	Caulk/Grouting 1	needed:	□ Yes	☑ No	Where:	
Drainage:	Satisfactory		□ Margina	al	□ Poor	
Water flow:	☑ Satisfactory		□ Margina	al	□ Poor	
Moisture stains p	resent: 🗆 Yes	□ Walls	□ Ceiling	s 🗹 No		
Outlets present:	☑ Yes □	No G	FCI protec	ted: 🗆 Yes 🗹 No	Operates: 🗹 Y	es 🗆 No
	Open ground/rev	· ·	•	neter of water:	🗆 Yes 🛛 No	
	Potential safety	hazards pr	esent:	\Box Yes \boxdot No (See	e Remarks page)	
Heat source prese	ent: 🗹	Yes		🗆 No		
Exhaust fan:	☑ Yes □	No O	perates:	☑ Yes	🗹 No 🛛 🗆 Noisy	ý
Windows:	\Box Sat. \Box Marg.	□ Poor □	Cracked g	lass 🗹 None 🗆 Evi	dence of leaking ins	ulated glass
Door:	\square Sat. \square Marg.	\Box Poor \Box	Holes	Does not latch \Box H	Iardware broken	None
General Comm	nents					

Outlets within 3 feet of the sink should be considered for upgrading to GFCI protected outlets. Exhaust fan was operating but not pulling any aire, have reviewed and repaired as necessary.

INTERIOR ROOMS

MAS'	TER	BED	RO	ОМ
INIAU			i.v	

Location: Seco	nd floor								
Walls & Ceiling: 🗹 Satisfactory			arginal		□ Poor	□ Typical (Cracks	□ Holes	
	Moisture s	stains:	□ Y€	es		⊠ No			
Flooring:	☑ Satisfac	ctory	\Box M	arginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sa	tisfactory		🗆 Marginal		□ Poor	
Electrical:	Switches:	🗹 Yes	□ No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	🗆 No
	Open grou	nd/reverse	polarity:	□Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	🗹 Sat. 🛛	Marg. \square	Poor 🗆 Cra	cked glass	🗆 None 🛛	□ Evidence of	leaking insu	lated glas	ss
Door:	🗹 Sat. 🛛	Marg. 🗆	Poor 🗆 Ho	les 🗆 Does	not latch	1 🛛 Hardware	broken 🛛	None	
Closet Doors:	☑ Sat. □	Marg. 🗆	Poor 🗆 Ho	les 🗆 Miss	sing 🗆 T	racks broken	□ None		
General Comm	ents:								

At the time of the inspection the room was found to be in overall satisfactory condition.

BEDROOM #2

Location: Seco	nd floor								
Walls & Ceiling:	☑ Satisfac	tory	□ M	arginal		□ Poor	□ Typical Cracks □ Hole		□ Holes
	Moisture st	tains:	\Box Ye	□ Yes		☑ No			
Flooring:	☑ Satisfac	tory	\Box M	arginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sa	atisfactory		🗆 Marginal		□ Poor	
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open groun	nd/reverse	polarity:	□ Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹	Yes 🛛	Not visible						
Windows:	⊠ Sat. □	Marg. 🛛	Poor 🗆 Cra	acked glass	□ None [□ Evidence of	leaking insu	lated glas	ss
Door:	☑ Sat. □	Marg. 🛛	Poor 🗆 Ho	les 🗆 Does	s not latch	🛛 🗆 Hardware	broken 🛛	None	
Closet Doors:	☑ Sat. □	Marg. 🛛	Poor 🗆 Ho	oles 🗆 Miss	sing 🗆 T	racks broken	□ None		
General Comm	ents:								

At the time of the inspection the room was found to be in overall satisfactory condition.

BEDROOM #3

Location: Second floor									
Walls & Ceiling: 🗹 Satisfactory			arginal		□ Poor	□ Typical Cracks □ Holes		□ Holes	
	Moisture	stains:	\Box Ye	es		🗹 No			
Flooring:	🗹 Satisfa	ctory	\Box M	arginal		🗆 Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sa	tisfactory		🗆 Marginal		🗆 Poor	
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	□ No
	Open grou	und/reverse	e polarity:	\Box Yes	🗆 Safet	y Hazard	🗹 No	\Box Cove	ers missing
Heat source prese	ent: 🗹	Yes 🗆	Not visible						
Windows:	🗹 Sat. 🗆	l Marg. 🛛	Poor Cr	acked glass	□ None	□ Evidence of	f leaking ins	ulated gla	iss
Door:	🗹 Sat. 🗆	l Marg. 🛛	Poor 🗆 He	oles 🗆 Doe	s not late	h 🛛 Hardwar	e broken 🗆	l None	
Closet Doors:	🗹 Sat. 🗆	l Marg. 🗆	Poor 🗆 H	oles 🛛 Mis	sing 🗆 🛛	Fracks broken	□ None		
General Comm	ents:								

At the time of the inspection the room was found to be in overall satisfactory condition.

LIVING ROO	M								
Location: First	floor								
Walls & Ceiling:	☑ Satisfacto	ory	🗆 Ma	arginal		□ Poor	□ Typical (Cracks	□ Holes
	Moisture sta	ains:	□ Ye	s		🗹 No			
Flooring:	☑ Satisfacto	ory	🗆 Ma	arginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	🗹 N/A		🗆 Sat	tisfactory		□ Marginal		D Poor	
Electrical:	Switches:	🗹 Yes	🗆 No	Outlets:	🗹 Yes	□ No	Operates:	🗹 Yes	🗆 No
	Open groun	d/reverse	polarity:	\Box Yes	□ Safet	y Hazard	🗹 No	\Box Cove	ers missing
Heat source prese	ent: 🗹 Yes	🗆 Not	visible						
Windows:	⊠ Sat. □ I	Marg. 🛛	Poor 🗆 Cra	acked glass	🗹 Evide	ence of leaking	insulated gl	ass	
Door:	\Box Sat. \Box 1	Marg. 🛛	Poor 🗆 He	oles 🗆 Does	s not late	h □ Hardwar	e broken 🗹	None	
General Comn	nents:								

At the time of the inspection the room was found to be in overall satisfactory condition.

EATING AREA

Location: First	floor						
Walls & Ceiling:	☑ Satisfactory	□ Marginal	C	□ Poor	□ Typical (Cracks	□ Holes
-	Moisture stains:	□ Yes	5	⊿ No			
Flooring:	☑ Satisfactory	Marginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	⊠ N/A	□ Satisfactory	Γ	☐ Marginal		□ Poor	
Electrical:	Switches: ☑ Yes □	No Outlets:	☑ Yes [□No	Operates:	🗹 Yes	□ No
	Open ground/reverse po	larity: □Yes	□ Safety]	Hazard	🗹 No	\Box Cove	rs missing
Heat source prese	ent: 🗹 Yes 🛛 Not vis	sible					
Windows:	☑ Sat. □ Marg. □ Po	or 🛛 Cracked glass	Evider	nce of leaking	insulated gl	ass	
Door:	☑ Sat. □ Marg. □ Po	or \Box Holes \Box Doe	es not latch	□ Hardwar	e broken] None	
General Comm	ents:						

At the time of the inspection the room was found to be in overall satisfactory condition.

REC ROOM

Location: Base	ment							
Walls & Ceiling:	✓ Satisfactory	□ Ma	rginal		□ Poor	□ Typical (Cracks	□ Holes
-	Moisture stains:	□ Yes	5		🗹 No			
Flooring:	✓ Satisfactory	🗆 Ma	rginal		□ Poor	□ Squeaks		□ Slopes
Ceiling fan:	☑ N/A	🗆 Sat	isfactory		□ Marginal		□ Poor	
Electrical:	Switches: Yes	No	Outlets:	🗹 Yes	🗆 No	Operates:	🗹 Yes	🗆 No
	Open ground/reverse po	larity:	□Yes	🗆 Safety	y Hazard	🗹 No	\Box Cove	ers missing
Heat source press	ent: 🗹 Yes 🛛 Not vi	sible						
Windows:	☑ Sat. □ Marg. □ Po	or 🗆 Cra	acked glass	🛛 🗆 Evid	ence of leaking	g insulated gl	lass	
Door:	\Box Sat. \Box Marg. \Box Po	or 🗆 Ho	oles 🗆 Doe	es not late	h 🗆 Hardwar	e broken	None 1	
General Comm	nents:							

At the time of the inspection the room was found to be in overall satisfactory condition.

WINDOWS / FIREPLACES / ATTIC

Interior Windows/Glass				
General condition:	☑ Satisfactory	y 🗆 Marginal	□ Poor	□ Painted shut
□ Hardware missing	•		Cracked glass	Broken counter-balance mech.
□ Surface deterioration:	(See Remarks	s page) 🛛 🗹	Representative numb	er of windows operated
Evidence of leaking insulat	ted glass:	☑ Yes ☑ No	□ Not determi	nable \Box N/A
Safety glazing:	⊠ N/A	□ Safety issue	Where:	
Security bars present:	□ Yes	☑ No □ Not	tested	mechanism before moving in
Fireplace		⊠None Loca	tion(s):	
□ Gas	□ Wood	□ Wood burner st	ove (See Remarks pa	ge)
□ Masonry insert	□ Metal inser	t 🗆 Metal	□ Electric	-
□ Blower built-in	Operates:	🗆 Yes 🛛 No	🗆 Damper ope	erates 🛛 Damper missing
□ Open joints or cracks in f	irebrick should	be sealed	□ Pre-fabricate	ed panels damaged/worn
Hearth: Satisfactory:	□ Yes	□ No	Mantle: 🗆 S	Satisfactory 🗆 Loose
□ Recommend having flue	e cleaned and r	e-examined	\Box Vent less	Direct Vent
Stairs		☑ Satisfactory	□ Marginal	□ Poor □ None
Handrail:	☑ Satisfactory	y 🛛 Marginal	□ Poor	🗆 Safety Hazard
Risers/Treads:	☑ Satisfactory	y 🗆 Marginal	□ Poor	□ Risers/treads uneven
Smoke/CO Detectors		(See Remarks pa	ge)	
Present: Yes	🗹 No			
	hould be tested mo	onthly and batteries chang	<mark>ed semi annually. Most bat</mark> i	n all levels of a home with sleeping tery operated units should be replaced
Attic				
Access: Access panel Ac	ccess Location:	Bedroom closet	Inspected from: Acce	ess panel
Flooring:	plete	Partial	☑ None	-
Insulation: Type: Loose fi	ill fiberglass	Average thickness:	9 to 12 inches I	R Rating: R32 Standard
Installed	d in: ☑ Floo	or 🗆 Rafters	\Box Walls	□ Not Visible
Vent fans:	ent 🗆 Not	tested	stat controlled 🛛 Sat	fety Hazard
Ventilation: Satisfac	tory			
Roof structure: Wooder				
Roof sheathing: Plywood				
Roof Sheathing Condition:		e		
	🗆 Yes 🗹 No	Outside: 🗹 Yes 🛛	\Box No \Box Not visible	□ N/A (See Remarks page)
Chimney chase:				
Structural problems observe	d: 🗆 Yes		nments below	
Vapour barriers: \square Not v	visible	□ Improperly insta	lled	
□ Kraft			See Remarks page)	
Electrical:	n junction box(e	es) 🗆 Handyr	nan wiring	□ Visible knob-and-tube
General Comments				

Trusses showed no major defects or damage at the time of inspection. Roof sheathing, examined from the attic, showed no major defects or moisture damage. Insulation was sufficient for homes in this area. Ventilation was normal. Vapour barrier not visible. No CO detector on sleeping level. Smoke detectors are past their normal life expectancy and should be replaced.

BASEMENT

(See Remarks page)

Stairs						
Condition:	☑ Satisfactor		□ Marginal	D Poor	🗆 Safety Haz	zard
Handrail: 🗹 Yes		ndition:	☑ Satisfactory	🗆 Marginal	\Box Poor	
Headway over stairs:	☑ Satisfactor		□ Marginal	\square Poor	_	
Under carriage:	Satisfactor	ry	□ Marginal	□ Poor	□ Not visible	
Foundation						
Wall Material:	Poured Conc	rete				
Condition:	Satisfactory					
Foundation Cracks:		None Vis	sible Visib	ble from: \Box Extended	rior 🗆 Interior	•
Movement apparent:	🗆 Yes 🗹 N					
Partially/Covered walls:	ØYes □N	lo				
	Condition re	eported	above reflects <u>visil</u>	ole portion only		
Floor			(See vapour bar	mion romonks)		
Material:	Concrete		(See vapour bar	fiel femalks)		
Condition:	Satisfactory					
	Substactory		XX			
Seismic Bolts			Not applicable			
Basement Drainage						
Indication of moisture:	No					
Sump Pump:		ımn Pur	np Operates: Not a	nnlicable		
Floor drain(s) present:	Yes	ump i un	np operates. Not a	ipplicable		
			1 1 /		(C D	
Drain Tile (See Remarks	page)		almer valve present	□ Not Visible	(See Remar	ks page)
Girders (1), Columns (2)			J/A			
	□ Steel		□ Wood	□ Block	□ Concrete	☑ Not visible
Condition:	□ Satisfactor	ry	□ Marginal	□ Poor	□ Stained/rus	sted
Joists /Trusses						
Ø Joist □ Trusses	□ I-Joist		□ Steel	☑ Wood	□Concrete	□ Not visible
	$\Box 2x6$		☑ 2x8	$\Box 2x10$	$\Box 2x12$	
Sub Floor						
	□ Indication	of mois	ture stains/rotting			
	** Areas	around s	shower stalls, etc., as	s viewed from bas	sement or craw	l space
General Comments						

Foundation appeared to be in overall satisfactory condition. Foundation walls were covered/partially covered with paneling/drywall/insulation and were not visible. No representation can be made to the conditions of the covered/partially covered walls. Floor appeared to be in overall satisfactory condition. No active seepage visible at the time of the inspection. No representation can be made to future leaking of the basement walls.

		PLUME	BING		
Water Service		Shut off location:	Basement		
Water entry piping: Co	pper Water	lines: Copper and P	lastic		
	Lead (other than	solder joints):	🗆 Yes 🗹 No	□ Service entry	Unknown
	Water flow:	☑ Satisfactory	□ Poor	Cross connection:	\Box Yes \Box No
	Water pressure:	☑ Satisfactory	□ Poor □ Aboy	ve 80 psi (Needs eva	luation)
	Pipes: Corroc	led 🗆 Leaking	□ Valves broker	n/missing 🛛 🗆 Dia	ssimilar metal
Drain/waste/vent pipe:	Plastic				
	Condition:	☑ Satisfactory	□ Marginal	D Poor	□ Not visible
	Waste discharge:	☑ Satisfactory	□ Slow drain		
Gas Lines		□ Not visible	□ Shutoff miss	sing	
	□ Copper	□ Brass	☑ Black iron	□ Stainless steel	\Box CSST
Water Heater					
Brand name: GSW					
Energy Source: Gas	Approx. age:7	yrs		Capacity: 50 gallo	n
Rental Unit: Yes		Seismic restraints n	eeded: 🗹 N/A 🗆	l Yes □ No	
Relief valve:	🗹 Yes 🛛 No	Extension pr	oper: 🗹 Yes	🗆 No 🛛 🗆 Missi	ing
Vent pipe:	□ N/A ☑ Satisfa	actory Improper	pitch Rusted	□ Safety Hazard	-
Water Softener		(Unit not evaluat	ted)		
	□Yes ☑ No	Plumbing hoc	oked up:	□No	
General Comments					

Overall the plumbing system, faucets, water pressure and drain rates were found to be in satisfactory condition at the time of the inspections.

	HE	EATIN	IG SYS	TEN	/	
Fuel Shutoff fo	r Building	Main fuel s	shutoff location:	Outside	at gas meter	
Forced Air Sys	tom	☑ Central	Unit	🗆 Wall I	Furnace	□ Floor Furnace
	Brand name: Rh		Ollit			<i>age:</i> 1 to 3 yrs
Energy source:			: High Efficienc	v	Approximate	uge: 1 to 5 yis
Hot air systems:		ce Efficiency	. Ingli Enterene	y		
	Sealed unit, not visible	View is ex	stremely limited	d - See R	emarks page a	about options
Distribution:	Metal Ducts	Flue pipin	•		10	•
Filter: Standard	Filter Condition: Sa	tisfactory	0			
Operated:	When turned on b	by thermostat	:		□ Did not fire	2
Operation:	Satisfactory:	Yes 🗆 No	□ Recommend	HVAC 1	technician exam	ine 🗆 Before closing
Controls:	□ Disconnect		🗹 Normal oper	rating and	d safety control	s observed
Heat pump:	\Box Aux. Elec.	□ Aux. Gas	□ Aux. geothe	rmal	🗹 N/A	
	Emergency heat t	ested:	□ Yes □	l No	☑ N/A	
Others		☑ N/A				
	Electric baseb	oard	□ Radiant ceilir	ng cable	□ Gas space l	neater
	□ Radiant in floor	heating	U Wood burning	ng stove	(See Remark	s page)
General Comm	nents					

Furnace was not fired due to seasonality and outside temperature. Furnace was run under cooling.

COOLING SYSTEM

System Components		□ None		Approximate age: 1 to 3 yrs		
Energy source: Electric	Central air: Air C	cooled				
Operated: Yes	Operation: Satisfa	actory				
Refrigerant lines:	🗆 Leak	Damaged		□ Insulation missing		☑ Satisfactory
Through wall unit(s):	⊠ N/A	Operated:	□ Yes	□ No	□ Satisfactory	\Box Needs service
General Comments						

A/C unit was operating in satisfactory condition.

		ELECTR				
Main Panel		Location: Basement				
	Amps: 100 amps	ps Volts:120/240 volts Panel Type: Breakers				
Appears grounded:	☑ Yes □ No	GFCI present:	🗆 Yes 🛛 No	Operates:	\Box Yes \Box No	
Main Wire:	Not visible					
Branch Wire:	Copper					
	☑ Romex	□ BX cable	□ Conduit		□ Knob & tube	
	□ Multiple tapping □ Branch wires undersized □ Federal Pacific panel (see Remarks)					
	□ Multiple tapping of main disconnect □ Safety Hazard					
	\Box Arc fault present <i>Operates</i> : \Box Yes \Box No \Box N/A (see Remarks)					
	□ Panel not acce	ssible \Box Not e	evaluated Reason:			
Electrical Fixtures						
A representative number	-	-	and receptacles loc	ated inside the	e house, garage, and	
exterior walls were test	ed and found to be	:				
	☑ Satisfactory	0	□ Poor			
		Reverse polarity			ounded 3-prong outlets	
□ Solid conductor aluminum branch wiring circuits (See Remarks page)						
	□ Recommend a	a licensed electrician	evaluate the servi	ce		
General Comments:						

Panel size appeared to be compatible to service size. Branch breaker distribution appeared normal. No signs of overheating were evident at the time of the inspection. Outlets were randomly tested and had correct polarity, except as noted. There is a live wire hanging in the furnace room and it should be properly secured in a proper junction box.





Pic. 1: Front view



Pic. 5: AC unit



Pic. 9: Master bedroom



Pic. 13: Bed 3



Pic. 17: Kitchen



Pic. 21: Rec room



Pic. 2: Updated roof covering



Pic. 6: Garage



Pic. 10: Master bath



Pic. 14: 2nd floor bath





Pic. 22: Basement bath



Pic. 3: Back view



Pic. 7: Attic



Pic. 11: Master bath



Pic. 15: Living room







Pic. 23: Laundry



Pic. 4: Rear deck sagging, repair as necessary



Pic. 8: Attic



Pic. 12: Bed 2



Pic. 16: Eating area



Pic. 20: Powder room



Pic. 24: Laundry

Subject Property: 53 Gianmarco Way, Maple, Ontario



Pic. 25: Hot water tank



Pic. 26: Updated gas furnace



Pic. 27: Open live wire needs to be secured in a proper junction box



Pic. 28: 100 amp breaker panel

GENERAL REMARKS

List below are general remarks about the different areas and components of a home. These remarks are for general information purposes only and some of the information provided may not be specific to the home inspected.

GROUNDS REMARKS

Service Walks/Driveways

Spalling concrete cannot be patched with concrete because the new will not bond with the old. Water will freeze between the two layers, or the concrete will break up from movement or wear. Replacement of the damaged section is recommended. Walks or driveways that are close to the property should be properly pitched away to direct water away from the foundation. Asphalt driveways should be kept sealed and larger cracks filled so as to prevent damage from frost.

Patios that have settled towards the structure should be mudjacked or replaced to assure proper pitch. Improperly pitched patios are one source of wet basements.

Exterior Wood Surfaces

All surfaces of untreated wood need regular applications of paint or special chemicals to resist damage. Porch or deck columns and fence posts which are buried in the ground and made of untreated wood will become damaged within a year or two.

Decks should always be nailed with galvanized or aluminium nails. Decks that are not painted or stained should be treated with a water sealer.

Grading and Drainage

Any system of grading or landscaping that creates positive drainage (moving water away from the foundation walls) will help to keep a basement dry. Where negative grade exists and additional backfill is suggested, it may require digging out around the property to get a proper pitch. Dirt shall be approximately 15 cm below the bottom sill and should not touch wood surfaces.

Flower beds, loose mulched areas, railroad ties and other such landscaping items close to the foundation trap moisture and contribute to wet basements. To establish a positive grade, a proper slope away from the house is 2.5 cm per meter for approximately 1.5 to 2 meters. Recommend ground cover planting or grass to foundation.

Roof and Surface Water Control

Roof and surface water must be controlled to maintain a dry basement. This means keeping gutters cleaned out and aligned, extending downspouts, installing splash blocks, and building up the grade so that roof and surface water is diverted away from the building.

Window Wells

The amount of water which enters a window well from falling rain is generally slight, but water will accumulate in window wells if the yard is improperly graded. Plastic window well covers are useful in keeping out leaves and debris.

Retaining Walls

Retaining walls deteriorate because of excessive pressure build-up behind them, generally due to water accumulation. Often, conditions can be improved by excavating a trench behind the retaining wall and filling it with coarse gravel. Drain holes through the wall will then be able to relieve the water pressure.

Retaining walls sometime suffer from tree root pressure or from general movement of topsoil down the slope. Normally, these conditions require rebuilding the retaining wall.

Railings

It is recommended that railings be installed for any stairway over 3 steps and porches over 75 cm for safety reasons. Balusters for porches, balconies, and stairs should be close enough to assure children cannot squeeze through.

ROOF COVERING REMARKS

Valleys & Flashings

Valleys and flashings that are covered with shingles and/or tar or any other material are considered not visible and are not part of the inspection.

Stone Roofs - Coverings

This type of covering on a pitched roof requires ongoing annual maintenance. We recommend that a roofing contractor evaluate this type of roof. Infra-red photography is best used to determine areas of potential leaks.

Flat Roofs

Flat roofs are very vulnerable to leaking. It is very important to maintain proper drainage to prevent ponding of water. We recommend that a roofing contractor evaluate this type of roof.

ROOF TYPE	LIFE EXPECTANCY	SPECIAL REMARKS		
Asphalt Shingles	15-20 years	Used on nearly 80% of all residential roofs; requires little maintenance		
Asphalt Multi-Thickness Shingles*	20-30 years	Heavier and more durable than regular asphalt shingles		
Asphalt Interlocking Shingles*	15-25 years	Especially good in high-wind areas		
Asphalt Rolls	10 years	Used on low slope roofs		
Built-up Roofing	10-20 years	Used on low slope roofs; 2 to 3 times as costly as asphalt shingles		
Wood Shingles*	10-40 years ¹	Treat with preservative every 5 years to prevent decay		
Clay Tiles* Cement Tiles*	20 + years 20 + years	Durable, fireproof, but not watertight, requiring a good subsurface base		
Slate Shingles*	30-100 years ²	Extremely durable, but brittle and expensive		
Asbestos Cement Shingles*	30-75 years	Durable, but brittle and difficult to repair		
Metal Roofing	15-40 + years	Comes in sheets & shingles; should be well grounded for protection from lightning; certain metals must be painted		
Single Ply Membrane	15-25 years (mfgr's claim)	New material; not yet passed test of time		

* Not recommended for use on low slope roof ¹ Depending on local conditions and proper installation ² Depending on quality of slate

Roof covering should be visually checked in spring and fall for any visible missing shingles, damaged coverings or other defects. Before re-roofing, the underside of the roof structure and roof sheathing should be inspected to determine that the roof structure can support the additional weight of the shingles.

Wood shakes and shingles will vary in aging, due to quality of the material, installation, maintenance, and surrounding shade trees. Ventilation and drying of the wood material is critical in extending the life expectancy of the wood. Commercial preservatives are available on the market, which could be applied to wood to impede deterioration.

CHIMNEY / GUTTERS / SIDING / TRIM REMARKS

Chimneys

Chimneys built of masonry will eventually need tuck pointing. A cracked chimney top that allows water and carbonic acid to get behind the surface brick/stone will accelerate the deterioration. Moisture will also deteriorate the clay flue liner. Periodic chimney cleaning will keep you apprised of the chimney's condition. The flashing around the chimney may need resealing and should be inspected every year or two. Fireplace chimneys should be inspected and evaluated by a chimney professional before using. Chimneys must be adequate height for proper drafting. Spark arrestors are recommended for wood burning chimney and chimney caps for fossil fuels

Unlined Chimney - should be re-evaluated by a chimney technician.

Have flue cleaned and re-evaluated. The flue lining is covered with soot or creosote and no representation can be made as to the condition.

NOT EVALUATED- The flue was not evaluated due to inaccessibility such as roof pitch, cap, cleanout not accessible, etc.

Cricket Flashing

Small, sloped structure made of metal and designed to drain moisture away from a chimney. Crickets are usually placed at the back of a chimney.

Gutters and Downspouts

This is an extremely important element in basement dampness control. Keep gutters clean and downspout extensions in place (1.25 meters or more). Paint the inside of galvanized gutters, which will extend the life. Shortly after a rain or thaw in winter, look for leaks at seams in the gutters. These can be re-caulked before they cause damage to fascia or soffit boards. If no gutters exist, it is recommended that they be added.

Siding

Wood siding should not come in contact with the ground. The moisture will cause rotting to take place and can attract carpenter ants.

EIFS - This type of siding has experienced serious problems and requires a certified EIFS inspector to determine condition.

Brick and stone veneer must be monitored for loose or missing mortar. Some brick and stone are susceptible to spalling. This can be caused when moisture is trapped and a freeze/thaw situation occurs. There are products on the market that can be used to seal out the moisture. This holds true for brick and stone chimneys also.

Metal sidings will dent and scratch. Oxidation is a normal reaction in aluminum. There are good cleaners on the market and it is recommended that they be used occasionally. Metal siding can be painted.

Doors and Windows

These can waste an enormous amount of energy. Maintain the caulking around the frames on the exterior. Check for drafts in the winter and improve the worst offenders first. Windows that have leaky storm windows will usually have a lot of sweating. Likewise, well-sealed storms that sweat indicate a leaky window. It is the tighter unit that will sweat (unless the home has excess humidity to begin with.)

Wood that exhibits blistering or peeling paint should be examined for possible moisture sources: roof leaks, bad gutters, interior moisture from baths or laundry or from a poorly vented crawl space. Some paint problems have no logical explanation, but many are a symptom of an underlying problem. A freshly painted house may mask these symptoms, but after you have lived in the home for a year or two, look for localized paint blistering (peeling). It may be a clue.

New glazing will last longer if the raw wood is treated with boiled linseed oil prior to glazing. It prevents the wood from drawing the moisture out of the new glazing.

Caulking

Many different types of caulk are available on the market today. Check with a paint or hardware store for the kind of application you need.

EXTERIOR / ELECTRICAL / AC / GARAGE REMARKS

Exterior Doors

The exposed side of wood exterior doors needs to be painted or stained and varnished to prevent discolouring and delamination. Weather-stripping is a must to prevent drafts.

Electrical

Overhead wires from the mast to the main panel that are exposed to the weather may fray and crack. If this occurs, wires should be replaced by a licensed electrician.

Any outdoor overhead service conductor wires should have adequate clearance above the ground (3 meters) and from balcony and windows (1 meter), for safety reasons.

Underground system - Some exterior boxes that are at ground level have a grade line on them. You should insure that the grade remains below this line to prevent moisture from entering the main panel.

Overhead Door Openers

We recommend that a separate electrical outlet be provided. Openers that do not have a safety reverse are considered a safety hazard. Small children and pets are especially vulnerable. We recommend the operating switches be set high enough so children cannot reach them. If an electric sensor is present, it should be tested occasionally to ensure it is working.

Garage Sill Plates

Sill plates within the garage should be elevated or treated lumber should be used. If this is not the case, try to direct water away to prevent rotting.

A/C Compressors

They should not become overgrown with foliage. Clearance requirements vary, but 60 cm on all sides should be considered minimal with up to 2 meters of air discharge desirable. If a clothes dryer vent is within five to ten feet, either relocate the vent or do not run when the A/C is running. The lint will quickly reduce the efficiency of the A/C unit.

Burners

Any appliance such as a water heater, furnace, etc. should have the flame a minimum of 45 cm above the floor. Any open flame less than 45 cm from the floor is a potential safety hazard. The appliance should also be protected from vehicle damage.

KITCHEN / LAUNDRY / UTILITY ROOM REMARKS

Plaster on Wood Lath

Plaster on wood lath is an old technique and is no longer in general use. Wood lath shrinks with time and the nails rust and loosen. As a result, the plaster may become fragile and caution is needed in working with this type of plastering system. Sagging ceilings are best repaired by laminating drywall over the existing plaster and screwing it to the ceiling joists.

Plaster on Gypsum Lath (Rock Lath)

Plaster on gypsum lath will sometimes show the seams of the 40 cm wide gypsum lath, but this does not indicate a structural fault. The scalloping appearance can be levelled with drywall joint compound and fibreglass mesh joint tape or drywall can be laminated over the existing plaster on the ceiling.

Wood Flooring

Always attempt to clean wood floors first before making the decision to refinish the floor. Wax removers and other mild stripping agents plus a good waxing and buffing will usually produce satisfactory results. Mild bleaching agents help remove deep stains. Sanding removes some of the wood in the floor and can usually be done safely only once or twice in the life of the floor.

Nail Pops

Drywall nail pops are due to normal expansion and contraction of the wood members to which the drywall is nailed, and are usually of no structural significance.

Carpeting

Where carpeting has been installed, the materials and condition of the floor underneath cannot be determined.

Appliances

Dishwashers are tested to see if the motor operates and water sprays properly (full cycles are not run). Stoves are tested to see that burners are working and oven and broiler get hot. Timer and controls are not tested. Refrigerators are not tested.

No representation is made to continued life expectancy of any appliance.

Asbestos and Other Hazards

Asbestos fibres in some form are present in many homes, but are often not visible and cannot be identified without testing.

If there is reason to suspect that asbestos may be present and if it is of particular concern, a sample of the material in question may be removed and analyzed in a laboratory. *However, detecting or inspecting for the presence or absence of asbestos is not a part of our inspection.*

Also excluded from this inspection and report are the possible presence of, or danger from, radon gas, lead-based paint, urea formaldehyde, toxic or flammable chemicals and all other similar or potentially harmful substances and environmental hazards.

Windows

A representative number of windows are inspected.

BATHROOM REMARKS

Stall Shower

The metal shower pan in a stall shower has a potential or probable life of 10-20 years depending on quality of the pan installed. Although a visible inspection is made to determine whether a shower pan is currently leaking, it cannot be stated with certainty that no defect is present or that one may not soon develop. Shower pan leaks often do not show except when the shower is in actual use.

Ceramic Tile

Bathroom tile installed in a mortar bed is excellent. It is still necessary to keep the joint between the tile and the tub/shower caulked or sealed to prevent water spillage from leaking through and damaging the ceilings below.

Ceramic tile is often installed in mastic. It is important to keep the tile caulked or water will seep behind the tile and cause deterioration in the wallboard. Special attention should be paid to the area around faucets and other tile penetrations.

Exhaust Fans

Bathrooms with a shower should have exhaust fans where possible. This helps to remove excess moisture from the room, preventing damage to the ceiling and walls and wood finishes. The exhaust fan should not be vented into the attic. The proper way to vent the fans is to the outside. Running the vent pipe horizontally and venting into a gable end or soffit is preferred. Running the vent pipe vertically through the roof may cause condensation to run down the vent pipe, rusting the fan and damaging the wallboard. Insulating the vent pipe in the attic will help to reduce this problem.

SLOW DRAINS on sinks, tubs, and showers are usually due to build-up of hair and soap scum. Most sink pop-ups can be easily removed for cleaning. Some tubs have a spring attached to the closing lever that acts as a catch for hair. It may require removing a couple of screws to disassemble. If you cannot mechanically remove the obstruction, be kind to your pipes. Don't use a caustic cleaner. There are several bacteria drain cleaners available. They are available at hardware stores in areas where septic tanks are used. These drain cleaners take a little longer to work, but are safe for you and your pipes.

Safety Hazards

Typical safety hazards found in bathrooms are open grounds or reverse polarity by water. Replacing these outlets with G.F.C.I.'s are recommended. (See Electrical section)

Whirlpool Tubs

This relates to interior tubs hooked up to interior plumbing. Where possible, the motor will be operated to see that the jets are working. Hot tubs and spas are not inspected.

ROOMS (INTERIOR) REMARKS

Door Stops

All swinging doors should be checked for door stops. Broken or missing door stops can result in door knobs breaking through drywall or plaster.

Closet Guides

Sliding closet doors should be checked to see that closet guides are in place. Missing or broken closet guides can cause scratches and damage to doors.

Cold Air Returns

Bedrooms that do not have cold air returns in them should have a 1.75 cm gap under the doors to allow cold air to be drawn into the hall return.

AN INSPECTION VERSUS A WARRANTY

A home inspection is just what the name indicates, an inspection of a home...usually a home that is being purchased. The purpose of the inspection is to determine the condition of the various systems and structures of the home. While an inspection performed by a competent inspection firm will determine the condition of the major components of the home, no inspection will pick up every minute latent defect. The inspector's ability to find all defects is limited by access to various parts of the property, lack of information about the property and many other factors. A good inspector will do his or her level best to determine the condition of the home and to report it accurately. The report that is issued is an opinion as to the condition of the home. This opinion is arrived at by the best technical methods available to the home inspection industry. It is still only an opinion.

A warranty is a policy sold to the buyer that warrants that specific items in the home are in sound condition and will remain in sound condition for a specified period of time. Typically, the warranty company never inspects the home. The warranty company uses actuarial tables to determine the expected life of the warranted items and charges the customer a fee for the warranty that will hopefully cover any projected loss and make a profit for the warranty seller. It is essentially an insurance policy.

The service that we have provided you is an inspection. We make no warranty of this property. If you desire warranty coverage, please see your real estate agent for details about any warranty plan to which their firm may have access.

Page 30

WINDOWS / FIREPLACES / ATTIC REMRKS

Window Frames and Sills

Window frames and sills often are found to have surface deterioration due to condensation that has run off the window and damaged the varnish. Usually this can be repaired with a solvent style refinisher and fine steel wool. This is sometimes a sign of excess humidity in the house.

See comments regarding caulking doors and windows above (Chimneys/Gutters/Siding).

Fireplaces

It is important that a fireplace be cleaned on a routine basis to prevent the build-up of creosote in the flue, which can cause a chimney fire.

Masonry fireplace chimneys are normally required to have a terra cotta flue liner or 8 inches of masonry surrounding each flue in order to be considered safe and to conform to most building codes.

During visual inspections, it is not uncommon to be unable to detect the absence of a flue liner either because of stoppage at the firebox, a defective damper or lack of access from the roof.

Wood burners

Once installed, it can be difficult to determine proper clearances for wood burning stoves. Manufacturer specifications, which are not usually available to the inspector, determine the proper installation. We recommend you ask the owner for paperwork verifying that it was installed by a professional contractor.

Ventilation

Ventilation is recommended at the rate of one square foot of vent area to 300 square feet of attic floor space, this being divided between soffit and rooftop. Power vents should ideally have both a humidistat and a thermostat, since ventilation is needed to remove winter moisture as well as summer heat. Evidence of condensation, such as blackened roof sheathing, frost on nail heads, etc. is an indication that ventilation may have been or is blocked or inadequate.

Insulation

The recommended insulation in the attic area is R-38, approximately 30cm. If insulation is added, it is important that the ventilation is proper.

Smoke Detectors

Smoke detectors should be tested monthly. At least one detector should be on each level.

Vapour Barriers

The vapour barrier should be on the warm side of the surface. Older homes were often built without vapour barriers. If the vapour barrier is towards the cold side of the surface, it should be sliced or removed. Most vapour barriers in the attic are covered by insulation and therefore, not visible.

Safety Glazing

Safety glazing requirements vary depending on the age of the home. Every attempt is made to identify areas where the lack of safety glazing presents an immediate safety hazard, such as a shower door. In some older homes it is difficult to determine if safety glazing is present, since the glass is not marked. Therefore, no representation is made that safety glazing exists in all appropriate areas.

Insulated Glass

The broken seals are not always detectable due to dirty windows, covered windows, etc. In most cases, leaking glass seals take some time before they are evident.

BASEMENT REMARKS

Basement

Any basement that has cracks or leaks is technically considered to have failed. Most block basements have step cracks in various areas. If little or no movement has occurred, and the step cracks are uniform, this is considered acceptable. Horizontal cracks in the third or fourth block down indicate the block has moved due to outside pressure. They can be attributed to many factors, such as improper grading, improperly functioning gutter and downspout system, etc. Normally, if little or no movement has taken place and proper grading and downspouts exist, this is considered acceptable. If the wall containing the stress crack(s) has moved considerably, this will require some method of reinforcement. Basements that have been freshly painted or tuck-pointed should be monitored for movement. This will be indicated by cracks reopening. If cracks reappear, reinforcement may be necessary. Reinforcing a basement wall can become expensive.

Foundation (Covered Walls)

Although an effort has been made to note any major inflections or weaknesses, it is difficult at best to detect these areas when walls are finished off, or basement storage makes areas inaccessible. *No representation is made as to the condition of these walls.*

Monitor indicates that the walls have stress cracks, but little movement has occurred. In our opinion, the cracks should be filled with mortar and the walls monitored for further movement and cracking. If additional movement or cracking occurs, re-enforcements may be necessary.

Have Evaluated — we recommend that the walls be re-evaluated by a structural engineer or basement repair company and estimates be obtained if work is required.

Vapour Barrier

Floors that are dirt or gravel should be covered with a vapour barrier.

Moisture Present

Basement dampness is frequently noted in houses and in most cases the stains, moisture or efflorescence present is a symptom denoting that a problem exists outside the home. Usual causes are improper downspout extensions or leaking gutters and/or low or improper grade (including concrete surfaces) at the perimeter of the house. A proper slope away from the house is one inch per foot for four to six feet.

Expensive solutions to basement dampness are frequently offered, and it is possible to spend thousands of dollars on solutions such as pumping out water that has already entered or pumping of chemical preparations into the ground around the house, when all that may be necessary are a few common sense solutions at the exterior perimeter. However, this is not intended to be an exhaustive list of causes and solutions to the presence of moisture. *No representation is made to future moisture that may appear.*

Palmer Valve

Many older homes have a valve in the floor drain. This drain needs to remain operational.

Drain Tile

We offer no opinion about the existence or condition of the drain tile, as it cannot be visibly inspected.

Basement Electrical Outlets

We recommend that you have an outlet within 2 meters of each appliance. The appliance you plan to install may be different than what exists; therefore the inspection includes testing a representative number of receptacles that exist. It is also recommended to have ground fault circuit interrupts for any outlet in the unfinished part of the basement and crawl spaces.

PLUMBING REMARKS

Wells

Examination of wells is not included in this visual inspection. It is recommended that you have well water checked for purity by the local health authorities and, if possible, a check on the flow of the well in periods of drought. A well pit should have a locked cover on it to prevent anyone from falling into the pit.

Septic Systems

The check of septic systems is not included in our visual inspection. You should have the local health authorities or other qualified experts check the condition of a septic system.

In order for the septic system to be checked, the house must have been occupied within the last 30 days.

Water Pipes

Galvanized water pipes rust from the inside out and may have to be replaced within 20 to 30 years. This is usually done in two stages: horizontal piping in the basement first and vertical pipes throughout the house later as needed.

Copper pipes usually have more life expectancy and may last as long as 60 years before needing to be replaced.

Polybutylene pipes are grey pipes that have a history of failure and should be examined by a licensed plumber.

Hose Bibs

During the winter months it is necessary to make sure the outside faucets are winterized. This can be done by means of a valve located in the basement. Leave the outside faucets open to allow any water standing in the pipes to drain, preventing them from freezing. Hose bibs cannot be tested when winterized.

Water Heater

The life expectancy of a water heater is 5-10 years. Water heaters generally need not be replaced unless they leak. It is a good maintenance practice to drain 5-10 gallons from the heater several times a year. *Missing relief valves or improper extension present a safety hazard.*

Water Softeners

During a visual inspection, it is not possible to determine if water is being properly softened.

Plumbing

The temperature/pressure valve should be tested several times a year by lifting the valve's handle. Caution: very hot water will be discharged. If no water comes out, the valve is defective and must be replaced.

Shut-Off Valves

Most shut-off valves have not been operated for long periods of time. We recommend operating each shutoff valve to: toilet bowl, water heater, under sinks, main shut-off, hose faucets, and all others. We recommend you have a plumber do this, as some of the valves may need to be repacked or replaced. Once the valves are in proper operating order, we recommend opening and closing these valves several times a year.

Polybutylene Piping

This type of piping has a history of problems and should be examined by a licensed plumber and repaired or replaced as necessary.

MECHANICAL DEVICES MAY OPERATE AT ONE MOMENT AND LATER MALFUNCTION; THEREFORE, LIABILITY IS SPECIFICALLY LIMITED TO THOSE SITUATIONS WHERE IT CAN BE CONCLUSIVELY SHOWN THAT THE MECHANICAL DEVICE INSPECTED WAS INOPERABLE OR IN THE IMMEDIATE NEED OF REPAIR OR NOT PERFORMING THE FUNCTION FOR WHICH IS IT WAS INTENDED AT THE TIME OF INSPECTION.

HEATING SYSTEM REMARKS

HEATING AND AIR CONDITIONING units have limited lives. Normal lives are:

GAS-FIRED HOT AIR15-25 years
OIL-FIRED HOT AIR
CAST IRON BOILER 30-50 years
(Hot water or steam) or more
STEEL BOILER 30-40 years
(Hot water or steam) or more
COPPER BOILER 10-20 years
(Hot water or steam)
CIRCULATING PUMP (Hot water) 10-15 years
AIR CONDITIONING COMPRESSOR8-12 years
HEAT PUMP8-12 years

Gas-fired hot air units that are close to or beyond their normal lives have the potential of becoming a source of carbon monoxide in the home. You may want to have such a unit checked every year or so to assure yourself that it is still intact. Of course, a unit of such an age is a good candidate for replacement with one of the new, high efficiency furnaces. The fuel savings alone can be very attractive.

Boilers and their systems may require annual attention. If you are not familiar with your system, have a heating contractor come out in the fall to show you how to do the necessary things. *Caution: do not add water to a hot boiler!*

Forced air systems should have filters changed every 30 to 60 days of the heating and cooling season. This is especially true if you have central air conditioning. A dirty air system can lead to premature failure of your compressor - a \$1,500 machine.

Oil-fired furnaces and boilers should be serviced by a professional each year. Most experts agree you will pay for the service cost in fuel saved by having a properly tuned burner.

Read the instructions for maintaining the humidifier on your furnace. A malfunctioning humidifier can rust out a furnace rather quickly. It is recommended that the humidifier be serviced at the same time as the furnace, and be cleaned regularly. *During a visual inspection it is not possible to determine if the humidifier is working.*

Have HVAC Technician Examine - A condition was found that suggests a heating contractor should do a further analysis. We suggest doing this before closing.

Heat exchangers cannot be examined nor their condition determined without being disassembled. Since this is not possible during a visual, non-technically exhaustive inspection, you may want to obtain a service contract on the unit or contact a furnace technician regarding a more thorough examination.

Testing pilot safety switch requires blowing out the pilot light. Checking safety limit controls requires disconnecting blower motor or using other means beyond the scope of this inspection. If furnace has not been serviced in last 12 months, you may want to have a furnace technician examine.

CO Test - This is not part of a non-technical inspection.

Combustible Gas Test (Potential Safety Hazard) - If a combustible gas detector was used during the inspection of the furnace and evidence of possible combustible gases was noted, we caution you that our test instrument is sensitive to many gases and not a foolproof test. None-the-less, this presents the <u>possibility</u> that a hazard exists and could indicate that the heat exchanger is, or will soon be, defective.

COOLING SYSTEM / ELECTRICAL REMARKS

Electrical

Every effort has been made to evaluate the size of the service. Three wires going into the home indicate 240 volts. The total amps are sometimes difficult to determine. We highly recommend that ground fault circuit interrupters (G.F.C.I.) be connected to all outlets around water. This device automatically opens the circuit when it senses a current leak to ground. This device can be purchased in most hardware stores. G.F.C.I.'s are recommended by all outlets located near water, outside outlets, or garage outlets. Pool outlets should also be protected with a G.F.C.I.

The G.F.C.I. senses the flow of electricity through a circuit. If more current is flowing through the black ("hot") wire than the white ("neutral") wire, there is a current leakage. The G.F.C.I., which can sense a ground leak of as little as .005 amps, will shut off the current in 1/40 of a second, which is fast enough to prevent injury.

If you do have G.F.C.I.'s, it is recommended that you test (and reset) them monthly. When you push the test button, the reset button should pop out, shutting off the circuit. If it doesn't, the breaker is not working properly. If you don't test them once a month, the breakers have a tendency to stick, and may not protect you when needed.

Knob and tube wiring found in older homes should be checked by an electrician to insure that the wire cover is in good condition. Under no circumstances should this wire be covered with insulation. Recess light fixtures should have a baffle around them so that they are not covered with insulation. The newer recessed fixtures will shut off if they overheat.

Federal Pacific electrical panels may be unsafe. See www.google.com and search for "Federal Pacific" for additional and up-to-date information.

Aluminum wiring in general lighting circuits has a history of overheating, with the potential of a fire. If this type of wiring exists, a licensed electrical contractor should examine the whole system.

Arc Faults

In some areas, arc faults are required in new homes, starting in 2002. These control outlets in the bedrooms.

Reverse Polarity

A common problem that surfaces in many homes is reverse polarity. This is a potentially hazardous situation in which the hot and neutral wires of a circuit are reversed at the outlet, thereby allowing the appliance to incorrectly be connected. This is an inexpensive item to correct.

Each receptacle has a brass and silver screw. The black wire should be wired to the brass screw and the white wire should go to the silver screw. When these wires are switched, this is called "reverse polarity". Turning off the power and switching these wires will correct the problem.

Main service wiring for housing is typically 240 volts. The minimum capacity for newer homes is 100 amps, though many older homes still have 60 amp service. Larger homes or all electric homes will likely have a 200 amp service.

Main service wiring may be protected by one or more circuit breakers or fuses. While most areas allow up to six main turnoffs, expanding from these panels is generally not allowed.

Cooling

Testing A/C System and Heat Pump - The circuit breakers to A/C should be on for a minimum of 24 hours and the outside temperature at least 15 ° C for the past 24 hours or an A/C system cannot be operated without possible damage to the compressor. Check the instructions in your A/C manual or on the outside compressor before starting up in the summer. Heat pump can only be tested in the mode it's running in. Outside temperature should be at least 15 ° C for the past 24 hours to run in cooling mode.

Temperature differential, between 7°-15°, is usually acceptable. If out of this range, have an HVAC contractor examine it. It is not always feasible to do a differential test due to high humidity, low outside temperature, etc.